

MACHINERY

JUNE 13, 1958

ONE SHILLING & THREEPENCE



HYDRAULIC 2 ft 6 in x 2 ft 6 in OPENSIDE PLANER

with *STROKE*
6 ft or 8 ft

Maximum Stroke 6 ft or 8 ft

Work Capacity 30 in. Wide x 30 in. High
under Cross-Slide

15 h.p. Self-Contained Drive


Hydraulic Tool Relief

Cutting Speeds, Low, 20 to 60 ft/min

Cutting Speeds, High, 68 to 120 ft/min

Return Speeds 36 to 136 ft/min

Feeds (10 Rates) 0.02 in. to 0.20 in/min



The **BUTLER MACHINE TOOL CO. LTD.**
HALIFAX **TELEPHONE 61641** **ENGLAND**

PLANERS
SHAPERS
SLOTTERS



MACHINERY
JUNE 13, 1958

"Speetol"
Reg'd



MAGNETIC GRIPPER

Solves a Pressing Problem!

IT'S HELD

IT'S RELEASED

Enables ferrous parts to be fed to power presses faster and safer ... so increases output without risk to operator. Design (Patent 738193) incorporates a special permanent magnet of high lifting power and instantaneous cut-off is provided by thumb pressure on the convenient trigger.

Simple yet Efficient

Speed Tools Ltd
VEREKER BUILDINGS, GRESSE ST., LONDON W.1. Museum 1039/1099.


**very
large**
. . . jigs and fixtures

Our Machine Shops are laid out for
EXPERIMENTAL MACHINING
DEVELOPMENT WORK
PRODUCTION—
LONG OR SHORT RUNS
AUTOMATION AND SPECIAL
PURPOSE MACHINERY

We can work to the finest limits on the **FINEST MACHINE TOOLS**


LEYTONSTONE JIG & TOOL CO. LTD. LEYTOOL WORKS, HIGH ROAD, LEYTON, LONDON, E.10

Telephone: LEYtonstone 5022-3-4



Fully A.I.D. approved
Ref. No. 793672/38


"Our heat-treatment? Wild-Barfield furnaces of course"



Where heat-treatment is concerned—are you doing the job as economically as possible?

It's surprising the number of people who invest in expensive machine tools—and then spoil a good job in outdated furnaces.

And the result? Rejects—time, money and probably customer goodwill lost. More and more people are relying on Wild-Barfield equipment. Write for full details of the Wild-Barfield range and see how you can save by changing to modern, electric furnaces.



*Horizontal General
Purpose Furnace HW.1.*



FOR ALL HEAT-TREATMENT PURPOSES

WILD-BARFIELD ELECTRIC FURNACES LIMITED

ELECURN WORKS, OTTERSPOOL WAY, WATFORD BY-PASS, WATFORD, HERTS. Phone: Watford 6091 (8 lines) Grams: Elecurn, Watford

W373

When answering advertisements kindly mention MACHINERY.

GHA

*For two- and three
dimensional
reproduction*



**PRESENT DELIVERY
DIESINKING
MACHINES—
EX STOCK**

GEORGE H. ALEXANDER MACHINERY LTD.

82-84 COLESHILL STREET · BIRMINGHAM · 4

PHONE : ASTON CROSS 3264 (7 LINES)

GRAMS : · VIKING, · BIRMINGHAM

When answering advertisements kindly mention MACHINERY.

ROSA

CAP.
0"— $\frac{1}{8}$ "

T-Slotted
Table,
6" x 6".

Screw
Feed to
Rise & Fall
3,000—18,000 r.p.m.
Optical Glass




★
MODEL
3/1
Stock
Delivery

HIGH
PRECISION


★ **WORLD FAMOUS. MADE BY MANUFACTURERS OF 50 YEARS' EXPERIENCE**
SOLE CONCESSIONAIRES

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BALham 8551 (5 lines)



Send for list of full range. Trade supplied.

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BALham 8551 (5 lines)
FOREIGN **SOLE CONCESSIONAIRES.**



★
BRITISH
MADE
★
REGISTRATION
N° 883106

★ **MAGNETIC** ★

MICROTEST
PRECISION MAGNETIC VEE BLOCKS

★ **WORLD RENOWNED** ★
FOR TOOLROOM • OR PRODUCTION
MADE OF TOUGHENED STEEL, HARDENED AND
GROUND ENSURING CONTINUED ACCURACY
NOT TO BE COMPARED WITH CHEAPER
NON-HARDENED TYPES ON THE MARKET
Microtest Vee Blocks are in a class apart


W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BALham 8551 (5 lines)




SEND FOR LIST OF FULL RANGE
Trade Supplied.

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BALham 8551 (5 lines)

AT CANADIAN PRATT AND WHITNEY AIRCRAFT


ALMCO

barrel finishing SAVES 97% on deburring and finishing of spark plug bushings


● SAVES 9d. ON EACH BUSHING

—Deburring and finishing threaded spark plug bushings like the one shown at the left, formerly cost £37.4.0 per thousand when CP & W used speed lathes, portable power tools and other hand methods.

After installing two ALMCO DB-200 Supersheen units, records showed a cost cut of 97%. This equipment turns out 1,000 bushings in 45 minutes, releases grinders and finishers to other duties. Cost reports showed:

£37.4.0	cost per thousand with power tools.
£ 1.1.0	cost per thousand with 2 ALMCO barrels.
£36.3.0	Savings per thousand pieces.

This year CP & W will process 24,000 spark plug bushings, with a total savings of £867.10.0 on this one part alone.

PRACTICALLY ELIMINATES REJECTS—Before installing controlled-type barrel finishing, parts inspectors returned for re-work an average of 125 bushings out of every 1,000 (12½%). With Almco Supersheen equipment and processes, these parts are now finished to a degree of uniformity that is virtually free of rejects.


CUTS DEBURRING AND FINISHING COSTS £867.10.0

—Threaded spark plug bushings used in famous Pratt & Whitney aircraft engines will be deburred and finished for £867.10.0 less this year with Almco equipment and processes. Maurice Harrison, Supervisor of Process Planning, shows the small part on which this saving will be made.

DESIGNED FOR MANY METAL FINISHING OPERATIONS—In addition to deburring and finishing, ALMCO equipment and processes are used for descaling, degreasing, grinding, burnishing, work-hardening, rust-inhibiting, polishing, etc.

ALMCO SUPERSHEEN materials, equipment and processes have been developed by engineers and technicians fully trained in all the intricate variables of modern barrel finishing applications.

FREE SAMPLE PROCESSING. ALMCO has ample facilities for running sample parts. Send sample components, with your specifications to our Process Laboratory, your enquiry will be handled promptly. You'll get a complete report on where you can save deburring and finishing costs, improve product quality and appearance, the method and machine best suited for your operation. **GET THE FACTS TO-DAY.**




Two Model DB-200 Almco machines, using Supersheen bonded abrasive chips and compounds, deburr and polish 1,000 spark plug bushings in 45 minutes at Canadian Pratt and Whitney.

ALMCO Supersheen
BURY MEAD WORKS · HITCHIN · HERTS
Telephone: Hitchin 3669

HOLLAND (Rotterdam) N.V. Technische Handelsonderneming "Carborundum-Aloxite" ; **BELGIUM & LUXEMBURG** (Bruxelles) Technimetal Societe Anonyme ; **SWEDEN** (Stockholm) Trumlingsaktiebolaget ; **SWITZERLAND** (St. Gallen) L. Kellenberger & Co. ; **SOUTH AFRICA** (Johannesburg) Barry Colne & Co. (Pty.) Ltd. ; **AUSTRALIA & NEW ZEALAND** (Melbourne) Hardie Trading Ltd.

When answering advertisements kindly mention **MACHINERY**.



how a GROMMET V-BELT works

A BTR High Test Grommet V-belt drives heavier loads with a higher safety factor because it's stronger; transmits more power for electricity consumed because it's more flexible; lasts longer because it's more durable, size for size, than any other V-belt. 'Grommetise' your drives with BTR High Test Grommet V-belts, especially where conditions are punishing—the more difficult the drive the more outstanding you'll find BTR High Test Grommet V-belt performance.

- A grommet (a cord loop built by winding high-tensile rayon cord upon itself in an endless spiral) is essentially strong and flexible.
- Grommet spiral construction ensures that all the windings share the load and stresses equally.
- Two identical matched grommets symmetrically positioned in the belt share the load equally.
- The grommets are on the neutral axis of the belt and largely unaffected by flexing stresses as the belt travels round the pulleys.
- Grommet construction makes room for extra rubber to absorb shock loads and protect the grommets from unfavourable conditions.



BTR HIGH TEST GROMMET V-BELTS

Patented in Britain by BTR Patent No. 567406


BTR Industries Ltd

BRITISH THERMOPLASTICS & RUBBER MANUFACTURERS

Herga House, Vincent Square, London S.W.1 Telephone: VIctoria 3848

D.1249

When answering advertisements kindly mention MACHINERY.



1400

Milled complete in one hour -



1600

on the NEW
AHCOL**ROTAMILL**



Semi-Automatic

ROTARY MILLING MACHINE

With Automatic Work-Clamping and continuous cycle, the $\frac{1}{2}$ " x $\frac{1}{2}$ " slots and end faces of these components, in brass, were gang milled at 1,400 and 1,600 pieces per hour—typical of the impressive times being regularly recorded on this amazing machine.

Write for our illustrated Catalogue now—or better still, send drawings or samples and let us submit proposals for your own components.

SOLE WORLD DISTRIBUTORS

**DOWDING & DOLL LTD**

346 KENSINGTON HIGH STREET, LONDON, W.14


Telephone: WESTERN 8877 (8 lines)

Telegrams: ACCURATOOL HAMMER LONDON

110

When answering advertisements kindly mention **MACHINERY**.


***SPEED UP* your 2nd Opⁿ work...**




with the *NEW* ACCURATOOL SECOND OPERATION LATHE




Compound
Slide



Drilling and
Boring
Tailstock



Thread Chasing
Attachment



With 4' turning length and lever operated compound slide swivelling up to 45° for taper turning, this machine is unusually sensitive and versatile. Work up to nearly 3" dia. can be handled. The collet is lever operated (air operated collet extra) and the drilling and boring tailstock is provided with drill extractor. Eight spindle speeds 75-3000 r.p.m. or alternative higher speeds are available, a single lever selecting High or Low speeds, both Forward and Reverse. Many useful items of equipment are available, such as thread chasing, and alternative methods of work holding.

Write now for the New Accurtool Catalogue.


SOLE WORLD DISTRIBUTORS:

DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W. 14


Telephone: WESTERN 8077 (8 lines)

Telegrams: ACCURATOOL HAMMER LONDON



When answering advertisements kindly mention MACHINERY.

TWIST DRILLS



For
LONG LIFE
at
MAXIMUM
PENETRATION RATES

High Speed Steel Drills in a wide range
of sizes and types to suit all requirements.

Agents and Stockists for Intal Drills.

Richard Lloyd Limited

GALTON HOUSE, ELMFIELD AVENUE, TYBURN, BIRMINGHAM, 24

Telephone: ASHfield 1801 Telegrams: "Cogs, Birmingham" Telex No. 33366


When answering advertisements kindly mention **MACHINERY**.

F/1/2.

Ward for
Maximum Production

**CAPSTAN and TURRET
LATHES**

Capacities up to 35 in. swing over bed
and 8½ in. dia. hole
through spindle.



H·W·WARD & CO
LTD

SELY OAK
BIRMINGHAM 29
TELEPHONE SELLY OAK 1131



54.75" (52 min.)

37.875" (32 min.)

16.06" (9 min.)

24.625" (19 min.)

43.25" (73 min.)

2.5" (13 min.)

TYPICAL PROFILING
FLOOR TO FLOOR TIMES

model J 6
Unitrace Profiling
Lathe




LANG

PROFILING + TURNING BORING SURFACING + STANDARD SLIDING SURFACING & SCREWCUTTING LATHE ALL IN ONE MACHINE


LONDON OFFICE
ASSOCIATED BRITISH MACHINE
TOOL MAKERS LIMITED
17 GROSVENOR GARDENS SW1

JOHN LANG & SONS LTD.
JOHNSTONE RENFREWSHIRE SCOTLAND
Telephone: Johnstone 400 Telegrams: "Lang Johnstone"



*precision
grinding
with ---*



**The ideal machine for FACE,
CYLINDRICAL, INTERNAL
SURFACE, TOOL AND
CUTTER grinding.**



--- KELLENBERGER *universal grinders*

Features include adjustable table for taper grinding; wheelhead and workhead with 360° swivel. Six rates of automatic table traverse. Automatic in-feed to wheelhead.

Three sizes 29½", 46½" and 59" between centres.



Kellenberger also offer a Tool and Cutter Grinder with 30½" or 36½" between centres.

Full details from sole agents:—

ALFRED

HERBERT

LTD. COVENTRY

Factored Division, Red Lane Works.




AD432




PATENTS
PENDING

POWA-LASTIK




Pedestal Models
12" or 14"
Wheels



ABRASIVE WHEEL CUT-OFF MACHINES

Designed for fast, smooth cutting of all TYPES and SHAPES, hard or soft materials, in a FEW SECONDS. Spring-loaded clamp holds work securely, leaving operator's hands free for control. Vee block adjustable for mitre cutting. Totally enclosed drive.




Bench Models
10" Wheel or
Saw

MACHINE TOOL DRIVING UNITS

Provides a speedy, simple and efficient conversion of existing machines at low cost. Four models (Minor, Major, Monarch and Mammoth) cover a wide range of application.

New gear drive unit features the four-speed constant-mesh gearbox with convenient change lever enabling quick selection of speeds.



POWA-LASTIK
applicable to
horizontal
milling machine



Gear Drive
Unit Model G.1

Further details gladly supplied
on application to Dept. M.

CONCESSIONAIRES:

SMITH BROS & WEBB LTD



STRATFORD ROAD, BIRMINGHAM, 11, ENGLAND

Telegrams "Powalastik, Birmingham"

Telephone VICTORIA 2714

London Office: 64 CHANDOS COURT, BUCKINGHAM GATE S.W.1. Telephone ABBEY 6937/8

When answering advertisements kindly mention **MACHINERY**.

**10 TON MODEL**

3 speed ranges from 75 to 500 strokes per minute—
5 h.p. variable speed motor
—maximum stock width
5" x 3/32" thick.




High Speed DIEING PRESSES

50 TON MODEL

4 speed ranges from 45 to 300 strokes per minute—12 h.p. variable speed motor—maximum stock width 12 1/2" x 3/16" thick.

100 TON MODEL

2 speed ranges from 50 to 200 strokes per minute—30 h.p. motor—maximum stock width 15" x 1/4" thick.

**25 TON MODEL**

4 speed ranges from 60 to 600 strokes per minute—
7 1/2 h.p. variable speed motor
—maximum stock width
6 1/2" x 1/8" thick.

Power with a Punch!

E.H. JONES
(MACHINE TOOLS) LTD

You will obtain **MORE COMPONENTS**
PER HOUR PER SQUARE FOOT OF
FLOOR AREA from C.V.A. Dieing
Presses.

GARANTOOLS HOUSE
PORTLAND ROAD, HOVE, SUSSEX

Telephone: HOVE 47253 Telegrams: Garantools, Portslade

LONDON • BIRMINGHAM • EDINBURGH • MANCHESTER • BRISTOL

NRP


When answering advertisements kindly mention **MACHINERY**.

*Designers, Methods Engineers
and Works Managers ...*

CLAIM

CASTINGS BY PRECISION METHODS REALLY CUT COSTS

CASE N° 1



Old Method



*Precision
Casting*



*Finished
Component*

WEIGHT OF BAR : 7 lbs

WEIGHT OF CASTING : 1½ lbs

PREVIOUS METAL

WASTAGE : 410%

BAR MACHINING TIME : 100%

CASTING MACHINING TIME : 22%

PREVIOUS

TIME WASTAGE : 350%

** Remember these advantages*

- (1) WASTED MACHINING MINIMISED.
- (2) STOPPAGE TIME ON MACHINE TOOLS GREATLY REDUCED.
- (3) EASIER SWarf HANDLING.
- (4) PRODUCTION EXPEDITED.
- (5) CLEAN FINISH OF CASTINGS.

SAMUEL OSBORN & CO., LIMITED

When answering advertisements kindly mention MACHINERY.

... You cannot afford to miss these facts!

PROOF

TWO FACTUAL CASE HISTORIES



Precision
Casting

WEIGHT OF BAR : 4 lbs
WEIGHT OF CASTING : 1½ lbs

PREVIOUS METAL
WASTAGE : 220%

BAR MACHINING TIME : 100%
CASTING MACHINING TIME : 67%(max)

PREVIOUS
TIME WASTAGE : 50%(min)



Finished
Component

CASE N°2

*Write
Now!*

Send for literature and advice on how you may drastically reduce production costs, by using 'SOCAST' steel castings. These close tolerance castings are made by the Shell Moulding, Osborn Shaw and

Osborn CO₂ Block processes, in stainless, acid heat-resisting and most alloy steels.


OSBORN

**'SOCAST'
STEEL CASTINGS**

CLYDE STEEL WORKS, SHEFFIELD

When answering advertisements kindly mention MACHINERY.

AJAX *high speed* FORGING PRESSES



**INTEGRAL SOLID
STEEL FRAME**

**DIRECT ACTING
AIR CLUTCH**

BUILT IN 13 SIZES

**CAPACITIES
FROM 300 TO 8000
TONS**

**LET US
DEMONSTRATE
TO YOU**

Sole agents for the range of Ajax Forging Machinery

**VAUGHAN
ASSOCIATES LIMITED**

4 Queen Street, Curzon Street, London, W.1

Telephone: GROSVENOR 8362-5

Midland Office and Demonstration Room:

WILFORD CRES., NOTTINGHAM. Tel.: Nott. 88008

NRP

When answering advertisements kindly mention MACHINERY.

The SEAL makes it possible

The Joy Limberoller flexible conveyor idler is an ingenious device which considerably simplifies the construction and maintenance of conveyors. Its striking difference from the ordinary conveyor idler lies in its flexible 'spindle', this consists of a stranded steel cable with swaged-on steel end-pieces. Neoprene discs, picked out in orange on the illustrations for clearness, are bonded to the cable at suitable spacings in such a way as to be virtually integral with it, and the neoprene is continued between the discs so as to protect the cable.

The steel fittings at the shaft ends are carried in two-row deep-groove FBC bearings, with a neoprene seal. This seal has proved to be effective in excluding dirt and in retaining the lubricant. Thus, two bearings take the place of the usual six.

As will be seen from the illustration, the steel cable hangs in a natural catenary and thereby imposes not only the radial loading directly due to the weight on the conveyor, but combines with it a simultaneous end-thrust. The bearings—made to the requirements of Joy-Sullivan Ltd., by whose courtesy we reproduce these photographs—are formed with recesses in the housing, permitting instant changing of an idler assembly without the use of tools.

FISCHER BEARINGS COMPANY LTD., WOLVERHAMPTON


Fischer Bearings Co. Ltd., & Timken-Fischer Stockists Ltd., Birmingham, are both subsidiaries of British Timken Ltd.



ALL BRITISH
BALL AND
PARALLEL-ROLLER
BEARINGS



AJAX *high speed* FORGING PRESSES



**INTEGRAL SOLID
STEEL FRAME**

**DIRECT ACTING
AIR CLUTCH**

BUILT IN 13 SIZES

**CAPACITIES
FROM 300 TO 8000
TONS**

**LET US
DEMONSTRATE
TO YOU**

Sole agents for the range of Ajax Forging Machinery

**VAUGHAN
ASSOCIATES LIMITED**

4 Queen Street, Curzon Street, London, W.1

Telephone: GROSVENOR 8362-5

Midland Office and Demonstration Room:

WILFORD CRES., NOTTINGHAM. Tel.: Nott. 88008

NRP

When answering advertisements kindly mention MACHINERY.

The SEAL makes it possible

The Joy Limberoller flexible conveyor idler is an ingenious device which considerably simplifies the construction and maintenance of conveyors. Its striking difference from the ordinary conveyor idler lies in its flexible 'spindle', this consists of a stranded steel cable with swaged-on steel end-pieces. Neoprene discs, picked out in orange on the illustrations for clearness, are bonded to the cable at suitable spacings in such a way as to be virtually integral with it, and the neoprene is continued between the discs so as to protect the cable.

The steel fittings at the shaft ends are carried in two-row deep-groove FBC bearings, with a neoprene seal. This seal has proved to be effective in excluding dirt and in retaining the lubricant. Thus, two bearings take the place of the usual six.


As will be seen from the illustration, the steel cable hangs in a natural catenary and thereby imposes not only the radial loading directly due to the weight on the conveyor, but combines with it a simultaneous end-thrust. The bearings—made to the requirements of Joy-Sullivan Ltd., by whose courtesy we reproduce these photographs—are formed with recesses in the housing, permitting instant changing of an idler assembly without the use of tools.

FISCHER BEARINGS COMPANY LTD., WOLVERHAMPTON

Fischer Bearings Co. Ltd., & Timken-Fischer Stockists Ltd., Birmingham, are both subsidiaries of British Timken Ltd.



ALL BRITISH
BALL AND
PARALLEL-ROLLER
BEARINGS



WICKMAN S-L-A-S-H

EXPANSION REAMER PRICES

The benefit of our lower production cost is yours.

The considerable demand for Wimet Expansion Reamers has resulted in the introduction of new manufacturing methods. These have led to lower costs which are now being passed to you in the form of lower prices.

Wimet tipped tools already possess a life many times greater than ordinary tools and in the Expansion Reamer this is multiplied many times over by the ability to expand it and regrind to size.

Delivery of all commonly used sizes can be made from stock. Please write or 'phone your enquiries.

Wimet

EXPANSION REAMERS



PRICES

SIZE	Finished Reamers	* Blanks for sizing
	B.S.I. Limits	Grinding Allowance on Nominal +0.030"/0.040"
1/8" to 1/2" (0.0005"/0.001")	64/3	47/9
5/8" to 1" (0.0004"/0.0008")	76/-	58/-
1 1/8" to 2" (0.0005"/0.001")	84/-	64/6
2 1/2" to 3" (0.0005"/0.001")	89/3	68/3

* Blanks for sizing are finished in all respects but left with grinding allowance for circular grinding and backing-off by customer.

WICKMAN S-L-A-S-H LIMITED

WIMET DIVISION, TORRINGTON AVENUE, COVENTRY

Telephone: Tilt Hill 66621


510 ST

When answering advertisements kindly mention MACHINERY.



For Accuracy

THE ABWOOD UNIVERSAL COMPOUND ANGLE TABLE




Universal table fitted with interchangeable rectangular table. Changeover from circular to rectangular table is readily effected by loosening clamping bolts.



Movements in the table are fully indexed through 360° in the horizontal plane and 90° in the vertical, so that any combination of angles may be obtained. 'T' slots in the table are machined from the solid and a hole is bored centrally and fitted with a steel sleeve for receiving spigots. Available in two sizes, circular 6in. and 8in. diameter, rectangular 8in. by 6in. and 10in. by 8in.

ABWOOD MACHINE TOOLS LTD. PRINCES ROAD, DARTFORD, KENT

Telephone : Dartford 5271 (5 lines)



Telegrams: ABWOOD DARTFORD

CT-1

When answering advertisements kindly mention MACHINERY.



HYDRAULICS FOR MACHINE TOOLS

We at Keelavite are a team of experts in the design, installation and maintenance of complete hydraulic systems. We are ready to accept full responsibility for the proper working of all our installations, including all electrical or other control equipment.

Not only this, we are the manufacturers of the largest range of hydraulic units in the United Kingdom.

We are, of course, fully experienced in special applications of hydraulic power for the machine tool industry.

KEELAVITE

Hydraulics

MACHINE TOOL DIVISION

THE RECOGNISED AUTHORITY

KEELAVITE ROTARY PUMPS & MOTORS LTD.

ALLESLEY, COVENTRY

Telephone: Meriden 441

When answering advertisements kindly mention MACHINERY.

WIN *half the battle* **BEFORE** *you start!*

**PRECISION GROUND
STEEL & BRASS ROD**
*Aids machining
& assembly!*



SIZES FROM $\frac{1}{16}$ in. TO 1 in. DIAMETER SUPPLIED TO LIMITS OF ± 0.00025 in. SIZES ABOVE 1 in. TO 3 in. DIAMETER SUPPLIED TO LIMITS OF ± 0.0005 in. LENGTHS FROM 6 ft. TO 30 ft. ALL WITH FLAWLESS SURFACE FINISH.

PRATT, LEVICK & CO. LTD.

CHESTER • ENGLAND

TELEPHONE: CHESTER 22265/6

When answering advertisements kindly mention MACHINERY.



You should have heard the boffins on that controversial subject the other day. Old boffin Sid for example.

He was saying that titanium satellites and nimonic space ships were fair game for SKY-ACKY welding.


"After all," he said, "saucepans, cages, bicycles, motor cars, missiles and aeroplanes are all SKY-ACKY welded."

"You mean SHE-ICKY welded" squeaked boffin Emanuel. Then all the other boffins joined in: "SHE-ACKY," "SKY-ICKY," "SHI-ARKY," "SKEE-ICKY."

I myself pronounce it *SEE-ACKY*, which is, perhaps, how any self-respecting boffin would pronounce it.

SCIAYK ELECTRIC WELDING MACHINES LIMITED, FALMOUTH ROAD, SLOUGH, BUCKS, ENGLAND. TEL: SLOUGH 25551 (10 LINES) CABLES: SCIAYKWELD, SLOUGH
Paris Chicago London Birmingham Manchester Christchurch (N. Zealand) Calcutta Johannesburg Capetown Kuala Lumpur Bombay Bangalore Karachi

When answering advertisements kindly mention MACHINERY.




..... auxiliary feed change in apron

ON 26" and 30" SWING LATHES

Rotation of finger knob on
end of apron gives 4 changes
to normal feed rate from
operators position

Ratios: $1\frac{1}{2}$ -1, 1-1, 3-4 & 1-2



DESCRIPTIVE LITERATURE SENT ON REQUEST

Dean Smith & Grace
KEIGHLEY LIMITED

TELEX NO. 51-123 • TELEGRAMS: LATHES KEIGHLEY TELEX • TEL. NO. 5261 (7 LINES)

When answering advertisements kindly mention MACHINERY.



MACHINERY

FOR GREATEST GRIPPING POWER
AT THE BUSINESS END

Jacobs

British-made genuine JACOBS chucks are well maintaining the high reputation of precision, gripping-power, speedy operation and long life that has won world-wide fame for the JACOBS name. Your usual merchant is in a position to supply, and we recommend you to get in touch with him.



JACOBS CHUCKS ARE STANDARD EQUIPMENT
WITH THE MAJORITY OF PORTABLE TOOLMAKERS

THE JACOBS MANUFACTURING CO. LTD.
MILLHOUSES SHEFFIELD

IF IT'S A
JACOBS
IT HOLDS

SUPPLY THE WORLD OVER



No. 16 UNIVERSAL THREAD GRINDING MACHINE

the
authority
on
MACHINE TOOLS

•
PRECISION
MEASURING
INSTRUMENTS
& GAUGES

•
PRECISION
ENGINEERING
EQUIPMENT



No. 61 GEAR GRINDING MACHINE




Coventry Gauge

& TOOL COMPANY LTD

P.O. BOX 21, COVENTRY, GL. BRITAIN



Be Wise Slaterize!



DIE-HEADS & CHASERS


Tangential
**SCREWING
EQUIPMENT**
specialists

SLATER (TANGENT) LTD

HALESOWEN RD., QUINTON, BIRMINGHAM, ENGLAND

Telephone: WOODgate 2264-5

When answering advertisements kindly mention MACHINERY.



Photograph by permission of The Ford Motor Company Ltd.

You'll find RYDERMATICS at Fords—

MACHINING TRACTOR CLUTCH PLATES

The vertical design of Rydermatics gives rigidity, easy loading and accessible tooling; the simple tooling system allows easy changeover for a variety of work. Swarf disposal is via a gravity chute away from the operator. Combined with pneumatic chucking and automatic cycle, these are the features that result in . . . PRODUCTION.



Thomas Ryder & Son Limited, Turner Bridge Works, Bolton, England.
Makers also of Verticalautos and Piston Ring Lathes.

When answering advertisements kindly mention MACHINERY.

June 13, 1958
NO. 75

Let us "HANDLE" your machines

NO. 54

NO. 55

NO. 1




NO. 91

NO. 3




NO. 67

NO. 4




NO. 33





NO. 82



NO. 58



NO. 80



The above display is a small selection from our range of 104 shapes and sizes of standard handles and 10 sizes of handwheels in both dished and flat type.

Why add to your costs by making special form tools? This is our special service in BALL HAND AND HANDWHEELS. Handles and moulded knobs too! They not only save time but also reduce production costs.

WM. WHITELEY & SONS, LTD. incorporating J. CHARLESWORTH
(MACHINE TOOL DIVISION) PROSPECT IRONWORKS, LOCKWOOD, HUDDERSFIELD, YORKS.

Telegrams: Drying, Huddersfield

Telephone: Huddersfield 4410/11

makers of Machine Components since 1854



A Multi Station Indexing Machine producing Differential Pinions of the Massey-Ferguson 35 Tractor at a production time of one set of four per 100 seconds.

Photo by courtesy of
The Standard Motor Co. Ltd



The latest techniques in
mass production...



FIRTH BROWN


...demand
the latest techniques
in steel making

ALLOY STEELMAKERS • FORGEMASTERS • STEEL FOUNDERS • HEAVY ENGINEERS
THOS FIRTH & JOHN BROWN LIMITED SHEFFIELD ENGLAND

When answering advertisements kindly mention MACHINERY.

RAYBROOK

HONING STONES
AND MANDRELS



A COMPLETE RANGE
TO SUIT ALL MACHINES
BRITISH AND AMERICAN

ORDERS DESPATCHED
WITHIN 24 HOURS

RAYBROOK PRECISION HONING CO LTD
DURKAR LOW LANE, WAKEFIELD, YORKSHIRE
TEL: WAKEFIELD 2665

SOUTHERN AGENT: G. E. SUMMERSBY, 55 SIDMOUTH STREET, GRAYS INN ROAD, LONDON, W.C.1.

Milnes

VERTICAL MILLING MACHINES


- ★ SWIVELLING HEAD
- ★ POWER DOWN FEED TO SPINDLE
- ★ GAUGE BLOCK MEASURING EQUIPMENT FOR ACCURATE POSITIONING WHEN BORING
- ★ PRECISE · VERSATILE · ROBUST

With its wide range of movements, gauge block measuring equipment, ample power and robust construction, this machine is capable of precise and rapid production on a wide range of work.


NOTE THESE FEATURES

- Spindle hardened and ground on Timken precision roller bearings.
- Head with power down feed, can be swivelled through 360 deg.
- Table feed, automatic 18in.
- Cross feed 6½in., vertical 14½in., both hand.
- Spindle to table 15in.
- Spindle speeds 50 to 1,000 r.p.m.
- Table working surface 30in. by 8½in.


EARLY DELIVERY



ANGULAR DRILLING



ANGULAR END MILLING



BORING

HENRY MILNES LTD., INGLEBY WORKS, ROSSE STREET, BRADFORD, 8, YORKS

ESTABLISHED 1858

TELEPHONE : BRADFORD 41301

When answering advertisements kindly mention MACHINERY.



FeMPAwELD

SUPER COBALT & 'TRIPLE 5C' BUTT WELDED LATHE & PLANER TOOLS

These butt-welded super cobalt, high speed steel tools are available in a full range, 53 standard shapes and sizes, from $\frac{1}{2}$ in. square up to 2 in. by $1\frac{1}{2}$ in. The highest possible quality is assured by scientific heat treatment in a modern automatic plant. All tools are supplied ground on the face.

Illustrated Leaflets available on request.

HEAD OFFICE

F. M. PARKIN (SHEFFIELD) LTD.
ST. THOMAS [STEELWORKS]
SHEFFIELD, 8, ENGLAND

Telephone : 50083 (5 lines) 'grams: Sorbitic, Sheffield. 8

OFFICES and WAREHOUSES
Chapel Street, Booth Street, Handsworth, Birmingham.,
and Red Lion Market, Finsbury, London, E.C.1.

AGENTS and REPRESENTATIVES


LONDON AREA: W. J. PERCY, 143, Cambridge Road, Seven Kings, Ilford, Essex.

SCOTLAND AND NORTHERN IRELAND: W. C. WILLIS & CO., LTD., 172-4, West Regent Street, Glasgow, C.2.

MANCHESTER AND NORTH OF ENGLAND: S. H. JACKSON & SMITH LIMITED, 21b, Station Road, Cheadle Hulme, Stockport.

EASTERN AND EAST MIDLANDS: G. H. CHURCHWARD LTD., Cookhill, Near Alcester

SOUTH-WEST OF ENGLAND & S. WALES: F. H. NOEL PIKE 27, Hill View, Henleaze, Bristol. Tel. No. Bristol 62-5420



ALSO SUPPLIED

boxed in sets of one dozen
in 18% tungsten or cobalt high speed
steel. Special tools available at short
notice to customers'
drawings.



When answering advertisements kindly mention MACHINERY.

the
EXCEL

3/12

Has a

*** COOL HEAD**

for

*"Superfine
finish!"*

*** Standard machine features MIST and gusher coolant. Both systems can be used together or independently.**



- Capacity 24" x 8"
- 12" dia. wheel.
- Hydraulic longitudinal table traverse—variable 0—90 ft. per min.
- Maximum distance table to wheel—11".
- Built-in diamond dresser. (Extra.)
- Fully automatic operation.
- Simplicity of control.

** Grind the
EXCEL way—Always!*

PLEASE WRITE FOR 44-PAGE MACHINE TOOL CATALOGUE

Manufactured by:

B. ELLIOTT (MACHINERY) LTD

MEMBER OF THE B. ELLIOTT GROUP OF COMPANIES

Victoria Works, Willesden, London, N.W.10 Tel. ELGar 4050

Overseas Subsidiaries: Canada, U.S.A., Australia, S. Africa





Somebody's running his automatics *Flat Out!*

- so can you with

**ALMINAL W.151
FREE-MACHINING BAR**

The **ALUMINIUM ALLOY**
with all these advantages

1. Special chipping characteristics eliminate swarf jamming.
2. Automatics can operate at maximum speed and feed.
3. Longer tool life—normal angles on tool tips can be used.
4. Lower labour costs—one man can watch several machines.
5. Output dramatically increased.

Write TODAY
for full Technical Details


Southern Forge LTD

MEADFIELD ROAD · LANGLEY · BUCKS

— Telephone: Langley 301 —

**ALUMINIUM AND
ALUMINIUM-ALLOY EXTRUSIONS
TUBES AND FORGINGS**

When answering advertisements kindly mention **MACHINERY**.



30,000 shackles drilled and tapped
per 44 hour week on —

- two **HERBERT** type C
2 spindle Drilling Machines
- two **HERBERT** Flash
Tappers at William Hanke
of Brierley Hill



AD.433

Up to 200 gross of shackles are tapped per
regrind of the Herbert Ground Thread Taps.

ALFRED

HERBERT

LTD., COVENTRY



When answering advertisements kindly mention **MACHINERY**.

c2

LUMSDEN

MODEL 96 LM

SURFACE GRINDERS

Top rates of production are linked with a high order of accuracy when 12 cast steel gear housings for the Jones KL66 crane pass under an 18-piece segmental wheel on this model 96 LM Heavy Duty Surface Grinder. The large diameter table revolves at 8 R.P.M., $\frac{3}{16}$ " of metal is removed and the components are sized to ± 0.002 ".

Whilst the Lumsden model 96LM is designed to tackle just such a job as this, in the most rapid, precise and economical manner possible, a complete range exists, from which to choose a machine ideally suited to your own grinding requirements.

*Close limits
and high Output
on
Differential Housings
for JONES' CRANES*




Manufacturers:
LUMSDEN MACHINE CO., LTD. GATESHEAD

Sole Distributing Agents:
ALFRED HERBERT LTD., COVENTRY

When answering advertisements kindly mention MACHINERY.

Holbrook

STRATFORD LONDON ENGLAND



MODEL "U" No. 17

MODEL "U"

PRECISION TOOL-MAKERS' LATHES

BUILT-IN RELIEVING EQUIPMENT WITH INFINITELY VARIABLE RISE CAM
AND NO CHANGE-OVER REQUIRED FOR ORDINARY TURNING

INFINITELY VARIABLE SPINDLE SPEEDS IN FOUR GROUPS
(NOT ELECTRONIC)


REVERSE TO SPINDLE ON ALL SPEEDS

FULL RANGE OF ADDITIONAL EQUIPMENT, INCLUDING PITCH
VARIATOR, CONSTANT CUTTING SPEED UNIT, ETC., IS AVAILABLE

3 SIZES, NOMINAL SWING 13 - 17 - 21 INCHES

The Finest Lathe in its Class

When answering advertisements kindly mention MACHINERY.



Shardlow *Micrometers*

BRITISH PATENT 637034

FOR ABSOLUTE PRECISION ON
DIRECT READING OF INTERNAL
MEASUREMENTS

COMPLETE RANGE
FROM 0.275 in.
TO 8 INS. DIA.

WRITE FOR DESCRIPTIVE BROCHURE

SHARDLOW MICROMETERS LTD.
PETRE STREET, SHEFFIELD, 4
TELEPHONE, SHEFFIELD 386951/2
TELEGRAMS, "MICROMETERS", SHEFFIELD, 1

When answering advertisements kindly mention MACHINERY.


Over 250 NEW MACHINE TOOLS UNDER POWER

for your inspection


Here in London is a new permanent exhibition of British and Continental machine tools—where you can inspect and compare toolroom, production and special purpose plant at your leisure.

One of Britain's finest displays—every item is 'Elgar-Approved', your guarantee of confidence, in purchase and service.

We invite you to come and see us.



*** 40,000 SQ. FT.
OF BRITISH AND
CONTINENTAL PLANT!**



ELGAR MACHINE TOOL COMPANY LIMITED


172-178 VICTORIA ROAD • ACTON • LONDON W3 • Telephone ACORN 5555

Midlands Showroom: 1075, Kingsbury Road, Birmingham, 24


NRP 1904

When answering advertisements kindly mention MACHINERY.

Set-ups for any number and type of Unit Heads from the small U.H.0. to the larger U.H.4. Milling type head are available in standard equipment.



Single and Double ended BILLET DRILLING MACHINES



Enquiries are invited and if you have a production problem our Design Engineers will gladly collaborate with you.

DESIGNED AND BUILT FROM STANDARD UNIT PARTS

A.M.T. (B'HAM) LTD., Bournbrook, Birmingham. Tel.: Selly Oak 1128/9/20. Grams: 'Amtold' B'ham.

When answering advertisements kindly mention MACHINERY.

For accuracy in operation

THE BESCO Inclinable Power Presses

*Model BA,
Mark II.*

*bring pressure
to bear
with power
to spare*

These machines have all the qualities making them the key to your press shop and they can be supplied **IMMEDIATELY FROM STOCK** or just when you want them.

First, and essentially, they will give you quality in workmanship and accuracy in their operation.

From the foremost medium range on the market, Besco Inclinable Presses, Model BA, Mark II, sizes 18, 19, 20 and 21 (Registered Design No. 841913).

SIZE	Pressure exerted	Adjustable stroke
BA18	10 tons	$\frac{1}{2}$ "—1 $\frac{1}{4}$ "
BA19	18 tons	$\frac{1}{2}$ "—2 $\frac{1}{4}$ "
BA20	28 tons	$\frac{1}{2}$ "—2 $\frac{1}{2}$ "
BA21	40 tons	$\frac{1}{2}$ "—3 $\frac{1}{4}$ "

They give you top capacity with plenty of safety and the adjustable strokes are generous in their range.

Full details from

F. J. Edwards Ltd


Specialists in the manufacture of fine medium presses

Edwards House, 359-361, Euston Rd., London, N.W.1


Telephones: EUSTON 4681 (7 lines) 3771 (4 lines)
Telegrams: Bescotools Norwest London

Lansdowne House, 41, Water Street, Birmingham 3

Telephones: CENTRAL 7606/8
Telegrams: Bescotools Birmingham 3



Remember 1913?



45-year-old William Beardmore veteran

Simple design, slow speeds and adequate cooling ensure high efficiency, whilst constant research and development steadily improve performance.

Put these economical machines to work for you.

IMMEDIATE DELIVERY

"BROOMWADE"


AIR COMPRESSORS & PNEUMATIC TOOLS

Your Best Investment

BROOM & WADE LTD · P.O. BOX No. 7 · HIGH WYCOMBE · ENGLAND

Telephone: High Wycombe 1630 (10 lines)

Telegrams: "Broom," High Wycombe, Telex



Type EH compressor — a modern development of the design supplied to William Beardmore & Co. Ltd. in 1913.

the 1024



Precision

TOOLROOM LATHE

- ★ Swing over bed: 11", between centres 24"
1" capacity collet.
- ★ 12 spindle speeds, 30-2,500 r.p.m.
- ★ Range of threads 4-112 t.p.i.
- ★ American cam lock spindle nose.

FLAME HARDENED BED.



SMART & BROWN (MACHINE TOOLS) LTD.

25 · MANCHESTER SQUARE · LONDON · W · 1

Telephone: Welbeck 794116 Telegrams and Cables: Smartool, Wesdo, London



'OPEN HOUSE' *at Battersea*

Soag Machine Tools Limited cordially invite you to visit their new Battersea Works.

A fine selection of new, reconditioned and used Machine Tools will be on display.

Many will be demonstrated under power.

TUESDAY 17th JUNE to FRIDAY 20th JUNE

MONDAY 23rd JUNE to FRIDAY 27th JUNE

10.30 a.m. to 5.30 p.m.

AT HESTER ROAD LONDON S.W.11

(first turning south of Battersea Bridge)



R.S.V.P. to

SOAG MACHINE TOOLS LIMITED

JUXON STREET, LAMBETH, LONDON, S.E.11

Telephone: Reliance 7201

☐

I will be visiting you at Battersea on

(date)

☐

Please send a map


Signed

Firm or Organisation

Address

When answering advertisements kindly mention MACHINERY.

Adjustable hobbing head can be swivelled round this axis.



Block gauge for setting the length of area of contact.


For more than 30 years

KLINGELNBERG PALLOID SPIRAL BEVEL GEARS

(used in all industries, and especially in the manufacture of transport vehicles.)

The Klingelberg method is the only one producing spiral bevel gears by the use of hobs.

1. Simple maintenance of the very accurately ground hobs, and therefore high and constant accuracy of the gears.
2. Quiet running of the gears even in the case of displacements due to crowning flanks and suitable area of contact.
3. Easy positioning of area of contact with normal hobs by machine setting only and therefore absolute repeatability.
4. Long life through sturdy teeth with even tooth thickness and efficient tooth root radius.
5. Simple calculation and setting of machines and therefore very economical for cutting individual gears and for mass production.
6. Spiral Bevel Gears for intersecting axis and offset axis can be cut on the same machine with the same standard hobs.



W. FERD. KLINGELNBERG SÖHNE-REMSCHIED
GERMANY


For full information please contact our Sole British Agents:
MESSRS. SYKES MACHINE TOOL CO. LTD.
HYTHE WORKS : THE HYTHE : STAINES : MIDDLESEX
Phone: STAINES 5076 (3 lines) Grams: "SYTOOL, STAINES"

"Such satisfactory results
have never been obtained before"
say CUNLIFFE & CROOM of . . .


HARPER CASTINGS

Of this precision dividing-head plate for milling machines Cunliffe & Croom say, "We find that by using Harper Castings we get a plate with a good clean surface and, equally important, consistent hardness. Each casting has to be drilled with about 2,000 small holes which must have a clean edge and a firm wall between the holes which are extremely close together."


Harper quality covers grey iron and Meehanite castings, also metal pressings, machining, enamelling and other finishes and sub-assembly work.



Un-machined casting of dividing-head plate.



Casting machined and drilled.



Left: Finished Casting in position on milling machine.

JOHN HARPER & CO. LTD. JOHN HARPER (MEEHANITE) LTD.
ALBION WORKS Phone: WILLENHALL 124 (5 lines) Grams: HARPERS, WILLENHALL **WILLENHALL**

LONDON OFFICE: SEAFORTH PLACE, 57, BUCKINGHAM GATE, LONDON S.W.1 Tel.: TATE GALLERY 0286



MANCHESTER OFFICE: c/o B. J. Brown & Partners Ltd. 248/9 Royal Exchange, Manchester 2





When answering advertisements kindly mention MACHINERY.

SAFETY

with Instant Access



*In
Wirework
or
Sheet
Metal*



'Harco' Machinery guards are accurately designed to afford complete protection without interfering with the efficient operation of machinery, and are substantially constructed to withstand vibration and rough treatment. Full provision is made for authorised access for maintenance purposes, and all guards fully conform to Factory Act requirements. Ask for List MN996.

'HARCO' MACHINERY GUARDS

Harvey

G. A. HARVEY & CO. (LONDON) LTD.
WOOLWICH ROAD, LONDON, S.E.7


Telephone: GREENWICH 3232 (22 lines)

When answering advertisements kindly mention MACHINERY.

Do the 'hole' job better !

Model 28AN

**Heavy Duty Vertical
Box Column Machine**
2in. Cap in M.S.



Model 21AR

**Light Duty Vertical
Round Column Machine**
1½in. Cap in M.S.

Made in 3 sizes
1½in., 1½in., 2in. capacity


Box and round column

Box column machines
supplied in multiple form

9 spindle speeds

Automatic feed:
3 rates—lighter model
6 rates—heavy model

Adjustable head and table



CORONA

GENERAL PURPOSE DRILLING MACHINES

FRED'K POLLARD & CO. LTD.
CORONA WORKS, LEICESTER, ENGLAND

LONDON OFFICE: COASTAL CHAMBERS, 15 ELIZABETH ST.,
BUCKINGHAM PALACE ROAD, S.W.1 Tel.: SLOane 6880

When answering advertisements kindly mention MACHINERY.

REDUCED PRICES
FOR B.S.D. VENTILATED MOTORS
to B.S. 2960



★ Range covers $\frac{1}{2}$ to 50 h.p.
in 6 frame diameters

★ Class 'E' insulation
to B.S. 2613/1957

For your copy of our stock list, please write to:
The ENGLISH ELECTRIC Co. Ltd., Industrial Motor Works, Bradford


'ENGLISH ELECTRIC'

THE ENGLISH ELECTRIC COMPANY LIMITED, MARCONI HOUSE, STRAND, LONDON, W.C.2
WORKS: STAFFORD • FRESTON • RUGBY • BRADFORD • LIVERPOOL • ACCRINGTON

DM.71B8

When answering advertisements kindly mention MACHINERY.

D



CROWN

SURFACE PLATES AND TABLES. Made from hard close-grained cast iron. Sizes from 6in. by 4in. up to 12ft. 0in. by 6ft. 0in. in Grade "A" and "B" accuracy.

GRANITE SURFACE PLATES AND TABLES. Made from hard close-grained black Swedish granite. Sizes from 8in. by 8in. up to 10ft. 0in. by 5ft. 0in.

SINE TABLES. Simple or Compound Angle types. Supplied with Electro Magnetic, Non-electric Magnetic or "T" slotted work faces. Sizes 8in. by 5in., 10in. by 5in. and 12in. by 8in.

ANGLE PLATES AND BOX ANGLE PLATES. Made from hard close-grained cast iron and rigidly designed for stability. Grade "A" and "B" in all sizes.

STRAIGHT EDGES. Cast Iron Camel Back and "I" Section types from 12in. up to 16ft. 0in.

PARALLELS. Hardened Tool Steel to B.S.S. Grade "A" and "B". Complete in wooden case. Sizes 4in. up to 16in.

MAGNETIC CHUCKS. Made from high permeability steel castings and having exceptional holding power. Sizes from 12in. by 6in. up to 72in. long.

DEMAGNETISERS. Of new design to cope with all demagnetising problems.


LAPPING BLOCKS. Made from hard close-grained cast iron surfaced on top and bottom faces and grooved for lapping. Complete with cover for each face. Sizes 6in. by 4in. up to 12in. circular.

WINDLEY BROS • LTD
CROWN WORKS
CHELMSFORD • ENGLAND
 Telephone CHELMSFORD 2224


When answering advertisements kindly mention MACHINERY.

13, 1958

PILOT WIRE TYPE



for the PRECISION GAUGING
of INSTRUMENT PARTS



RANGE	DOUBLE END COMPLETE		REPLACEMENT ENDS	
	CHROME	STEEL	CHROME	STEEL
.000" - .010"		45/-		20/-
.011" - .020"		40/-		18/-
.021" - .250"	45/-	35/-	20/-	15/-
.250" - .500"	57/-	43/-	26/-	19/-

The lengths of the gauge ends vary with diameter and are from 1½ in. to 1¾ in. long. Because they are parallel the worn front end in the smaller sizes may be cut off and the gauging member ed a little further out of the handle.


Alternatively it can be turned end for end.

PILOT holds at least 50,000 of these high precision gauges in stock for immediate delivery when required.

PILOT PLUG GAUGES

SWALLOW RD., COVENTRY
TEL. 88894

MACHINERY 51
June 13, 1959



**For peak
production**


HARRIS

Standards from stock

JOHN HARRIS TOOLS LTD., WARWICK, phone: 1221 (6 lines

and at LONDON, GLASGOW, BIRMINGHAM

"It Speaks for Itself"



FIXED TABLE
ADJUSTABLE TABLE
INCLINABLE

GEARED
UNGEARED

20 to 315 TONS

Schuler

P

PEARSON & ANKE LTD

1-3 HALE GROVE GARDENS • MILL HILL • LONDON • N.W.7

Telephone: MILL HILL 3232 (P.B.X.)


Telex: 23273

The most modern machine tools for Sheet Metal Working

A wide range of
Open-Fronted Presses
kept in stock

When answering advertisements kindly mention MACHINERY.

Rainbow
D☆




For peak
production

HARRIS

Standards from stock

JOHN HARRIS TOOLS LTD., WARWICK, phone: 1221 (6 lines)
and at LONDON, GLASGOW, BIRMINGHAM

"It Speaks for Itself"



FIXED TABLE
ADJUSTABLE TABLE
INCLINABLE

GEARED
UNGEARED

20 to 315 TONS

Schuler

P

PEARSON & ANKE LTD

1-3 HALE GROVE GARDENS • MILL HILL • LONDON • N.W.7

Telephone: MILL HILL 3232 (P.B.X.)

Telex: 23273

A wide range of
Open-Fronted Presses
kept in stock

The most modern machine tools for Sheet Metal Working

When answering advertisements kindly mention MACHINERY.

Rainbow
D☆



'MY GUY'NOR'...


"Mr. Mac" says "as Steel Specialists our range of steel must cover all the sizes and specifications in demand by industry today!" We strive to meet this challenge, our stock is in excess of 5000 tons covering all sizes, in 25 different specifications.

BETTER TRY "MR. MAC" FIRST, FOR BRIGHT & ALLOY STEELS

Macready's Metal Co. Ltd.


USASPEAD CORNER, PENTONVILLE ROAD, LONDON, N.1
 Telephone: TERminus 7060 (20 lines) Telegrams: Usaspead, London, Telex. Telex No. 22783

When answering advertisements kindly mention MACHINERY.



- Optical adjustment
- Measuring system free from wear
- Pre-selection of adjustments
- Projection optics
- Open-front design
- Automatic locking and releasing of the co-ordinate table and boring head
- Spindle speeds 25—1900 infinitely variable
- Centralized lubrication

**SETTING
ACCURACY
WITHIN 0.0004in.**



SOLE AGENTS FOR GT. BRITAIN

STEDALL MACHINE TOOL CO.

**145-157 ST. JOHN STREET
CLERKENWELL, LONDON, E.C.1**

Telephone: Clerkenwell 1010 Telegram: Lockstone-Smith, London

When answering advertisements kindly mention MACHINERY.

D☆☆

BOX·FORD

means added value

MODEL A

4½"

SCREWCUTTING LATHE



"KNOW YOUR LATHE"

A comprehensive training manual on all aspects of lathe operation. 115 fully illustrated pages packed with information for 6s. 6d.

16 spindle speeds make this precision lathe ideally suitable for toolrooms, workshops, light manufacturing and for apprentice training schools. Versatility is further increased by the wide range of accessories available. An unbeatable machine at

£185




SPECIFICATION

Height of centres ... 4½"
Between centres ... 22" or 28"
Range of speeds ... 40-1300 r.p.m.

LEFT. Six station turret head for bed mounting.

CENTRE. Cut-off slide for use in conjunction with turret head.

RIGHT. Tool Post Grinder.



Send for fully detailed leaflet TODAY


DENFORDS ENGINEERING CO. LTD., HECKMONDWIKE, YORKSHIRE

When answering advertisements kindly mention MACHINERY.



SIEMENS

Electromagnetic Multiple-Plate Clutches



The sound design and outstanding efficiency of our electro-magnetic multi-plate clutches has ensured their wide adoption for machine drives of every type.

Multiple thin magnetic steel plates form an exceptionally compact unit, capable of transmitting very high torques. Operation is unaffected by oil and the clutches are therefore very suitable for gear box operation. No adjustment is necessary, as the clutches will function without an air gap.

TYPICAL APPLICATIONS OF OUR ELECTRO-MAGNETIC MULTI-PLATE CLUTCHES



VERTICAL MILLING MACHINE

The feeds, either forward, rapid traverse or rapid reverse, are changed by means of electro-magnetic multi-plate clutches.



TURRET LATHE

On which spindle speed changes are made through electro-magnetic multi-plate clutches.



VERTICAL TURNING AND BORING MILL

On which the electro-magnetic multi-plate clutch ensures gentle, but firm braking.

SIEMENS - SCHUCKERTWERKE A.G., BERLIN - ERLANGEN

Sole Selling Agents in Great Britain:—**SIEMENS - SCHUCKERT (GREAT BRITAIN) LTD.**
FARADAY WORKS • GREAT WEST ROAD • BRENTFORD • MIDDLESEX

When answering advertisements kindly mention MACHINERY.

*an entirely
automatic machine
for grinding
curvic and zerol face
coupling teeth*

**GLEASON
No 19
CURVIC
COUPLING
GRINDER**

write for descriptive brochure

*an outstanding feature of
this machine is a totally
automatic cycle which produces
completely uniform ground
teeth, either from the solid or
from the rough cut
so that the couplings
are truly interchangeable*


sole agents in the United Kingdom

BUCK & HICKMAN LTD

Head Office: Whitechapel Road, London, E.1.

Machine Tools: Otterspool Way, Watford-by-pass.

Branches: Birmingham · Glasgow · Leeds · Manchester



When answering advertisements kindly mention MACHINERY.

If your needs are pressing . . .

Super C.12 a high carbon high chromium non-distorting air or oil hardening steel containing molybdenum and vanadium, has exceptional resistance to wear.

It is particularly suitable for fine press tools and all blanking and shearing operations requiring the retention of a good edge under highly abrasive conditions. Also ideal for the forming and deep drawing of sheet metal, moulding plastics and abrasive powders, cold extrusion tools, rolls, slitting cutters, thread rolling dies, hobbing tools, gauges, etc.



choose SUPER C.12

Air or Oil Hardening steel

Supplied as rolled or forged bars in round, square and flat sections, also as individually forged rings and blanks.
Data sheet available on request.

Photo by courtesy
of Powers-Samas
Accounting
Machines Ltd.




ENGLISH STEEL ROLLING MILLS CORPORATION

limited

North Street Works, Openshaw, Manchester

A wholly owned subsidiary of English Steel Corporation Ltd., Sheffield

When answering advertisements kindly mention MACHINERY.



THE π BALL

π , we understand from those who know, may be approximated to ten or more places of decimals, viz., 3.1415926536. Hoffmann balls are not guaranteed to be quite so near to absoluteness as that, but they are guaranteed to be within $1/10,000$ " both as to size and sphericity; and what is more important, the variation between any two balls in a bearing is far finer.

And what of surface finish? Hoffmann balls are of incomparably flawless mirror finish. There is nothing piebald about the π ball!




STEEL BALLS

THE LOAD CARRIERS OF THE WORLD-FAMED HOFFMANN BALL BEARINGS

THE HOFFMANN MANUFACTURING COMPANY LTD., CHELMSFORD, ESSEX

When answering advertisements kindly mention MACHINERY.

WHEREVER ACCURACY
is demanded . . .



. . . so are **HARDINGE**
PRECISION LATHES

HARDINGE MACHINE TOOLS LIMITED


(One of the Sheepbridge Group)

Feltham • Middlesex • England

Telephone : Feltham 3221/5 Telegrams : Hardinge, Feltham

OA 3307

When answering advertisements kindly mention MACHINERY.



THE π BALL

π , we understand from those who know, may be approximated to ten or more places of decimals, viz., 3.1415926536. Hoffmann balls are not guaranteed to be quite so near to absoluteness as that, but they are guaranteed to be within $1/10,000$ " both as to size and sphericity; and what is more important, the variation between any two balls in a bearing is far finer.

And what of surface finish? Hoffmann balls are of incomparably flawless mirror finish. There is nothing piebald about the π ball!




STEEL BALLS

THE LOAD CARRIERS OF THE WORLD-FAMED HOFFMANN BALL BEARINGS

THE HOFFMANN MANUFACTURING COMPANY LTD., CHELMSFORD, ESSEX

When answering advertisements kindly mention MACHINERY.

WHEREVER ACCURACY
is demanded . . .



. . . so are **HARDINGE**
PRECISION LATHES

HARDINGE MACHINE TOOLS LIMITED

(One of the Sheepbridge Group)


Feltham • Middlesex • England

Telephone : Feltham 3221/5 Telegrams : Hardinge, Feltham

OA 3307

When answering advertisements kindly mention MACHINERY.

• in the *production*
LONG RUN



**you'll be
glad
you chose
a ...**

UNION

DRILLING MACHINE

$\frac{1}{2}$ " and $\frac{3}{4}$ " capacity models


Send for
fully detailed leaflet TO-DAY!

**T. S. HARRISON & SONS LTD
HECKMONDWIKE YORKSHIRE**

"Union" motorised Drilling Machines will give you long years of fast, accurate, dependable drilling with low unit production costs and minimum maintenance. Bench and pedestal models are available from all leading Machinery Merchants.

When answering advertisements kindly mention MACHINERY.

**"BRITISH★BUILT
American" for better
BROACHING!**



Model T-8-24
used at
VAUXHALL MOTORS
broaching
3 Rocker Arms
every 15 seconds

SEMI OR FULLY AUTOMATIC CYCLE
MODELS NOW AVAILABLE

★ Write today for full technical information

BUILT AND TOOLED BY



WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033



ALSO AT BIRMINGHAM—TEL: SPRINGFIELD 1134/5 • STOCKPORT—TEL: STOCKPORT 5241 • GLASGOW—TEL: MERRYLEE 2822

ADV 6


When answering advertisements kindly mention MACHINERY.

E

A 'MUST' for every Toolroom

THIEL 158

for the
manufacture of
FIXTURES • JIGS
PUNCHES
GAUGES • DIES



Photographed by courtesy of
Vactric (Precision Tools) Ltd.


MORE VERSATILE

HIGHER PRECISION


EASIER TO OPERATE

This Thiel has a higher value in the tool room than any other single piece of equipment for the manufacture of punches, dies, gauges, profiles, jigs and fixtures. Most other equipment of the older No. 58 will fit this machine.


Large number of attachments can be supplied including drilling attachment with spindle speeds up to 5000 r.p.m. All power feeds fitted with automatic stops and fine measuring device.



Vertical spindle
drive through overarm,
independent of horizontal spindle



Close to
column
jig boring



Jig boring
showing large throat capacity

WELSH HARP, EDWARE ROAD, LONDON, N.W.2. TELEPHONE: GLADSTONE 0033

ROCKWELL
MACHINE TOOL CO. LTD.

ALSO AT • BIRMINGHAM—TELEPHONE SPRINGFIELD 1134/5 • STOCKPORT—TELEPHONE STOCKPORT 5241 • GLASGOW—TELEPHONE MERRYLEE 2822
T158

When answering advertisements kindly mention MACHINERY.

You can count on STALKER for all your needs in small tools. We produce a comprehensive range including twist drills, reamers, milling cutters, hollow mills, end mills, etc. Note, too, that STALKERIDE carbide tipped drills and reamers are available in many sizes. Ask about LUBRICOLD Oil Feed Drills.

**if it's
small
tools
you
need...**



**STALKER
exactly!**



LEE 2022

THE STALKER DRILL WORKS LIMITED • DRILL SQUARE • SHEFFIELD, 6

When answering advertisements kindly mention MACHINERY.

F

A 'MUST' for every Toolroom

THIEL 158

for the
manufacture of
FIXTURES • JIGS
PUNCHES
GAUGES • DIES



*Photographed by courtesy of
Vactric (Precision Tools) Ltd.*


MORE VERSATILE

HIGHER PRECISION


EASIER TO OPERATE

This Thiel has a higher value in the tool room than any other single piece of equipment for the manufacture of punches, dies, gauges, profiles, jigs and fixtures. Most other equipment of the older No. 58 will fit this machine.


Large number of attachments can be supplied including drilling attachment with spindle speeds up to 5000 r.p.m. All power feeds fitted with automatic stops and fine measuring device.



Vertical spindle
drive through overarm,
independent of horizontal spindle



Close to
column
jig boring



Jig boring
showing large throat capacity

WELSH HARP, EDGWARE ROAD, LONDON, N.W.2. TELEPHONE: GLADSTONE 0033

ROCKWELL
MACHINE TOOL CO. LTD.

ALSO AT • BIRMINGHAM—TELEPHONE SPRINGFIELD 1134/5 • STOCKPORT—TELEPHONE STOCKPORT 5241 • GLASGOW—TELEPHONE MERRYLEE 2822
7158

When answering advertisements kindly mention MACHINERY.

You can count on STALKER for all your needs in small tools. We produce a comprehensive range including twist drills, reamers, milling cutters, hollow mills, end mills, etc. Note, too, that STALKERIDE carbide tipped drills and reamers are available in many sizes. Ask about LUBRICOLD Oil Feed Drills.

**if it's
small
tools
you
need...**




**STALKER
exactly!**



THE STALKER DRILL WORKS LIMITED · DRILL SQUARE · SHEFFIELD, 6

When answering advertisements kindly mention MACHINERY.

F



'Between you and me' (SAID THE DRILL)
'I like a spot of R.T.D.'

"Me too," said Stainless (with a steely glance),
 "especially when I'm under pressure."
 "It does avoid a lot of friction," agreed the Drill.
 "D'you know, the other day I almost had a seizure."
 "Drills run free with R.T.D.," said Stainless,
 "and don't you forget it makes things smoother for
 the likes of us, as well."
 "Just the stuff when the drilling's tough," replied the
 Drill. "And saves me growing old before my time!"

Write to ROCOL about R.T.D.

ROCOL LTD. IBEX HOUSE, MINORIES, LONDON, E.C.3. Tel : ROYal 4372

ROCOL HOUSE, SWILLINGTON, Nr. LEEDS. Tel : Garforth 2261/2

ROCOL R.T.D. COMPOUND
 does indeed prolong the life of
 drills (in fact, *all* cutting tools)
 many times over, and obtains a
 higher finish. Lubricate with
 R.T.D. when working with tough
 metals, including stainless steel,
 alloy steels and nickel alloys.
 Write for the Brochure, giving
 technical information and over
 twenty actual case histories.

A
ROCOL
PRODUCT

mdh

3273

When answering advertisements kindly mention MACHINERY.

ARCHDALE 28"



**COMBINES ACCURACY WITH THE POWER
AND SPEED TO REDUCE COSTS**

- ANTI-BACKLASH DEVICE
- BUILT-IN CLIMB MILLING
- REVERSIBLE LONGITUDINAL FEEDS
- QUICK POWER TRAVERSE

These sturdy and powerful machines, with their many outstanding features, mean increased milling efficiency wherever they are installed. Forgrove Machinery Co. Ltd., Leeds, are no exception, and in this modern factory ARCHDALE machines are setting the pace on a variety of work, such as the straddle milling of cast iron twist boxes as shown. Six speeds, 30/462 r.p.m. with eight feeds from 0.7in. to 15.5in. per minute.

Complete details gladly sent on request.



JAMES ARCHDALE & CO., LTD., LEDSAM STREET, BIRMINGHAM, 16

A Member of the Stavely Coal & Iron Co. Ltd. Group.

Telephone: EDGaston 2276

Sole Agents: **ALFRED HERBERT LTD., COVENTRY.** Telephone: 89221

When answering advertisements kindly mention MACHINERY.

F 2







JESSOP-SAVILLE

alloy tool steels

The ever-insistent demands of the Engineer for more rapid production processes has led to an equally insistent demand for superior tool steels.

Jessop-Saville manufacture a wide range of Alloy Tool Steels of which three outstanding qualities are available from stock.



JESSOP-SPECIAL G1 SAVILLE S.V.L.

An air-hardening Nickel-Chrome-Molybdenum Steel which is highly resistant to shock and used for cold-punches, stamping and trimming dies, shear blades and chisels, etc.

JESSOP ALLOY C SAVILLE W.P.S.

A high-carbon, high chromium cold-work steel having very high wearing qualities and resistance to corrosion. Used for the highest quality press tools, drawing and cutter dies, cold-forming and burnishing rolls, etc.

JESSOP-SAVILLE K.4 SPECIAL

A low-alloy, non-distorting cold-work steel capable of deep and intense hardening and used for high-quality press tools, gauges, taps, and dies, etc.

A Stock List is published each month and will be supplied on request.

All Jessop-Saville Steels are produced in the one works and under one technical direction which ensures the highest order of control in the careful selection of raw materials, melting and casting.




WM JESSOP & SONS LTD
BRIGHTSIDE WORKS SHEFFIELD

J J SAVILLE & CO LTD
TRIUMPH WORKS SHEFFIELD


MEMBERS OF THE B.S.A. GROUP

When answering advertisements kindly mention MACHINERY.

three men speak their mind about their machines . . .



This is just one of the many refinements you can obtain!



Curve milling on VF 1 with circular feed table and power driven circular feed.

A Works Manager says :

Among the many excellent features of VF 1, I want to emphasise the extra support pillar for the knee as well as the spindle enclosure. Besides hand feed, VF 1 has power feed with variable feed pressure and automatic release against an adjustable micrometer stop. The spindle head is moreover swivelling, and can be adjusted accurately. Final judgment. Powerful construction which gives it the precision we want and must have.

A Planning Manager says :

I am naturally especially interested in the practical and well thought out accessories which can be obtained. Take for example the large round feed table with machine feed and dividing plate, or multiple stop for the spindle adjustment, as well as the easily mounted quick milling apparatus. That the machine, by having double-length feed screws, can be used for climb milling makes it doubly valuable.

A Purchasing Manager says :

During my years as buyer I have learnt one fundamental thing, which I will readily share. A machine is never better than the service the manufacturer can give. That was also a thing I checked carefully before we decided on VF 1. We were promised perfect service, and practice has also shown that the type of service Köping gives is just right for us on the purchasing side.

Three men with a
common denominator . . .



There is so much more we would like to tell you about VF 1. We have a brochure for you packed with valuable and interesting facts about a machine which can be the right one to increase production at your works. Send us a line, and you will receive it by return of post.

DISTRIBUTORS AND STOCKISTS FOR THE UNITED KINGDOM



Showroom & Sales : 204-206 ACTON LANE : HARLESDEN : N.W.10.


Tel. ELG 3834

MARTONAIR TECHNICAL ADVISORY SERVICE—7

The circuit contains three cylinders, sequentially operated, and is a further example of the type of sequential control that can be obtained. The cycle shown is: A+, B+, C+ A—, B— C—. The cylinders do not necessarily operate in the same direction or in the same plane, and re-arrangement of the piping or components could provide many variations on this sequence.

Depression of the push-button of the three-port valve (1) reverses valve (2) and outstrokes cylinder (A). Roller-operated three-port valve (3) is tripped, reversing valve (4). Cylinder (B) outstrokes. Valve (5) is tripped, reversing valve (6) to outstroke cylinder (C). At the same time, valve (2) is returned to its original position to instroke cylinder (A).

As cylinder (C) completes its stroke, valve (7) is tripped and supplies a signal to return valves (4) and (6) to their original positions and thus return or instroke cylinders (B) and (C). Flow regulators may be fitted to control the speeds of the cylinders, and if necessary, valves could be fitted to prevent a movement should an earlier movement not be completed. Thus, if it should be essential that (B) and (C) should not return to the position shown until (A) has completed a slow return, the air supply for valve (7) could be taken through a roller operated three-port valve fitted in such a position as to be depressed by the trip or cam on the piston rod of cylinder (A) in its inward position.



MARTONAIR LIMITED

PARKSHOT • RICHMOND • SURREY • ENGLAND


TELEPHONE : RICHMOND 2201 (6 lines)

MANUFACTURERS OF PNEUMATIC HOISTS • CYLINDERS • CONTROL VALVES AND ACCESSORIES

When answering advertisements kindly mention MACHINERY.


The Martonair Technical Service is freely at your disposal at all times. Fully qualified to advise on all aspects of applied pneumatics, the Service is backed by a staff of technical representatives in Great Britain, and by overseas offices and manufacturing companies.

Copies of this advertisement and earlier issues in this series are available from Martonair Limited.



I'm a spaceman myself!

but don't get me wrong. I won't be on the first moon rocket. I'm putting my factory space which cost good money to its proper use. In other words, I'm using it to house machinery and not throwing it away on big space-wasting drives. If you think three-dimensionally, like me, you'll use chain drives, and get another machine or two on that floor.



Photograph by kind permission of
Rose, Downs & Thompson Ltd., Hull.

RENOLD chain drives conquer space problems in almost all applications

*This oil expeller installation for the
treatment of oil bearing seeds and nuts is
equipped with Renold Stock Chain Drives.*



save space



save power



increase production



— the FIRST name in precision chain

RENOLD CHAINS LIMITED • MANCHESTER

When answering advertisements kindly mention MACHINERY.

MARBAIX

FOR UNUSUAL MACHINES



BARNESDRIL COOLANT FILTERS

**... assure continuous high
quality and surface finish
PLUS lower costs all round**

"Savings are secondary to the quality control we have gained in the use of Barnesdril Kleenall Filters. The Filters have allowed us to keep ahead of our competition in the quality of our product."

This statement was made by the Plant Superintendent of a prominent roller bearing manufacturer. A centreless grinder (shown) and a super-finisher are used for surface finishing and bringing bearings to their final accuracies. Both are equipped with Barnesdril Kleenall Combination Magnetic and Fabric Coolant Filters. The bearings, used in guided missiles, aviation electrical motors, and transportation equipment, are finished to 2 to 3 RMS. micro-inches. Size must be held to ± 0.000025 in. and their crowns held to 0.00001 in., checked by electronic measuring device.

By filtering the re-circulated coolant through Kleenall Filters, definite production savings are also accrued. Less coolant and less labour are required and equipment lasts longer. If quality control or extreme accuracy are part of your production requirements, write to Dept. M.18 for full details of Kleenall Filter.

**ORIGINATORS OF THE DRUM TYPE MAGNETIC
AND COMBINATION SEPARATORS.**

MADE IN GREAT BRITAIN

Patents Nos. 603083, 731655 and 745604; others pending

THE CENTRELESS GRINDER WITH A BARNESDRIL
MODEL MP-15 KLEENALL COMBINATION MAGNETIC
AND FABRIC FILTER.

GASTON E. MARBAIX LTD


DEVONSHIRE HOUSE, VICARAGE CRESCENT,
BATTERSEA, LONDON, S.W. 11
PHONE BATTERSEA 8888 (8 lines)

When answering advertisements kindly mention MACHINERY.

MARBAIX

FOR UNUSUAL MACHINES

new



MÄGERLE

FULLY AUTOMATIC PRODUCTION PROFILE GRINDER

The most advanced machine of its type

ENTIRELY
AUTOMATIC
EXCEPT FOR
LOADING &
UNLOADING

THREE SIZES WITH WHEELS UP TO 4in. WIDE

MODEL FP 7A TABLE WORKING SURFACE 29½ in. by 9½ in.

MODEL FP10A TABLE WORKING SURFACE 41½ in. by 9½ in.

MODEL FP12A TABLE WORKING SURFACE 49½ in. by 9½ in.

ALL MODELS HAVE 15½ in. CLEARANCE UNDER WHEEL

WRITE FOR FULL DETAILS TO DEPT. MIS

- WHEEL PERIPHERAL SPEED CONSTANT
- AUTOMATIC SIZING WITHIN 0-0002in.
- NEW PATENTED WAYS GIVING ABSOLUTE RIGIDITY & PRECISION
- AUTOMATIC COMPENSATION FOR WHEEL WEAR THROUGH REDRESSING



ROCKER
ARM

GROUND FROM FORGING
AFTER SNAGGING REMOVING MAX. .100in. STOCK.
SURFACE FINISH—10 MICRO INCHES RMS or BETTER
PRODUCTION — — — 170 PARTS PER HOUR

GASTON E. MARBAIX LTD

DEVONSHIRE HOUSE, VICARAGE CRESCENT,
BATTERSEA, LONDON, S.W. 11
PHONE BATTERSEA 8888 (8 lines)

When answering advertisements kindly mention MACHINERY.

MARBAIX

FOR UNUSUAL MACHINES

MARBAIX-NASH

Rotary Finishers



FOR ULTRA FAST FLASH REMOVAL,
GRINDING, BUFFING, ETC., ON
CIRCULAR MOULDED
AND MACHINED PARTS

MODEL 103

- UNSURPASSED PRODUCTION RATES
- CONTINUOUS TURRET OPERATION
- VARIABLE TURRET AND SPINDLE SPEEDS ADJUSTABLE WHILE RUNNING
- PRODUCTION UP TO 70 PIECES PER MINUTE

Here is a machine that really solves the problem of finishing circular mouldings and diecastings—AT UNSURPASSED PRODUCTION SPEEDS. Applications are almost unlimited, as it is possible to use cutters, carbide files, grinding and buffing wheels, abrasive and buffing belts—in fact, any type of tooling that can be mounted on the working arc of the back table.

MODEL 103-B is a similar machine operating with an Intermittent motion and its index mechanism permits dwelling at tooling station
Production up to 20 pieces per minute

CAPACITY

Diameter range, ten spindles ..	0in. to 4½in.
Height range	0in. to 8in.
Number of spindles 10

WRITE FOR FULL DETAILS AND
PRODUCTION ESTIMATES TO DEPT. M.3.

GASTON E. MARBAIX LTD

DEVONSHIRE HOUSE, VICARAGE CRESCENT
BATTERSEA, LONDON, S.W. 11
PHONE BATTERSEA 8888 (8 lines)

When answering advertisements kindly mention MACHINERY.

■ EXTERNAL & INTERNAL MICROMETERS...DEPTH GAUGE MICROMETERS...FEELER GAUGES ■


Where accuracy is essential...



manufactured to
BRITISH STANDARD
SPECIFICATION



• • • In machine shops, toolrooms and inspection departments, men who are accustomed to working to fine limits, like to work with quality tools they can trust, — tools upon whose accuracy they can rely. If accurate measurement is *YOUR* requirement, *REMEMBER* —



Precision Tools measure up to any job

SEND 84d. IN STAMPS FOR A COPY OF OUR LATEST CATALOGUE, MENTIONING THIS JOURNAL.

■ MOORE & WRIGHT (Sheffield) LTD., NORTON LANE, SHEFFIELD 8. ■

When answering advertisements kindly mention MACHINERY.

BEVEL PROTRACTORS...ENGINEERS SQUARES & STRAIGHT EDGES...SURFACE PLATES...PROTRACTORS

RADIUS GAUGES...SCREW PITCH GAUGES...MILL TOE GAUGES...SURFACE GAUGES...TELESCOPIIC GAUGES

GREASE

for smoother
running -



The life and efficiency of a machine tool depends upon the correct application of the right lubricant in the proper place. The design of machine tools is complex and many factors have to be considered in selecting the most suitable lubricant—working conditions, operating temperatures, speed of rotation, bore of feed pipes. In the compact range of ALMARINE greases one can find lubricants to satisfy all these basic requirements economically and efficiently. Ask for Publication SP178.

LUBRICATION AT YOUR FINGERTIPS

Machine shop maintenance is always complicated but the task can be simplified by a FLETCHER MILLER Lubrication Survey—Your maintenance requirements are expertly analysed and grouped with all data clearly set out in a permanent record. May we help you in this way?

FLETCHER MILLER

Machine Tool Lubricants

ALMARINE FOR ALL GREASE POINTS

VETA FOR HYDRAULIC SYSTEMS GENERALLY

GENA THE MACHINE TOOL LUBRICANT

FLETCHER MILLER LTD., ALMA MILLS, HYDE, CHESHIRE.

Telephone: HYDE 3471 (5 LINES)


Telegrams: EMULSION, HYDE

Also at LONDON, WEST BROMWICH, NEWCASTLE-ON-TYNE, CARDIFF, GLASGOW AND BELFAST

When answering advertisements kindly mention MACHINERY.

MTL35

THE NEW SCRIVENER



No. 3

Centreless Grinding Machine

For continuous high production of precision ground parts the Scrivener feature of controlled cycle plunge grinding offers special economy unattainable by any other grinding method.

This example illustrates typical production.



Stub Axle. Plunge grinding two dia. ($\pm 0.0002''$) and two tapers (to gauge) magazine feed.

Total time. 30 seconds. 120 pieces per hour. Stock removed 0.012" to 0.015" in two passes.

The largest machine in the Scrivener range, this new Centreless Grinding Machine was introduced at the International Machine Tool Exhibition, and received wide approbation.

Employing the Scrivener system of controlled cycle operation, it demonstrated the plunge grinding of a stub axle in a total cycle time of 30 seconds (for two operations).

Scrivener machines incorporate, in addition to features for straight-through or hand-operated plunge grinding, a system for semi- or fully-automatic controlled cycle operation. By adopting the latter method, very economical mass production rates can be achieved, the machines feed, grind and eject in sequence and can be incorporated into automatic production lines.

The complete range comprises:

Model	No. 1D	No. 2	No. 3
Grinding wheel dia. and width	12" x 3"	20" x 6"	20" x 10"
Control wheel dia. and width	7" x 3"	12" x 6"	14" x 10"
Max. opening between rear wheels	2½" x 2"	6" x 4½"	9" x 9"

*Machines with controlled cycle operation.

WICKMAN LIMITED

FACTORED MACHINE DIVISION, FLETCHAMSTEAD HIGHWAY, COVENTRY

Telephone: Coventry 40351

When answering advertisements kindly mention MACHINERY.

GREASE



*for smoother
running -*

The life and efficiency of a machine tool depends upon the correct application of the right lubricant in the proper place. The design of machine tools is complex and many factors have to be considered in selecting the most suitable lubricant—working conditions, operating temperatures, speed of rotation, bore of feed pipes. In the compact range of **ALMARINE** greases one can find lubricants to satisfy all these basic requirements economically and efficiently. Ask for Publication SP178.

LUBRICATION AT YOUR FINGERTIPS

Machine shop maintenance is always complicated but the task can be simplified by a **FLETCHER MILLER** Lubrication Survey—Your maintenance requirements are expertly analysed and grouped with all data clearly set out in a permanent record. May we help you in this way?

FLETCHER MILLER

Machine Tool Lubricants

ALMARINE FOR ALL GREASE POINTS

VETA FOR HYDRAULIC SYSTEMS GENERALLY

GENA THE MACHINE TOOL LUBRICANT

FLETCHER MILLER LTD., ALMA MILLS, HYDE, CHESHIRE.

Telephone: HYDE 3471 (5 LINES)


Telegrams: EMULSION, HYDE

Also at LONDON, WEST BROMWICH, NEWCASTLE-ON-TYNE, CARDIFF, GLASGOW AND BELFAST

When answering advertisements kindly mention **MACHINERY**.

MTL35

THE NEW SCRIVENER




No. 3

Centreless Grinding Machine

For continuous high production of precision ground parts the Scrivener feature of controlled cycle plunge grinding offers special economy unattainable by any other grinding method.

This example illustrates typical production.



Stub Axle. Plunge grinding two dia. ($\pm 0.0002''$) and two tapers (to gauge) magazine feed.

Total time. 30 seconds. 120 pieces per hour. Stock removed 0.012" to 0.015" in two passes.

The largest machine in the Scrivener range, this new Centreless Grinding Machine was introduced at the International Machine Tool Exhibition, and received wide approbation.

Employing the Scrivener system of controlled cycle operation, it demonstrated the plunge grinding of a stub axle in a total cycle time of 30 seconds (for two operations).

Scrivener machines incorporate, in addition to features for straight-through or hand-operated plunge grinding, a system for semi- or fully-automatic controlled cycle operation. By adopting the latter method, very economical mass production rates can be achieved, the machines feed, grind and eject in sequence and can be incorporated into automatic production lines.

The complete range comprises:

Model	No. 1D	No. 2	No. 3
Grinding wheel dia. and width	12" x 3"	20" x 6"	20" x 10"
Control wheel dia. and width	7" x 3"	12" x 6"	14" x 10"
Max. opening between rear wheels	2½" x 2"	6" x 4½"	9" x 9"

*Machines with controlled cycle operation.

WICKMAN LIMITED

FACTORED MACHINE DIVISION, FLETCHAMSTEAD HIGHWAY, COVENTRY

Telephone: Coventry 40351

When answering advertisements kindly mention MACHINERY.

448728

A Cut above the rest...



Strasmann Cobalt Steel Milling Cutters are designed for rough machining high tensile steels and other tough materials. The thread form gives single point cutting action which is admirably suited to the removal of metal in bulk. The finish left by these cutters is slightly wavy, and as the surface is not glazed, finishing with conventional cutters is simplified.

★ **STRASMAN REAMERS**

Strasmann Machine Reamers also manufactured from cobalt steel are designed for through hole reaming in all metals. Good finish, straight holes are possible at high production rates. Hole sizes are constant and regrinding does not affect the diameter.



TE ROY
LTD

TEROY LTD., CENTRAL HOUSE · FRATTON BRIDGE · PORTSMOUTH
PORTS 33217/8

Sole distributors for Strasmann Roughing Cutters and Reamers in the U.K., would be pleased to send you literature and arrange a demonstration. Enquiries for special requirements are gladly invited.


When answering advertisements kindly mention MACHINERY.

SLIDING RAM
GIVES 27½ in.
AUTO CROSS
FEED

HEAVY DUTY MILLING

ANGULAR COMPOUND HORIZONTAL VERTICAL

HURON SUPER UNIVERSAL MILLERS



Integral double swivelling universal head provided with 27½ in. automatic cross feed by the sliding ram, can be set to the horizontal or vertical position, or to any angle instantaneously—permits the heaviest production cuts. Head can be retracted completely from table line. 27 spindle speeds from 30 to 2,066 r.p.m. 27 feeds from ⅛ in. to 30 in. Rapid traverses in all directions. All operating controls duplicated. Table slides directly in the knee without cross movement or swivel. Double guides of knee permit components in excess of 1½ tons to be machined. The double swivelling universal head requires an opening of only 14 in. to enter work pieces and the whole sliding ram with its 27½ in. automatic cross movement needs only 18 in. clearance.

Type	Table	Automatic Feeds		
		Long	Cross	Vert.
KU4	56½ in. × 15½ in.	43½ in.	27½ in.	19½ in.
KU5	64½ in. × 15½ in.	51½ in.	27½ in.	19½ in.
KU6	78½ in. × 16½ in.	59 in.	27½ in.	19½ in.
L7	157 in. × 39 in.	118 in.	27½ in.	39½ in.


Type 'L' Open-side Traversing Head Universal Miller will mill, bore, slot and drill the largest work-pieces at one setting.

The unique design permits greatest variety of operation on large work-pieces; the component remains stationary on the large work-table. Upright slides full length of base table, and the sliding ram moves vertically and horizontally.


DUFOUR UNIVERSAL MILLERS

Table surface 43½ in. by 9½ in. or 47½ in. by 10½ in. Auto long. feed, 26½ in. or 30½ in. Auto vert. feed, 15½ in. or 18½ in. Auto cross feed 9½. Rapid traverse in all directions. No. 40 International taper for main spindle, universal head, and rotary table. Direct reading dial change for speeds and feeds. All parts subject to wear hardened and ground and completely interchangeable. Built to closest tolerances. Spindle speeds 21 to 1,600 r.p.m. Twin overarms. Separate motor for rapid traverses.

Also table 63 in. by 15 in., with auto feeds: 40 in. long., 21 in. vert., 14 in. cross; 25 in. auto-univ. head feed. 36 spindle speeds 6 to 1,500 r.p.m.



SCULFORT LATHES



Swing over bed 20, 22 or 25 in.
and 28, 32 or 66 in.
and 40, 47 or 60 in.

Speed ranges: 6-2,000;
12-1,600;
or 3½-325 r.p.m.

18-45 h.p. motor drives for max. output. Totally enclosed gear box provides 90 different pitches. Flame hardened bed. Large spindle bore. All head stock gears hardened and ground. Built-in coarse screw cutting device.

Other products: Copying lathes, Locomotive and Carriage Wheel Turning Lathes, Centreless Bar Turning Machines, Facing Lathes and Special Purpose Centre Lathes.

We
supply
Ex-Stock
and demonstrate
CLARE Chucks & Collets.


Rudolph Carne & Co. Ltd.

SWAN WORKS, FISHERS LANE,
CHISWICK, LONDON, W.4.

Telephone: CHISWICK 0514 & 6585. Inland Telegrams: RUDCAR, CHISK, LONDON. Overseas Telegrams: RUDCAR, LONDON.

When answering advertisements kindly mention MACHINERY.

**THIS HAS
ALREADY
SOLVED
1001
PROBLEMS**



DE LAVAL OIL PURIFIERS *are the answer!*
CENTRIFUGAL

CONSULT US FOR:—

- Recovery of Cutting Oil.
- Clarification of honing and grinding coolants.
- Purification of dielectric fluid for spark-machining.
- Reclamation of used lubricating oil from Test-beds, hydraulic systems, etc., etc.
- Cleaning and degreasing of metal parts from machining, stamping, pressing and other operations.
- Transport of cutting oils and coolants to machine tools.

Call in

DE LAVAL

Our Research Laboratory and Technicians will be pleased to discuss your particular problem and recommend suitable equipment.

FACTORY EQUIPMENT DIVISION

ALFA-LAVAL COMPANY LIMITED

GREAT WEST ROAD · BRENTFORD · MIDDLESEX · Tel: EALing 0116

When answering advertisements kindly mention MACHINERY.

Smee's DL342

CL
NU
124
Stree
LEE



Precision profiling

Time meant little to yesterday's craftsmen; the perfect job was all important. Today, perfection is easier, and *time* the greatest factor.

This is the best reason we can give you for using Clarkson cutting tools—with the Clarkson new-system Autolock and Dedlock Milling Chucks. That means accurate cutting, with considerable savings in time and labour. There is a Clarkson stockroom near to you giving the benefits of ex-stock delivery, the renowned Clarkson quality—
and at the manufacturer's own prices.

Cut with **Clarkson**

CLARKSON (ENGINEERS) LTD.

NUNEATON Head Office and Works, Nuneston 2261
124 Hammersmith Road, W.6 RIVERSIDE 8241
Street, 2, Bristol 2-8464

MANCHESTER 98 Oxford Road, 13, ARDWICK 4804
LEEDS 8a Britannia House, 1, Leeds 26369

NEWCASTLE 241 Westgate Road, 1, NEWCASTLE 2-5248
BIRMINGHAM 15 Heath Mill Lane, 9 Victoria 3994
Oxford Road, 13, ARDWICK 4804

BELFAST 32 Shaftesbury Square

LONDON
BRISTOL 17 Cumberland
GLASGOW 430 Crown Street, C.5 SOUTH 1942

When answering advertisements kindly mention MACHINERY.




HEAVY DUTY SELF CENTRING CHUCKS

ALL SIZES
EX-STOCK

THE MOST
ACCURATE
CHUCK MADE

ALL WORKING PARTS
HARDENED AND
GROUND AND
INTERCHANGEABLE



THREE AND
FOUR JAW
FROM
4½ in. to 20 in. dia.

TWO JAW
FROM
5½ in. to 10 in. dia.

SEND FOR CATALOGUE No. 6M

TWO YEARS'
UNCONDITIONAL GUARANTEE
WITH EVERY CHUCK

TELEPHONE MIDLAND 0083-4-5

CHARLES TAYLOR
(BIRM) LTD
BIRMINGHAM.5. ENGLAND

When answering advertisements kindly mention MACHINERY.

AIR**CYLINDERS
& VALVES**

PROPERLY APPLIED AND CONTROLLED

AIRPROVIDES **FLEXIBLE POWER** FOR GREATER

EFFICIENCY WITH SAFETY SPEED AND

SIMPLICITY



Cylinders lin. to 12in.
diameter and any length, to-
gether with air hoists and wide
range of pneumatic control gear

FOR

**PUSHING - PULLING****LIFTING - LOWERING****PRESSING - SQUEEZING****TILTING - TURNING****OPENING - CLOSING**

STUART DAVIS LTD.
MUCH PARK STREET, COVENTRY


Telephone: Coventry 63091-2



When answering advertisements kindly mention MACHINERY.

Automation at Vauxhall Motors 84 MACHINERY

June 13, 1958



As in the many other fields of industrial production where continuous processes are called for **VICKERS-DETROIT** Oil Hydraulics are specified by the largest organisations to reduce cost, improve uniformity and provide flexibility — advantages which are at the service of every industrialist, whatever the size of plant.





by **STEIN ATKINSON VICKERS HYDRAULICS LIMITED**

S.A.V. HYDRAULICS

60 Buckingham Palace Road London S.W.1

*At Vauxhall's spectacular new plant automation is brought to the highest pitch of efficiency yet achieved. Pictured is the Asquith 18-station Drilling Transfer Machine used for machining all Vauxhall Victor, Velox and Cresta cylinder heads. With a total of 273 spindles it absorbs 269 H.P., cycling at 70 pieces/hr. performing all drilling, reaming, countersinking, boring and tapping operations. The sequence of all the fixtures, transfer bar, tilting and turning stations is actuated by **VICKERS-DETROIT** Oil Hydraulic Equipment.*

For further details please write for publication 1/39



on guard !

. . . eliminate risk with
BRABY machine guards in
wire lattice or sheet metal

Consult us for your special requirements

ONE OF THE WIDE RANGE OF

BRABY

PRODUCTS


FREDERICK BRABY & COMPANY LIMITED

LONDON WORKS: THAMES ROAD, CRAYFORD, KENT

Telephone: Bexleyheath 7777

and at London, Liverpool, Glasgow and Bristol

When answering advertisements kindly mention MACHINERY.



WHICHEVER WAY YOU LOOK AT IT,
YOUR PRODUCTION & PROTECTION DEMAND



**MACHINE
GUARDS**

A Clear action for Safety

COMPREHENSIVE AND FULLY ILLUSTRATED CATALOGUE WILL BE SENT ON REQUEST FREE FROM:
THE SILVAFLAME CO. LIMITED • 218a MONUMENT ROAD • BIRMINGHAM 16

When answering advertisements kindly mention MACHINERY.

ZBROJOVKA**MILLERS****for heavy duty**

**Immediate delivery
of most models from
our London Showrooms**

**Sole Agents**

Precision heavy duty milling is a speciality of ZBROJOVKA MILLERS which operate with complete rigidity at the highest speeds. The illustration shows a FA5V Vertical Miller installed in the works of Messrs. C. J. C. Developments (Portsmouth) Ltd., by whose courtesy this photograph is published. Write or telephone for full information.

BRIEF SPECIFICATIONS OF HORIZONTAL, UNIVERSAL AND VERTICAL MILLERS

Sizes	No. 2	No. 3	No. 4	No. 5
Working surface of table (approx.)	40" x 8"	50" x 10"	64" x 12"	80" x 16"
Power longitudinal travel (approx.)	25"	32"	40"	50"
Power cross travel (approx.)	8"	9"	12"	16"
Spindle speeds	62-2800	45-2000	32-1400	18-1400

The Selson Machine Tool Co. Ltd

41-45 MINERVA ROAD, NORTH ACTON, LONDON, N.W.10


Telephone: Elgar 4000 (10 lines) Telegrams: Selsomachi, London, N.W.10



Pre-selection for increased production with V.D.F.

Turret Lathes, type RS

The V.D.F. turret lathe, type RS, is supplied with automatic cycle control. An ingenious dial type pre-selector system now brings push button control to the turret lathe. Feeds, speeds, direction of rotation and instantaneous stopping are all programme controlled. The correct speeds and feeds are automatically engaged as the turret is indexed, resulting in consistently high production rates, long tool life and the desired standard of finish.



4 MODELS

each with hardened and ground bedways and rapid traverse in all directions.

* RS50	
max. diameter bar	1 $\frac{1}{32}$ "
swing over bed	17 $\frac{1}{2}$ "
motor h.p.	10
* RS63	
max. diameter bar	2 $\frac{31}{64}$ "
swing over bed	17 $\frac{1}{4}$ "
motor h.p.	13
* RS80	
max. diameter bar	3 $\frac{1}{16}$ "
swing over bed	22 $\frac{1}{16}$ "
motor h.p.	19
* RS100	
max. diameter bar	3 $\frac{1}{8}$ "
swing over bed	22 $\frac{1}{16}$ "
motor h.p.	19


Sole British Agents:

SYKES

Phone: STAINES 5076 (3 lines)
Grams: "SYTOOL, STAINES"

MACHINE TOOL CO. LTD

HYTHE WORKS • THE HYTHE • STAINES • MIDDLESEX



The Bliss Knuckle Joint Press is designed for work requiring powerful pressure close to bottom stroke.

This type of press can also be equipped with manual and automatic feeding devices to facilitate material handling and speed production.

With capacities up to two thousand American tons they are available in thirty-two standard sizes, fully described in Catalogue 12B.

Have you had your copy ?

COINING


EMBOSSING

SWAGING

HEADING

EXTRUDING

SIZING



**KNUCKLE
JOINT
PRESSES**


E. W. BLISS (ENGLAND) LTD.
CITY ROAD · DERBY
Telephone : DERBY 45801 (4 lines).

London Office:
2/3 THE SANCTUARY, WESTMINSTER, S.W.1.
Telephone: ABBEY 3651.

Pre-selection for increased production with V.D.F.

Turret Lathes, type RS

The V.D.F. turret lathe, type RS, is supplied with automatic cycle control. An ingenious dial type pre-selector system now brings push button control to the turret lathe. Feeds, speeds, direction of rotation and instantaneous stopping are all programme controlled. The correct speeds and feeds are automatically engaged as the turret is indexed, resulting in consistently high production rates, long tool life and the desired standard of finish.



4 MODELS

each with hardened and ground bedways and rapid traverse in all directions.

- * **RS50**
max. diameter bar $1\frac{31}{32}$ "
swing over bed $17\frac{3}{4}$ "
motor h.p. 10
- * **RS63**
max. diameter bar $2\frac{31}{64}$ "
swing over bed $17\frac{3}{4}$ "
motor h.p. 13
- * **RS80**
max. diameter bar $3\frac{5}{16}$ "
swing over bed $22\frac{1}{16}$ "
motor h.p. 19
- * **RS100**
max. diameter bar $3\frac{11}{16}$ "
swing over bed $22\frac{1}{16}$ "
motor h.p. 19

Sole British Agents:

SYKES

Phone: STAINES 5076 (3 lines)
Grams: "SYTOOL, STAINES"

MACHINE TOOL CO. LTD

HYTHE WORKS • THE HYTHE • STAINES • MIDDLESEX



The Bliss Knuckle Joint Press is designed for work requiring powerful pressure close to bottom stroke.

This type of press can also be equipped with manual and automatic feeding devices to facilitate material handling and speed production.

With capacities up to two thousand American tons they are available in thirty-two standard sizes, fully described in Catalogue 12B.

Have you had your copy ?

COINING

EMBOSSING

SWAGING

HEADING

EXTRUDING

SIZING

**KNUCKLE
JOINT
PRESSES**

E. W. BLISS (ENGLAND) LTD.
CITY ROAD · DERBY

Telephone : DERBY 45801 (4 lines).

London Office:

2/3 THE SANCTUARY, WESTMINSTER, S.W.1.

Telephone: ABBEY 3651.

CEJ

THREADING TOOLS

CEJ PRODUCTS

Ground Thread Taps	Bore Gauges
Chaser Dies	Deltameters (Automatic Sizers)
Screw Plug Gauges	Drill Chucks
Screw Ring Gauges	Gauge Blocks
Circular Chasers and Holders	Dynamometers
Round Dies	Extensometers
Thread Milling Hobs	Plain and Screw Snap Gauges
Thread Rolling Dies	Plain Ring Gauges
Plain Plug Gauges	Gronkvist Drill Chucks
Mikrokators	Dial Gauges
Micro Snap Gauges	Tapping Attachments
Surface Finish Indicators	Multiple Interference Microscopes
Micrometers	Vernier Height Gauges




CEJ JOHANSSON LTD.
PRECISION TOOLS AND INSTRUMENTS

A.I.D. AND A.P.I. APPROVED

SOUTHFIELDS ROAD, DUNSTABLE, BEDS · TEL: DUNSTABLE 422/314

DH8/2350

When answering advertisements kindly mention MACHINERY.



Sanderson

Instruments

introduce the new


400 B

**MODEL
HEIGHT
GAUGE**

Advantages:—

- New design rigid beam section to eliminate deflection.
- Easier to read Vernier Scales, parallel to and in line with the face of the beam.
- Fine adjustment control situated in the base.
- Quick release control provided on the sliding jaw.
- Heavy dull chrome finish base containing the gears.
- Conforming to all B.S.S. limits.
- Definitely the cheapest of its type on the market.
- Quick delivery.
- The instrument can be supplied in 12in., 18in., 24in., 36in., 48in., 60in. and 72in. sizes.

NOTE—Customers are asked to note that Sanderson Instruments (Huddersfield) Ltd. is the new trading name for the old-established Company of Instruments (Huddersfield) Ltd.



Sanderson Instruments (Huddersfield) Ltd

PROSPECT STREET WORKS, HUDDERSFIELD.

Tel.: 7868.

DORMER SILVER RING
is a registered Trade Mark

SILVER RING

*— recognised
for supreme
performance*



DORMER


TAPER SHANK
TWIST DRILLS

OUTSTANDING
AMONG
ALL OTHERS

THE SHEFFIELD TWIST DRILL AND STEEL COMPANY LIMITED
SHEFFIELD ENGLAND
DORMER TOOLS ARE OBTAINABLE FROM YOUR USUAL ENGINEERS' MERCHANTS





When answering advertisements kindly mention MACHINERY.









ACME-GRIDLEY

BAR
2 1/4", 3 1/2"
FOUR SPINDLE



BAR
7/16", 1 1/4", 1 5/8", 2 5/8"
SIX SPINDLE

BAR
1 5/8"
EIGHT SPINDLE



CHUCKING
6"
SIX SPINDLE

437

MAKERS.
B.S.A. TOOLS LTD · BIRMINGHAM 33
ENGLAND



*the multi-spindle autos
with positive direct-
action quick-change
cam control*

SOLE AGENTS GT BRITAIN: BURTON GRIFFITHS & CO. LTD · KITTS GREEN · BIRMINGHAM · STECHFORD 3071

When answering advertisements kindly mention MACHINERY.

METAL INDUSTRIES LIMITED

announce that, as from June 1st, 1958, all business previously dealt with by Finney Presses Limited, 27 Berkley Street, Birmingham, will be incorporated with that of Fawcett Preston & Company Limited, Bromborough, Cheshire, another of the Group Companies.

FINNEY PRESSES LIMITED will cease to trade on May 31st, 1958, and all outstanding orders will be transferred to

FAWCETT PRESTON & COMPANY LIMITED

(Incorporating FINNEY PRESSES)

The full range of products will, in the future, be advertised and sold by Fawcett Preston & Company Limited (incorporating Finney Presses) and not Fawcett Finney Ltd., as previously.

A strong Sales and Service Department will continue to exist at 27 Berkley Street, Birmingham, but correspondence should in general be sent to Fawcett Preston & Company Limited, Bromborough, except where customers particularly desire to route their inquiries through the Birmingham Offices.

This change in the Company's structure will in no way affect the Technical and Sales Services provided in the past, and full continuity of production will be maintained.

FAWCETT PRESTON & COMPANY LIMITED

(Incorporating FINNEY PRESSES)

BROMBOROUGH • CHESHIRE

Telephone: Rock Ferry 2201. Telegrams: "Fawcett Bromborough."

Branch Offices in London, Birmingham and Glasgow

When answering advertisements kindly mention MACHINERY.



... it must be a standard plain cylindrical bearing which doesn't need oiling

In conditions where maintenance for lubrication is difficult or undesirable, the use of Reservoir sintered-metal oil-retaining bearings ensures that oil is fed automatically by capillary action direct


to the bearing surface. There are shapes and sizes of Reservoir bearings for every normal medium duty, and most sizes of plain cylindrical bearings to B.S.I. standard dimensions are held in stock.

... you should

specify

Reservoir

Sintered-Metal OIL RETAINING BEARINGS



Please write or 'phone for Technical Brochure SD.40 or Catalogue of sizes SD.58

THE MORGAN CRUCIBLE CO. LTD., BATTERSEA CHURCH ROAD, LONDON, S.W.11 BAT: 8822

SM 122/A

When answering advertisements kindly mention MACHINERY.



"Who's a sub-normal moron?"

Spectra-Blue Spectra-Orange
 Spectra-Red Spectra-Brown
 Spectra-Pink Spectra-Green
 Spectra-Grey Spectra-Magenta
 Spectra-Yellow Spectra-Seagreen
 Spectra-Violet
 Spectra-White Spectra-Black

That's what our Works Manager says of anyone who doesn't use SPECTRA-COLOR layout fluids. Just a point of view, but he knows what it means in time and accuracy (as well as temper) to have permanent needle sharp lines, there until machined off or removed with Spectra Remover. Brushed or sprayed on, SPECTRA-COLOR is unaffected by oil, water or petrol, the surface film is only 0.0002in. thick and it won't peel, chip, crack or smudge. There are two grades—Standard for all bright metals and polished surfaces, Opaque for black metals and unmachined castings—both grades in thirteen colours. No need to look for a brush—we can supply those too, ½in. only—just ask for Spectra Brushes, singly or in dozens.




SPECTRA COLOR

... comes in pints, quarts, half gallons and gallons

SPECTRA CHEMICALS LIMITED

Spectra Works, High Street, Caterham, Surrey. Tel. Caterham 3182, 2293 Grams. Spectra Caterham

When answering advertisements kindly mention MACHINERY.



**How much does it cost you
to drill and tap small parts
like these in quantity**

parts shown actual size

**Get the price down with
MULTIMATIC Machines**

or make up your own machines
from MULTIMATIC

**DRILLING UNITS . TAPPING UNITS
MILLING UNITS . INDEXING UNITS
BAR-FEED and PART-OFF UNITS
HOPPER FEED UNITS**




Write for further details.



MACHINE SHOP EQUIPMENT LTD. Spenser Street, London. S.W.1.

Tel: VICToria 6086

When answering advertisements kindly mention MACHINERY.



This Air Ejection Set installation shows cam operation off the press crankshaft. It will provide an air blast timed for a fraction of a second, or longer, at any desired point in the press cycle. If required the air blast can be continued after press motion has ceased.

AIR EJECTION gears your production to machine speed

Compressed air scientifically applied to many production problems produces speedier operation and work removal. Schrader Air Ejection Sets are designed to do just that. When fitted to a press or other machine the controlled air blast is synchronized to operate at machine speed, increasing the output and reducing operator fatigue. The pilot valve in the circuit times the duration of the air blast and also its operation at any point of the machine cycle. May we discuss how air ejection will help gear your production to machine speed?

To: **A. SCHRADER'S SON** (Division of Scovill Mfg. Co.)
829 TYBURN ROAD, ERDINGTON, BIRMINGHAM, 24

Please send details of Schrader Ejection Sets
and Air Control Equipment.

NAME.....

ADDRESS.....

M.214



Schrader

AIR EJECTION SETS

When answering advertisements kindly mention MACHINERY.



SPECIAL STEELS for die casting dies



DIES & DIE INSERTS

(KE) **A 145** 5½% Chrome Vanadium Molybdenum Steel.

(KE) **X 369** 5½% Chrome Tungsten Molybdenum Steel.

(KE) **896** Medium Carbon Chrome Vanadium Steel.

Supplied in ultrasonically tested forged blocks and black bars of square, round and rectangular sections.

DIE CORES

(KE) **LOCK 237** 18% Tungsten Vanadium High Speed Steel or the same quality of steel as that used for the die. Supplied centreless ground to precision limits, in lengths.

*Photograph by courtesy of
J. V. MURCOTT LTD.
Castings 7½ lbs. each produced
at intervals over 3 years*

EJECTOR PINS

(KE) **896** Medium Carbon Chrome Vanadium Steel and other types.

Supplied centreless ground and in the annealed condition, suitable for upsetting of the ends.

UNCOATED WELDING FILLER RODS

(KE) **A 145** 5½% Chrome Vanadium Molybdenum Steel.

(KE) **X 369** 5½% Chrome Tungsten Molybdenum Steel. 5/32" diameter material, in 3 feet lengths, available from stock.

Especially suitable for atomic welding under hydrogen.

KAYSER ELLISON & CO. LTD

ESTABLISHED 1825

CARLISLE STEEL WORKS · SHEFFIELD

Midland Stock Warehouse
Station Road, Coleshill, Birmingham. Tel.: Coleshill 2041/2.

London Stock Warehouse:
4, Pambridge Mews, Notting Hill Gate, W.11. Tel.: KEN 9062/3.

*This booklet,
giving greater
detail, is
available free
on request.*



When answering advertisements kindly mention MACHINERY.

H

The Nut, Bolt and Stud People



We are specialists in the manufacture of Bolts, Nuts, Studs and Machined Parts in all classes of Acid and Heat-Resisting Stainless Steels.

THE SANDIACRE SCREW CO. LTD.,
 SANDIACRE NEAR NOTTINGHAM.
 PHONE SANDIACRE 2065/6 • GRAMS 'SCREWS' SANDIACRE.



LOWER MILLING COSTS WITH **THE SEC-OP-MIL**

*Increase production
 Release the large machines*

HIGH PRODUCTION
 MILLING • SLOTTING
 CUTTING OFF
 SECOND OPERATION
 WORK

Manufactured by

ERMA LIMITED

MOUNT PLEASANT • ALPERTON • WEMBLEY • MIDDLESEX
 Telephone: WEMBLEY 3491-5 Telegrams: ERMobil, WEMBLEY



When answering advertisements kindly mention **MACHINERY**.



SMALL TOOLS

*... mean
more Production*

MILLING CUTTERS

SIDE & FACE, CYLINDRICAL, SLOTTING
ANGLE, CONCAVE, CONVEX, SPECIAL FORMS

REAMERS • SLITTING

SAWS • TWIST DRILLS

ARBORS • SLEEVES

SOCKETS

LATHE CENTRES



THE **MOORE** MANUFACTURING CO., LTD.

PROGRESS WORKS • LAISTERDYKE • BRADFORD 4 • YORKS

'Phone: Bradford 64365-6

'Grams: Mooranco, Bradford

When answering advertisements kindly mention MACHINERY.



FOR HIGHER PRODUCTION

MACHINE TOOL DIRECTORY

AUTOMATICS

MANHURIN Single Spindle machines.
 Manuf. De Machines Du Haut-Rhin
 FranceSotasse S.A. Seltzerland
 MASSOVIA-LINSTEDT Vert. Rotary
 Chuck Autos. and Univ. Drum Autos.
 GERMANY
 MASSOVIA HANNS FICKERT G.m.b.H.
 PITTNER ACHE-GRIDLEY 4, 6, and
 8-spindle bar and chucking auto-
 matics.
 PITTNER Maschinenfabrik A.G. Germany

BALANCING MACHINES

DY-NAMIC Static Machines.
 Bear Manufacturing Co.U.S.A.

BORING MACHINES

Single and Multi-spindle machines.
 Ernst KRAUSE & Co.Austria
BORING MACHINES
 Horiz. Floor
 Wide range of traversing column
 machines.
 William ASQUITH Ltd.Halifax

BORING MACHINES

Horizontal Table Type
 Universal machines for precision
 work. Spindle diameter up to
 4 1/2 in.
 Officine Meccaniche CaratiItaly

BROACHING MACHINES

Vert. and Horiz. internal and surface
 broaching
 Oswald FORST G.m.b.H.Germany

CROPPING MACHINES

Portable m/c. up to 1 1/2 in. dia.
 HI-TON Machine Tools Ltd.Birmingham

DIE SINKING MACHINES

Auto. and semi-auto for high pro-
 duction.
 NASSOVIA HANNS FICKERT G.m.b.H. Germany

DRILLING MACHINES

Radial
 Wide range of sizes and capacities
 William ASQUITH Ltd.Halifax

DRILLING MACHINES

Multi-Spindle
 Auto. machines for high production.
 William ASQUITH Ltd.Halifax

DRILLING MACHINES

Turret
 BURGHMASTER machines for high
 production drilling, etc.U.S.A.
 Berg Tool Manufacturing Co.

FILING MACHINES

NASSOVIA HANNS FICKERT G.m.b.H. Germany

GEAR GENERATORS

Spiral Bevel Wheels or Pinions from
 solid in one operation
 FIAT Stabilimenti Grandi Motori...Italy

GEAR SHAPING MACHINES

MAXICUT High Speed and Heavy
 DutyGuildford
 Drummond Bros. Ltd.

GEAR TESTING MACHINES

WADTOOL Production machines.
 Waddington Tools Ltd. Welverhampton

GRINDERS, Projection Form

PETEWELGermany

GRINDING MACHINES

Cylindrical and Universal. Crankshaft
 grinding and Thread grinding
 machines.Germany

GRINDERS, Duplex Surface

For high production flat grinding.
 F. E. Rowland Ltd.Stockport
 (Overseas only)

HONING MACHINES

Hydro-elastic m/c. for highest
 production.Germany

INDUSTRIAL WASHING

MACHINES
 For every need from bolts to buses.
 DAWSON Bros. Ltd.Leeds

JIG BORING MACHINES

MSO WerkeGermany
 Oswald FORST G.m.b.H.Germany

KEYSEATING MACHINES

LATHES, Centre
 George SWIFT & Sons Ltd.Halifax
 COLCHESTER Lathes Co. Ltd. Colchester
 H.E.B.France

LATHES, Copying

MAXIPILOT Hydraulic High Pro-
 duction Machines
 MAXICUT Heavy Duty Copy Turning
 Machines.Guildford
 DRUMMOND Bros. Ltd.

LATHES, Heavy Duty

George SWIFT & Sons Ltd.Halifax
 DEUTSCHLAND G.m.b.H.Germany

LATHES, Multi-Tool

MAXICUT Automatic Heavy Duty
 Machines.Guildford
 DRUMMOND Bros. Ltd.

LATHES, Roll Turning

George SWIFT & Sons Ltd.Halifax
 DEUTSCHLAND G.m.b.H.Germany

LATHES

Surfacing and Boring
 Up to 60 in. swing in gap.
 George SWIFT & Sons Ltd.Halifax

LATHES, Turret

PIREX, PIROFA & PITRA range for
 bar and chuck work.
 PITTNER Dienst G.m.b.H.Germany

LATHES, Wheel

DEUTSCHLAND G.m.b.H.Germany

MILLING MACHINES

Horizontal and vertical types.
 REINHARD BOHLE K.G.Germany

PLANING MACHINES

With oil-hydraulic table operation.
 Adolf WALDRICH Coburg K.G.Germany

PRESSES, Hydraulic

HI-TON Bench and Floor types from
 1 to 300 tons.
 HI-TON Machine Tools Ltd.Birmingham

PRESSES, Auto Indexing

HI-TON (see repetition auto.
 machines.
 HI-TON Machine Tools Ltd.Birmingham

RIVETING MACHINES

HI-TON Portable m/c. up to 25 tons.
 HI-TON Machine Tools Ltd.Birmingham

SAWING MACHINES, Band

NASSOVIA HANNS FICKERT G.m.b.H. Germany

SAWING MACHINES

Cold
 Hydro heavy duty production m/c.
 J. F. OHLERGermany

SAW SHARPENING

MACHINES
 J. F. OHLERGermany

SHEET METAL WORKING

MACHINES
 REINHARDT & ADAM G.m.b.H.Germany

SLOTTING MACHINES

Hydro heavy duty angular slotting.
 Adolf WALDRICH COBURG K.G.Germany

TAPPING UNITS

William ASQUITH Ltd.Halifax

TESTING MACHINES

Hardness, Tensile, Compressive,
 Bending, Shearing and Folding Tests.
 Otto WOLPERT-WERKE G.m.b.H.Germany

THREAD CUTTING

MACHINES
 High Speed Thread Peeling Machines.
 Adolf WALDRICH COBURG, K.G.Germany

THREAD ROLLING

MACHINES
 PITCHMASTER for high tensile steel.
 HI-TON Machine Tools Ltd.Birmingham

TRANSFER MACHINES

Complete installations for mass
 production needs.Halifax
 William ASQUITH Ltd.

TUBE BENDING MACHINES

For quantity production and heavy
 duty bending up to 12 in. dia.
 Chamberlain Industries Ltd.London

Write to-day for further details on any of the above mentioned machines in which you are interested.

Sales & Service for ...


DRUMMOND-ASQUITH

the British Isles

DRUMMOND-ASQUITH (SALES) LTD., KING EDWARD HOUSE, NEW ST., BIRMINGHAM

*Phone: Midland 3431 (7 lines) *Grams: Maxishape, B'ham. Also at LONDON: Phone: Trafalgar 7224 (5 lines) and GLASGOW: *Phone: Central 0922

When answering advertisements kindly mention MACHINERY.




*for rapid and accurate grinding of
cylindrical, tapered and profile work*

M.S.O. fully hydraulic semi-automatic production grinding machines, type FH, are extremely simple to operate. The automatic grinding cycle is controlled by a single lever and if required the "Precimatic" grinding gauge can be supplied to control sizing. An hydraulic form dressing attachment, seen clearly in the illustration above, is a further item of equipment of specific value when the profiling of grinding wheels is required.

The arrangement above is for grinding the journals of a small automobile crankshaft, employing several profiled wheels.

These M.S.O. Type FH machines are built in a wide range of sizes for grinding by longitudinal or plunge-cut methods. Write today for details, mentioning the type and size of work in which you are interested.



Sales & Service for . . .

DRUMMOND-ASQUITH


. . . the British Isles

DRUMMOND-ASQUITH (SALES) LTD., KING EDWARD HOUSE, NEW ST., BIRMINGHAM


'Phone: Midland 3431 (7 lines) 'Grams: Maxishape, B'ham. Also at LONDON: Phone: Trafalgar 7224 (5 lines) and GLASGOW: 'Phone: Central 0922

When answering advertisements kindly mention MACHINERY.


IF294



Hi-Ton "B" Type 2-ton Bench Press.



Hi-Ton 75-ton Press equipped with hydraulically operated loading equipment enabling bars to be loaded onto the straightening equipment outside the throat area of the machine.



Hi-Ton Indexing Table Machine with two down stroking rams each of 15 tons capacity




The modern HYDRAULIC PRESS


for a wide variety of applications from one ton up to 300 tons capacity

All Hi-Ton Hydraulic Presses are designed to give any required pressure from zero to the maximum of the press, the pressure being predeterminable by an adjustable pressure control valve. All types are entirely self-contained and in the case of the presses from 2 tons upwards, the upper half of the body forms the oil reservoir and houses the pump which is completely immersed in this sump. These presses are operated by a light, sensitive foot control lever (hand control is optional), a gate being fitted for cases where it is necessary to maintain full pressure for short periods. A direct reading pressure gauge graduated in tons on the ram indicates the pressure being applied to the work.


Write to-day for details of Hi-Ton Presses and mention the type of presswork application in which you are interested.



Hi-Ton 150-ton Open Throat Drawing Press.



Hi-Ton HTR.20 Riveting Unit consisting of pump unit and cylinder assembly.



Hi-Ton 100-ton Planishing Press.

Sales & Service for . . .

DRUMMOND-ASQUITH

. . . the British Isles

DRUMMOND-ASQUITH (SALES) LTD., KING EDWARD HOUSE, NEW ST., BIRMINGHAM

'Phone: Midland 3431 (7 lines) 'Grams: Maxishape, B'ham. Also at LONDON: Phone: Trafalgar 7224 (5 lines) and GLASGOW: 'Phone: Central 0922

When answering advertisements kindly mention MACHINERY.

MACHINERY is registered as a newspaper at the General Post Office and the name is a registered trade mark

Published every Friday by
The Machinery Publishing Co., Ltd.

© The Machinery Publishing Company, Limited, 1958. All rights of reproduction and translation reserved by the publishers by virtue of the Universal Copyright and International Copyright (Brussels and Berne) Conventions and throughout the World
Price 1/3

LESLIE R. MASON
Managing Director

CHARLES H. BURDER
Editor

EDITORIAL OFFICE

REGISTERED OFFICE, SMALL AND CLASSIFIED
ADVERTISEMENTS DEPARTMENT AND ENQUIRY BUREAU

CLIFTON HOUSE
83-117 EUSTON ROAD
LONDON, N.W.1.

Telephone: Euston 8441/2
Telegrams: Machtool, Norwest, London

HEAD OFFICE

SUBSCRIPTION, ADVERTISEMENT, SERVICE,
PHOTOGRAPHIC, ACCOUNTS AND BOOK DEPARTMENTS

NATIONAL HOUSE
21 WEST STREET
BRIGHTON, 1.

Telephone:
Brighton 27356
(3 lines)



Telegrams
Machtool,
Brighton

NEW YORK:
93, Worth Street

PARIS:
15, Rue Bleue

SUBSCRIPTIONS.—Inland and overseas, 52 shillings per annum, post free. Cheques and Money Orders should be made payable to the Machinery Publishing Co., Ltd.

ADVERTISEMENTS.—Copy for displayed advertisements, if proofs are required, should reach the Brighton office 21 days in advance of publication. Rates on request.

Small (classified) advertisements can be accepted, space permitting, at the London office up to Saturday morning for publication on the following Friday. For rates, see p. 153.

Blocks are held at advertisers' own risk; no responsibility for loss is accepted by the publishers.

MANUSCRIPTS FOR BOOKS covering all branches of engineering production will receive careful consideration and should be sent to the Manager, Book Dept., MACHINERY, National House, 21 West St., Brighton, 1.

MACHINERY

A JOURNAL OF METAL-WORKING PRACTICE
AND MACHINE TOOLS

Vol. 92, No. 2378

June 13, 1958

COPIES PRINTED.....11,500 per week

CERTIFIED DISTRIBUTION.....11,376 per week

CERTIFIED PAID DISTRIBUTION.....10,566 per week

CONTENTS

Editorial

Precision Sand Casting 1371

Principal Articles (For Abstracts see next page)

The Production of Ball and Roller Bearings 1372
Tightening and Tensile Tests on Joints Assembled with Bolts
Threaded BSW, BSF, UNC and UNF 1381
East German Machine Tools at the Leipzig Fair 1395
Conference on Compressed Air as an Aid to Improving
Productivity 1401
Blanking "Number" Anodes from Thin Strip 1407
Holbrook Precision Mould Maker's Lathe 1410
Round Olympia with a Camera 1413
New Equipment at the Gauge and Tool Exhibition 1416

Short Articles

Bedford Mobile Gauge Inspection Unit 1412

News of the Industry

Manchester and District 1421
Osborn's Precision Castings Foundry 1422
New Laboratories for P.E.R.A. 1423
Classified Advertisements 153
Index to Advertisers 187

CONDITIONS OF SALE AND SUPPLY.—MACHINERY is sold subject to the following conditions:

That it shall not, without the written consent of the publishers first given, be lent, resold, hired out or otherwise disposed of by way of trade except at the full retail price of 1s. 3d. and, that it shall not be lent, resold, hired out or otherwise disposed of in a mutilated condition or in any unauthorized cover by way of trade; or affixed to or as part of any publication or advertising literary or pictorial matter whatsoever.

[p. 1369] 1

Abstracts of Principal Articles

The Production of Ball and Roller Bearings P. 1372

In this eighth article in a series describing some of the methods and equipment employed by the Hoffmann Manufacturing Co., Ltd., Chelmsford, Essex, the production of ball and roller races in the "B" factory is discussed. Large races, up to 72 in. diameter, are machined from forged rings, and the company has recently installed a number of large Acme-Gridley 4-spindle automatics for machining races from tube up to 7½ in. diameter. Fay high speed automatics, driven by 50-h.p. motors, are employed for machining the tracks in races up to 9½ in. diameter, using carbide-tipped negative rake form tools. Races exceeding 14½ in. diameter, up to the maximum produced, are machined complete on Swift type 16 SV 5 lathes, and are subsequently ground on Churchill 48-in. machines. In the extensive heat treatment department, low-carbon races are hardened by pack- and gas-carburizing, and for the latter process, the company have installed a large gas-fired, radiant-tube, Birlec pit-type furnace. A carburizing atmosphere is provided by a Birlec endothermic gas generator, the output of which is enriched with butane gas. The majority of the furnaces in the shop are regulated from a centralized control room. (MACHINERY, 92—13/6/58.)

Tightening and Tensile Tests on Joints Assembled with Bolts Threaded BSW, BSF, UNC and UNF P. 1381

The static strengths of BSW, BSF, UNC and UNF bolt-nut combinations have been compared under various conditions of tightening, with a particular view to checking the suitability of UNF threads for general use. Tests were carried out under single and repeated tightening, and some of the nuts were bored out to simulate conditions resulting from the use of an oversize tapping drill. While the UNF combinations were at least as strong as the other types for a single tightening, many of them failed by thread bending and stripping and they were not so resistant to repeated tightening as the other types. For satisfactory use of UNF combinations, tightening must not be sufficient to cause yield. It is suggested that UNC threads would generally be preferable in heavy applications where close control of tightening is not possible. In changing over from Whitworth to Unified threads, each case should be considered on its merits, and UNF should not be taken as an automatic replacement for BSF. (MACHINERY, 92—13/6/58.)

Conference on Compressed Air as an Aid to Improving Productivity P. 1401

At a conference which was organized recently by the Cornwall section of the Institution of Production Engineers, papers were read on subjects ranging from the design of compressors to the use of compressed air for machine operation and gauging. In connection with the latter, this article includes an example

of a multi-dimensional gauging unit built into an in-line transfer machine. Descriptions are also given of the use of pneumatic equipment to reduce operator fatigue and details are included of a 24-station, air-operated, fully-automatic machine for assembling small parts used in the radio industry. (MACHINERY, 92—13/6/58.)

Blanking "Number" Anodes from Thin Strip P. 1407

"Number" anodes from 0 to 9 are required for all-electronic numerical indicator tubes for computers and their production presents unusual problems. These numbers are made from 0.005-in. thick strip, and the proportions must be such as to permit clear reading when they are superimposed in a stack. For this reason, the width of metal forming the outline of a number may be as little as 0.007 in. It is also necessary that the various numbers should have approximately equal surface areas. In this article are described press tools which have been developed for blanking these numbers. Only very small clearance is permissible between the punches and dies, and it is stated that the value is of the order of 0.0002 in. At the final stage in machining the die apertures, the previously hardened punches were employed as broaches. (MACHINERY, 92—13/6/58.)

Holbrook Precision Mould Maker's Lathe P. 1410

The lathe described in this article has been developed from the company's type 15/20 machine, and particular attention has been paid to versatility. A slow-speed unit is provided for the headstock, and other features include a pitch variator, hydraulic copying slides, internal and external thread milling heads, also internal and external grinding attachments complete with diamond wheel dressers. A rotating master, driven from the headstock spindle, can be employed when it is required to produce parts of non-circular form. (MACHINERY, 92—13/6/58.)

Contributions to MACHINERY

If you know of a more efficient way of designing a tool, gauge, fixture, or mechanism, machining or forming a metal component, heat treating, plating or enamelling, handling parts or material, building up an assembly, utilizing supplies, or laying out or organizing a department or a factory, send it to the Editor. Short comments upon published articles and letters on subjects concerning the metal-working industries are particularly welcome. Payment will be made for exclusive contributions.

IN FORTHCOMING ISSUES

The new Vauxhall press shop—Gauges for checking workpieces with conical ends—The production of precision studs for severe duties.

Precision Sand Casting

The advantages which can be gained by casting many parts hitherto made by other methods, such as forging and machining, or machining from the solid, provided that the desired physical properties, dimensional accuracy, and surface finish can be obtained, are now increasingly recognized. In recent years, moreover, there have been numerous advances in the field of precision casting which have enabled greatly improved results to be achieved in various directions. For example, certain parts are now successfully cast in semi-permanent moulds made from high-grade refractory, and there has been great activity in connection with expendable mould processes based on the use of sand with an organic binder (shell moulding) or refractory with an inorganic binder (investment casting). Reports have recently been received, moreover, concerning what may be regarded as an interesting combination of the shell moulding and carbon dioxide techniques, whereby fairly thick shells of great strength are produced. These various methods undoubtedly offer important advantages within their particular spheres of application, but their wider adoption has been restricted by reason of the cost of tooling or mould materials. Commenting on the prevailing situation, in the introduction to a paper which he presented at the conference on Technology of Engineering Manufacture, organized by the Institution of Mechanical Engineers, Mr. J. S. Turnbull, A.M.I.Mech.E., expressed the following opinions: "there are in industry today countless thousands of cases where components are machined from forged or extruded bar, which could have been made as castings requiring considerably less machining. In an age when machining costs are high and skilled labour is scarce, it is of the utmost importance that methods of liquid forming should be used effectively with a view to reducing or eliminating man-machine hours."

In this connection it was pointed out that, owing to the difficulties of casting steel by the methods hitherto available, the output of castings in this material is only about 300,000 tons, whereas the annual production of steel is now of the order of 22,000,000 tons. It was also suggested that if any substantial change in this situation is to be brought about, it will be necessary to bridge the gap between sandcasting and investment casting, so as to incorporate "the best features of each in

order to obtain solid castings associated with the best possible economy of process operation."

The problem must be considered under two main headings, namely the supply of molten metal and the provision of satisfactory moulds, and after drawing attention to the difficulties associated with steel melting in an investment foundry, Mr. Turnbull advocated that "the precision foundry of the future should be built into the existing foundry or, alternatively, into any other organization where liquid steel is available in bulk." He then went on to discuss the Alphax process, which has been developed by his company to overcome some of the limitations associated with other methods of precision casting.

For this process, silica sand is not satisfactory, and zircon or other suitable material is employed in conjunction with a water-base, high-temperature phosphate binder. The sand and binder are mixed to a putty-like consistency, and it is one of the virtues of the process that moulding can then be carried out by hand or pneumatic ramming, with simple wood patterns, where only small quantities are required, by hydraulic pressing, with metal or plastics patterns, or by a combined core blowing and hydraulic pressing technique. The adaptability for both large and small outputs, characteristic of normal sand moulding, is thus preserved. Hydraulic pressures up to 5 tons per sq. in. are employed, and where the blowing and pressing procedure is followed, a considerable degree of mechanization can be achieved.

Green moulds may be allowed to harden in air, but are normally heated in a low-temperature oven, or subjected to the action of ammonia gas, which ensures rapid hardening, and are assembled with a high-temperature adhesive in preparation for firing. For the latter operation, temperatures up to 750 deg. C. are employed, to purge the moulds of any organic matter and ensure adequate permeability. Casting is carried out with the moulds hot, the normal temperature range being 200 to 500 deg. C., and this procedure offers the advantages that the air in the cavities is already expanded, and solidification of the castings is much slower.

As would be expected from this brief description, the costs of castings made by this method are intermediate between those associated with the investment and orthodox sand processes, but the

(Continued on page 1424)

The Production of Ball and Roller Bearings

Methods Employed by the Hoffmann Manufacturing Co., Ltd.

In earlier articles in *MACHINERY*, 91/664—20/9/57, and 91/1012—1/11/57, reference was made to some of the methods employed by the Hoffmann Manufacturing Co., Ltd., Chelmsford, Essex, for producing ball-bearing races on their No. 1 line. This line, it may be recalled, is devoted to races up to 4 in. diameter, in sizes for which there is a large demand. Two subsequent articles (92/640—21/3/58, and 92/779—4/4/58) were devoted to ball and roller cage manufacture, in a large specialized department concerned entirely with this work. Here, some of the operations on larger races, up to the maximum size produced by the company, are considered.

The Chelmsford works comprise three factories, designated "A," "B" and "C," and "A" factory is devoted to the production of balls and rollers (*MACHINERY*, 90/14—4/1/57, 90/680—29/3/57, and 90/1256—7/6/57). The No. 1 line is installed in "C" factory, and "B" factory, with which this article is concerned, is responsible for the manufacture of races for bearings which are required in smaller quantities. These bearings

include standard types from 1½ in. to 26 in. diameter, and special types up to 72 in. diameter. All roller races, it may be noted, are produced in "B" factory, which also houses the large centralized heat-treatment shop, a forging shop, and a special department for the manufacture of grinding wheels, for use in the various departments.

Races of the smaller sizes are produced from high-carbon steel bar and tube, but the larger sizes are machined from forged rings of high- and low-carbon steel. Rings of 3½ in. to 7½ in. diameter are made from bar, by hot upsetting on horizontal forging presses, and a proportion of the forged blanks required is produced on Massey hammers and a Rhodes press. Larger rings are obtained from specialist suppliers. The equipment of the ring forging shop includes two National machines (Buck & Hickman, Ltd.) of 3 in. and 5 in. capacity, and three Covmac machines (Coventry Machine Tool Works, Ltd.) of 3½ in. and 6 in. capacity. A view of the large Covmac machine, in operation, is given in Fig. 1.

On all these machines, the method of forging rings is the same, and 2-stage dies are employed. In Fig. 1, the Covmac machine is set up for forging rings of 7½ in. diameter and 1½ in. wide, with a bore-diameter of 5½ in., from 4½-in. diameter bar. The bars are heated in gas-fired furnaces installed at each side of the machine, and two rings are forged at each heat. A heated bar is taken from the furnace with the aid of an overhead hoist, and is placed on the air-operated lifting table seen in front of the machine. This table is provided with rollers, to facilitate feeding the bar between the split dies.

For the first stage, the bar is inserted in the lower station, against a




Fig. 1. This Large Covmac Machine, with a Capacity of 6 in., is Employed for Producing Rings From Bar, by Hot Upsetting, in Two Stages

stop, and when the press is operated, it is gripped between the dies, and the end is upset to form a plain flat disc. The work is then raised to the second station, at which the central portion, integral with the bar, is punched out. In this instance, the die-aperture is a sliding fit for the bar, to enable the latter to be ejected. On the return stroke, the ring is released into a chute, which guides it into a well in the shop floor, whence it is withdrawn to cool. Meanwhile, the bar is returned to the lower position, in readiness for the next stage. At this set-up two rings are forged in 45 sec. The smaller machines are somewhat faster, and three rings can be forged per heat. When the bar-length is reduced to such an extent that it cannot be handled conveniently, it is electrically welded to a fresh length, and forging is continued. The ring containing the weld, and those adjacent to it, are scrapped.

LARGE-DIAMETER TUBE

Comparatively recently, the economic advantages of producing upset rings, within the size-range indicated, have been somewhat diminished by the availability of high-quality British-made tube in the requisite sizes, up to 7½ in. diameter. This tube is sufficiently accurate and parallel for machining on automatic multi-spindle lathes, and its introduction has had a far-reaching effect on the firm's production policy. Hitherto, the machines in "B" factory have been arranged in groups according to function, but extensive reorganization is now in progress, in order that the full benefits may be gained from the use of tube for race production. As a part of this programme, the company is laying-down a No. 3 line, which will be generally similar to the No. 1 line, earlier described. In this connection, a number of large 4-spindle type RB. Acme-Gridley automatics, with a capacity of 7½ in. diameter, have already been installed. Further reference will be made to these machines, one of which is shown in Fig. 2. As a result of these




Fig. 2. One of the Large Acme-Gridley 4-spindle Automatics, Recently Installed for Machining Races from Tube up to 7½ in. Diameter

developments, the forging machines will shortly become obsolete, and will be removed to make way for the new No. 3 line.

GENERAL PROCEDURE

The general procedure for machining and heat-treating the races here considered, varies considerably according to the design and size of the bearing, also with the specification of the material, and the form in which it is initially received. For example, although high-carbon steel tube is, as already indicated, available in sizes up to 7½ in. diameter, forged rings are nevertheless required for a proportion of races over 3½ in. diameter, both in high- and low-carbon steel. High-carbon steel rings produced by the company are first ground to remove flash left on the periphery by the forging dies, and are then annealed. If necessary, depending on the condition of the dies, any flash on the end face is then removed by turning. For the low-carbon rings, the procedure is generally similar, except that the work is not annealed.

A proportion of the forged rings within the size range at present produced by the company is also obtained from outside suppliers, and high-carbon rings in this category are received already annealed. These rings are hardness tested, and, if necessary, are re-annealed before machining. Larger bought-




Fig. 3. Typical First Stage Set-up on a Drummond No. 1 Maxicut Lathe, for Machining Forged Rings. Wimet S.58 Carbide-tipped Tools are Employed

out rings of high-carbon steel are stress-relieved after the first rough machining stage, during which they are machined all over, and are subsequently finish machined, hardened, and ground. Low-carbon rings of 10 in. diameter and over are normalized after they have been rough machined, and are then shot blasted, finish machined, hardened, and ground.

On forged rings up to 9½ in. diameter, the initial rough machining is carried out in two stages on Drummond No. 1 Maxicut multi-tool lathes. At the first stage, the work is machined on the external surface and one face, and at the second, on the internal surface, and the second face. Rings in the size range indicated are finish-machined on 12-in. Churchill-Redman Fay lathes, again in two stages. At the first, the outside surface, one end face, and two corner radii are machined, and at the second, the bore and the remaining end face and radii. The tracks are machined in both inner and outer races, up to 9½ in. diameter, on Fay high speed lathes.

The rough- and finish-machining stages on rings exceeding 9½ in. and up to 14½ in. diameter, are performed on Drummond Maximatic lathes, on which plain roller races, without tracks, are also finish machined, complete. Tracks in races from 9½ in. up to 14½-in. diameter are machined

on Jones & Lamson lathes (Charles Churchill & Co., Ltd.). Larger rings, of more than 14½-in. diameter, up to the maximum size produced, are machined in a "specials" section, equipped with Herbert No. 9A and large Swift turret lathes, also Jones and Lamson lathes. The Fay high-speed lathes, it may be noted, are also used for machining the tracks in races produced from tube.

A typical first stage set-up on one of the Drummond No. 1 Maxicut lathes, for machining a high-carbon steel forged ring, is shown in Fig. 3. The work is gripped internally by an air operated chuck, and Wimet grade S.58 carbide-tipped tools are employed. For the component illustrated, the front cross-slide tool machines the external diameter to 6-138/6-146 in., taking a cut approximately 0.05 in. deep. An auxiliary tool, also mounted in the front tool-post, chamfers the external corner. Meanwhile, the rear cross-slide tool faces the outer end to an overall width of 1.419 in. A feed of 0.013 in. is employed, and the floor-to-floor time is 1 min. Generally similar tooling is employed for the second stage, at which the opposite side is faced to give an overall width of 1.368/1.378 in., and the bore machined to 4.671/4.681 in. diameter.

MACHINING RACES FROM TUBE

The working zone of one of the large 4-spindle Acme-Gridley automatics, set up for machining races from 4½-in. diameter, 3½-in. bore, high-carbon steel tube, is shown in Fig. 4. At this set-up, all the tools, including those for parting off, are carbide tipped, and the feed of the main tool slide is 0.0097 in. per rev.

At station 4, the stock, previously rough turned externally at station 3, is fed out to a stop, and is rough bored to within 0.063 in. of finished size, with a boring-bar tool on the main slide. This tool is tipped with Wimet S.58. At the same station, the rear end of the work is broken down, and chamfered, and parting off is begun with a Wimet XL 3 cross-slide tool, at a feed of 0.002 in. per rev. This tool also chamfers the front corner of the next component.

Subsequently, at station 1, the external surface is finish turned to 4.510/4.514 in., with a knee tool on the main slide, and the internal surface is finished to 3.762/3.766 in. with a boring-bar tool

similar to that employed at station 4. At the same station, a Wimet XX form tool, mounted on the cross-slide, is fed in to machine the external $\frac{1}{8}$ -in. corner radii. The outer end is finish faced at station 2, with a cross-slide tool which is fed in at 0.002 in. per rev., and a 45-deg. chamfer is formed on the inner corner with a tool on the main slide. At station 3, the work is parted off to a width of 1.078/1.082 in., with a Wimet XL.3 cross-slide tool $\frac{1}{8}$ in. wide, and the stock is rough turned, for the next component, with a knee tool. Carbide tools have proved satisfactory for parting off at this set-up.

TRACK MACHINING

As already mentioned, the high speed Fay automatics are employed for machining the tracks in races produced from tube and forged rings, in sizes up to 9 in. diameter. These machines are driven by 50-h.p. motors, and both ball and roller tracks are machined in inner and outer races, using carbide-tipped, negative rake form tools. Swarf disposal presents certain problems, as it is impractical to provide chip breaker grooves, and separately attached chip breakers have been found unsatisfactory, since the swarf tends to jam beneath them. The rate of metal removal is high, and as the swarf takes the form of long continuous




Fig. 5. Set-up for Machining the Ball Track in an Outer Race on a Fay Automatic, Using a Negative Rake Carbide-tipped Form Tool

ribbons, with very little curl, it is bulky, and the machines must be cleared repeatedly.

A typical set-up on one of these machines, for forming the ball track and internal corner radii in the outer race machined with the Acme-Gridley set-up described, is shown in Fig. 5. The work is inserted, against a back-stop, in an air-operated collet, with the parted-off face outwards, and is run at 482 r.p.m. When the automatic cycle is started, the tool slide is rapidly advanced, stopped in the required position, and then swung towards the rear to apply the Wimet XL 3 tools at a feed of 0.002 in. per rev.

The front tool is used to finish turn the parted-off face, and the rear tool is profiled to machine the track and the two internal corner-radii, simultaneously. At the end of the pass, the tool-slide is returned to the forward position, and then rapidly withdrawn. For inner races, the tooling arrangements are generally similar, except that the form and facing tools are transposed, and the work is gripped internally. A soluble oil coolant is employed.




Fig. 4. Close-up View of the Working Zone of One of the Large Acme-Gridley Automatics, Set Up for Machining Outer Races from 4½-in. Diameter Tube




Fig. 6. Machining a Large Race, of 27.1 in. External Diameter, on a Swift Type 16 SV 5 Lathe. These Machines are Employed for Races up to 50 in. Diameter

MACHINING LARGE RINGS

The larger rings, exceeding 14½ in. diameter and up to the maximum size produced, are machined by orthodox turning methods. In Fig. 6 is shown a typical set-up for a large roller outer race, on a Swift type 16 SV 5 lathe. When finish-machined, the component has an external diameter of 27.099/27.103 in., an internal diameter of 24.740/24.744 in., and a width of 3.540/3.544 in. The work is held in a 3-jaw chuck, with stepped jaws, and in order to minimize distortion, radial pressure is kept to a minimum, and flat clamps are applied to the end face. For the larger rings, face-plates of various sizes are employed, the largest of which has a diameter of 58 in.

For the component seen in Fig. 6, the low-carbon steel forged ring is approximately ¼ in., oversize on all four surfaces. Wimet S. 58 carbide-tipped tools are employed, and at the roughing stage the work is run at 40 r.p.m., and cuts approximately ⅜ in. deep are taken. Finish machining, to the dimensions indicated, is

carried out at 60 r.p.m., with cuts approximately 0.02 in. deep. These lathes are also employed for machining the tracks in large ball races, for which high-speed steel form tools are used, and the corner radii on the edges of the tracks are machined at a separate operation.

HEAT TREATMENT

Heat-treatment of all rings in the categories here considered is carried out in the large shop already mentioned. For initial annealing, high-carbon forged rings, produced by the company, are subjected to an isothermal heat-treatment in Hoffmann gas-fired furnaces. They are raised to the austenitizing temperature of 820 deg. C., and are then allowed to cool slowly to the soaking temperature of 710 deg. C. On completion of the soaking period, the furnace is shut-down, or the work is withdrawn and allowed to cool in air. High-carbon upset forged blanks, of 1 in. to 10½ in. diameter, are annealed in a similar manner. The larger high-carbon rings, after initial rough machining, are stress-relieved at 650 deg. C. to 700 deg. C., for 1 hour per sq. in. of cross-sectional area. Low-carbon rings, of 10 in. diameter and over, are normalized, after rough machining, at 950 to 1,000 deg. C., for 1 hour per sq. in. of section.

The hardening of high-carbon steel races, after they have been finish machined, is carried out at temperatures of 828 deg. C. to 840 deg. C., accord-




Fig. 7. Hoffmann Rotary Furnaces, of the Type Shown, are Employed for the Heat-treatment of the Smaller Races, also Balls and Rollers




Fig. 8. Special Mandrels, and Submerged-jet Quenching Heads, are Employed for Hardening the Larger Races, as Here Shown

ing to the section weight, and, for this purpose, several different methods are employed. For the smaller races, such as those produced from bar and tube, which are of light section in relation to diameter, a salt-bath treatment, generally similar to that performed in the No. 1 line (MACHINERY, 91/676—20/9/57) is employed. Small races, of comparatively heavy section, are hardened in Hoffmann gas-fired, thermostatically controlled, rotary furnaces of the type shown in Fig. 7, which are also employed for the heat-treatment of balls and rollers. Each of these furnaces incorporates a power-driven, spirally-grooved, nickel-chromium alloy drum, which feeds the work through the heating zone. The rate of rotation can be varied, so that the duration of the heating cycle may be adjusted, as required.

At the delivery end of the drum, the heated components fall through an enclosed vertical chute into an oil quench tank arranged below the furnace, where they are guided into the end of a long drum of perforated metal. This drum rotates

slowly, and is slightly inclined, so that the work is gradually fed through the quenching medium, to the opposite end. In this way, thorough cooling is ensured. At the delivery end of the drum, the work is discharged into a wire basket, placed on the floor of the tank. A proportion of small work is also hardened in shaker-hearth furnaces. The remainder of the races in the size-range here considered are heated in rotary-hearth furnaces, and all the high-carbon steel workpieces are quenched in oil.

As a precaution against distortion, the larger races are placed on quenching arbors. Each arbor comprises a pair of star-shaped members, which are stepped on the outer ends of the arms, to fit the bore and end faces of the work. These members are inserted in opposite ends of the race, and are held loosely together on a central pin, whereby the assembly is lowered into the quenching tank. To ensure rapid and even cooling, the quenching medium is agitated by means of submerged jets. The quenching heads are of various sizes, and are used interchangeably, according to the diameter of the work.

A typical head comprises a manifold ring, with a series of vertical limbs, equal in number to the arms of the star-shaped members. There are uniformly spaced holes in these vertical limbs, all facing in the same direction, through which the quenching medium is pumped, so that a powerful



Fig. 9. Typical Line of Hoffmann Pack-carburizing Furnaces, Showing Rail Trolleys Used to Facilitate Work Handling

swirling action is obtained. Quenching is carried out by lowering the work and mandrel assembly over the head, so that the vertical limbs enter the spaces between the arms of the star-shaped members. Heads of this type are also used with water, which is employed as the quenching medium when hardening carburized low-carbon steel races. A typical water quench set-up is shown in use in Fig. 8, and the swirling action resulting from the submerged jets may clearly be seen. As the mandrels are only in contact with the heated work for a short period before immersion, they remain cool enough for handling without tongs.

CARBURIZING

All low-carbon races which are carburized are treated to provide a controlled case depth from 0.020 in. to 0.400 in. The depth is controlled by the duration of the treatment, which, for pack-carburized work, ranges from 6 to 150 hours. Pack carburizing is carried out in Hoffmann gas-fired furnaces, some of which are seen in Fig. 9. Handling and loading are facilitated by the rail-trolleys, on which the packs are transferred, after treatment, to a cooling shed, located at the end of the main shop.

After they have cooled, the packs are emptied,



Fig. 10. This Large Pit-type Birlec Furnace is Employed for Gas-carburizing Low-carbon Steel Races. A Typical Charge is Seen Above the Water-jacketed Cooling Pit

and the work is subsequently normalized. This latter treatment is carried out in gas-fired furnaces at 900 deg. C., in an oxidizing atmosphere, for 30 to 60 min., according to the size of the components, and the weight of the charge. At the end of this period, the work is withdrawn and allowed to cool in still air, after which it is shot blasted, hardened, again shot blasted, and tempered.

Gas carburizing is also employed, and for this purpose the company has installed the large pit type radiant-tube Birlec furnace seen in the foreground in Fig. 10, which also shows the two associated cooling pits. The pit nearest the furnace has a water jacket, and an air-circulating fan in the bottom, to promote rapid cooling, and is provided with a sand-seal cover so that the interior can be isolated from the atmosphere. The second pit is not water cooled, and is open to the atmosphere at the top and bottom. A fan in the bottom provides a strong upward current of air. The work carriers, one of which is seen in use in Fig. 10, are of nickel-chromium steel, and are handled with the aid of a gantry crane.

The carburizing furnace is fired by producer gas, which is passed through carbonate of lime in order to remove sulphur, and thus avoid damage to the nickel-chromium steel radiant tubes. A carburizing atmosphere is provided by a Birlec gas generator, in which town's gas and air, in a 2:1 ratio, are heated electrically to 1,100 deg. C. This atmosphere is enriched by the controlled addition of butane gas, and the resulting mixture is fed to the furnace, in which a temperature of 950 deg. C. is maintained. After the necessary carburizing period, the work is transferred to the water-jacketed cooling pit, and when it has cooled, is returned to the carburizing furnace for normalizing. A carburizing atmosphere is again maintained, in order to prevent carbon loss, and the treatment, for a full charge, occupies approximately 2 hours. In this instance, the work is cooled in the second of the two pits mentioned, with forced draught.

The hardening of all carburized races is carried out by heating them in Hoffmann gas-fired furnaces, at 760-790 deg. C., according to the section-weight, and the specification of the material. As already indicated, they are quenched in water on mandrels, with the aid of submerged-jet heads of the type described in connection with the quenching of high-carbon components in oil. All hardened races, whether carburized or made from high-carbon steel are then tempered to give a Brinell hardness ranging from 825 to 900. For this purpose, Hoffmann, Wild-Barfield, and Homo (Integra Leeds & Northrup) electrically-heated, forced air circulation, ovens are employed, in




Fig. 11. One of Several Banks of Instruments in the Centralized Control Room for the Heat-treatment Shop. Coloured Light Signals Indicate Whether the Furnace Temperature is High, Correct or Low, and are Duplicated at the Furnaces

which the high-carbon components are heated to 125 deg. C., and the carburized components to 150 deg. C., followed by natural cooling in air.

CENTRALIZED CONTROL SYSTEM

With a few exceptions, such as the pack- and gas-carburizing units, all the furnaces in the heat-treatment shop are automatically regulated from a centralized control room, part of the instrumentation of which is shown in Fig. 11. Devised by the company, the system incorporates multi-channel recorder type equipment by Cambridge Instrument Co., Ltd., George Kent, Ltd., and Electroflo Meters Co., Ltd. In Fig. 11, a typical bank of 2-channel panels is seen, and beyond the far end there is a number of 6-channel panels. Each 2-channel panel incorporates a set of signal lamps, a temperature indicating instrument, a recorder, and two temperature setting controls. Each channel corresponds to one furnace, and the indicating and recording equipment is automatically switched from one channel to the other, at short pre-

determined intervals, so that virtually-continuous indications and records are obtained for both furnaces. Similarly, 6-channel panels serve six furnaces.

The signal lamps on each 2-channel equipment comprise two sets of three, and each set corresponds to one furnace. These lamps are red, white, and green, and are illuminated automatically to indicate whether the temperature of the furnace concerned is "high," "correct," or "low." These light signals are duplicated at the furnaces, two of which are tended by each operator, and two attendants in the control room are responsible for maintaining correct temperature. A separate temperature setting control is provided for each furnace, in the form of a calibrated adjustable dial. Each furnace is provided with two thermocouples, one of which serves the recorder equipment, and the other, the temperature control equipment and the signal lamps. The furnaceman enters, on a card, all particulars of the heating schedule required. This card is handed in at the control

room, where the attendants ensure that the requirements are met. The cards are subsequently filed with the instrument records, for each batch.




Fig. 12. Races of 9 in. to 18 in. Diameter are Ground Externally on a Mandrel, Between Centres, on a Churchill Machine, as Here Shown

GRINDING

The smaller and intermediate sizes of races in the range here discussed are ground by methods which are generally similar to those employed in the No. 1 line, and the first operation after hardening provides for grinding to width. For this purpose, Blanchard and Gardner face grinding machines are employed, and the races are then ground externally on Cincinnati centreless machines. Internal grinders of various types, including Bryant and U.V.A., are employed for the bores, and Bryant, Heald, and Van Norman machines are among those employed for grinding tracks.

Larger races, from 9 in. to 18 in. diameter, which cannot conveniently be ground externally by the centreless method, are mounted between centres, on mandrels, as shown in Fig. 12. At this set-up, on a 36-in. Churchill cylindrical grinder, a 30-in. diameter grade BA 463 J5 VBLU Carborundum wheel, 3 in. wide, is run at 730 r.p.m. The races are clamped axially by end-plates on a 2-in. diameter mandrel, which accommodates six at a time, and are aligned with the aid of a dial-gauge before the end-plates are tightened fully. Driven at 90 r.p.m., against the rotation of the wheel, the work is ground to 9.8425 in. diameter, to limits of $+0.000$ in., -0.0007 in.

All grinding operations on large races, such as those machined on the Swift type 16 SV 5 lathe, mentioned earlier, are performed on Churchill

48-in. machines, and a typical set-up is given in Fig. 13. The component shown is an outer race for an angular contact ball bearing, with the following finished dimensions. External diameter, 40.9985 in., $+0.0002$ in., -0.0013 in.; width, 3.7188 in., $+0.000$ in., -0.002 in.; track diameter (nominal), 38.5 in.; and track radius, for 2-in. diameter balls, 1 in., $+5$ per cent, $+7\frac{1}{2}$ per cent. The track diameter, it may be noted, is quoted as nominal, because the inner race track is ground to suit the outer, to give a controlled diametral clearance of 0.0268 in., ± 0.0005 in. Despite their large size, the ovality of these races does not usually exceed 0.0005 in.

As at the machining stage, the work is located in stepped jaws and clamped axially, in order to minimize distortion, and the locating faces of the jaws are ground in position on the faceplate. A variety of different wheels is employed, for roughing and finishing operations on external and internal surfaces. The wheels for internal grinding are of 9 in. diameter, and are run at a surface speed of 4,000 ft. per min., whereas those for external grinding are of 12 in. diameter, and are run at a speed of 6,000 ft. per min. Rough internal grinding is performed with Universal grade A 46 L5 wheels, and finish internal grinding with wheels of Hoffmann manufacture. The latter are of the alumina type, grade 60 LM. Carborundum grade BA 463 Aloxit wheels are employed both for rough and finish grinding on the external surfaces. For grinding the external surface, the work is run at 14 r.p.m., and for the internal surfaces, at 20 r.p.m. The wheel spindle is driven by a variable-speed D.C. motor, and a typical total metal removal on a component of this size is 0.06 in. on diameter.

Some further examples of the company's production methods will be described in a later article.




Fig. 13. Grinding a 41-in. Diameter Angular Contact Outer Race, on a Churchill 48-in. Machine

AN ELECTRONIC CLOCK which does not need to be connected to the electric power supply has been developed by the General Electric Co., U.S.A. Stray magnetic fields from the supply mains are picked up by an aerial in the clock, and the induced 60-cycle voltage produced is amplified and fed into a transistor oscillator. The oscillator is designed to have a stable frequency as close as possible to 60 c.p.s., and becomes synchronized with the mains frequency. It is used to control a miniature synchronous motor that drives the clock mechanism. This motor is powered by two mercury cells which have a working life of 18 months. In the event of a power failure, the clock will run for several hours without loss of timekeeping accuracy.

Tightening and Tensile Tests on Joints Assembled with Bolts Threaded BSW, BSF, UNC and UNF

By J. E. FIELD*

Owing to thread stripping failures encountered, under service conditions, with the Unified Fine (UNF) threads, where British Standard Fine (BSF) threads had previously been found satisfactory, it was decided to compare the static strengths of these two types of thread, also of Unified Coarse (UNC) and British Standard Whitworth (BSW) threads, under conditions similar to those found in practice. The fatigue strength of a bolt of given nominal thread form is not much affected by the thread pitch, as has been shown experimentally¹, and, as follows from the theoretical analysis², increased thread load concentration for fine threads tends to be balanced by the corresponding increase in core area of the bolt.

The static tests were carried out on commercial high-tensile bolts (Code R) and appropriate nuts (Code P), subjected to various degrees of tightening when employed as the clamping members of a steel joint.

It is recommended in the British Standards for Precision Hexagon Bolts, Screws, Nuts and Plain Washers, No. 1083:1951 (Whitworth) and 1768:1951 (Unified), that Code R bolts (45/55 tons per sq. in.) should be used with Code A nuts (28 tons per sq. in. minimum, Brinell Hardness Number 120/235 approximately). In these tests, Code P nuts (35/48 tons per sq. in., Brinell Hardness Number 152/235 approximately) were used, in order to narrow the range of variation of nut hardness, and because it was thought, on the basis of previous experience, that nuts near the bottom of the Code A hardness range would be too soft to develop the full strength of Code R bolts, for all types of thread.

Class 2 (Unified) and the corresponding Medium Fit (Whitworth) bolts and nuts were used, these being the classes of fit normally employed in high-grade engineering work. Since it has been found³ that increase of effective diameter clearance causes a serious decrease of thread stripping strength, any deficiencies of fine threads in this respect would be even more pronounced with Class 1 or Free Fit threads.

The sizes chosen were $\frac{3}{8}$ in., $\frac{1}{2}$ in. and $1\frac{1}{2}$ in., increasing by a factor of 2. The diameter/pitch

(D/p) ratio increases fairly regularly with size for all four types of thread, up to $1\frac{1}{2}$ in., except for UNF, where the pitch is constant at $\frac{1}{16}$ in. from 1-in. to $1\frac{1}{2}$ -in. diameter. For this reason, the D/p ratio for $1\frac{1}{2}$ -in. UNF threads is abnormally high (18.0), and it was thought desirable to check the strength of such threads. The D/p ratios for $\frac{3}{8}$ -24.UNF and $\frac{1}{2}$ -16.UNF (equal to 9.0 and 12.0 respectively) are also on the high side of the mean UNF curve of D/p against diameter, and any tendency to thread stripping would be expected to be rather more pronounced in these than in adjacent sizes.

DESCRIPTION OF BOLTS AND NUTS

All the bolts were Code R (45/55 tons per sq. in.), and all the nuts Ordinary, Code P (35/48 tons per sq. in.), obtained from a commercial stockist. The bolts, including the threads, were covered with a thin adherent black scale, whereas the nuts were bright. Sizes of the bolt heads and of the nuts conformed to the appropriate British Standards (1083:1951 for BSW and BSF, and 1768:1951 for UNC and UNF). All the bolts and nuts were stated to be Class 2 (Unified) or Medium Fit (Whitworth). The threaded lengths of the bolts were about half

TABLE 1. BOLT SIZES AND MANUFACTURERS

Nominal size and number of threads per in.	D/p	Length of bolt, in.	Symbol representing manufacturer	
			Bolt	Nut
$\frac{3}{8}$ -24.UNF	9.0	2	A	F
$\frac{1}{2}$ -20.BSF	7.5	2	A	F
$\frac{1}{2}$ -16.UNC	6.0	2	B	F
$\frac{1}{2}$ -16.BSW	6.0	2	A	F
$\frac{3}{4}$ -16.UNF	12.0	3	A	F
$\frac{3}{4}$ -12.BSF	9.0	3	D, E*	F
$\frac{3}{4}$ -10.UNC	7.5	3	C	F
$\frac{3}{4}$ -10.BSW	7.5	3	C	F
$1\frac{1}{2}$ -12.UNF	18.0	5	C	F
$1\frac{1}{2}$ -8.BSF	12.0	5	C	F
$1\frac{1}{2}$ -6.UNC	9.0	5	C	F
$1\frac{1}{2}$ -6.BSW	9.0	5	C	F

* The bolts from manufacturer E were used only for repeated tightening tests.

* Mechanics and Materials Division, Mechanical Engineering Research Laboratory, East Kilbride.

¹ All references at end of article.

TABLE 2. SUMMARY OF RESULTS OF TIGHTENING AND TENSILE TESTS ON $\frac{1}{2}$ -IN. THREADS
(Code R bolts + Code P nuts)

Type of thread	Average hardness of bolts/nuts HD/30	Tightening torque test to failure (no external tensile load)			Tensile test to failure (no pre-tightening)*		Tensile test to failure of joint pre-tightened to 90 per cent of maximum torque (Col. 3)*			
		Yield torque (lb.-in.)	Maximum torque (lb.-in.)	Mode of failure	Maximum load (tons)	Mode of failure	Pre-tightening torque (lb.-in.)	Maximum load (tons)	Mode of failure	Load for joint separation (tons)
		1	2	3	4	5	6	7	8	9
½-16.BSW	250/220	350 (+70) (-40)	400 (+80) (-40)	B (6)	4.5 (+0.2) (-0.4)	B (6)	360 P (3) + E (3)	4.4 (±0.2)	B (6)	3.7 (+0.3) (-0.6)
½-20.BSF	280/200	405 (+15) (-35)	500 (+50) (-40)	B (5) + N (1)	4.6 (±0.2)	B (5) + N (1)	450 P (6)†	4.6 (+0.1) (-0.2)	B (5) + N (1)	3.6 (±0.1)
½-16.UNC	230/200	400 (±20)	445 (±30)	B (6)	4.3 (±0.1)	B (6)	405 P (6)	4.2 (±0.1)	B (5) + N (1)	3.1 (+0.4) (-0.6)
½-24.UNF	250/200	415 (+35) (-25)	525 (+100) (-125)	B (2) + N (4)	4.5 (+0.2) (-0.9)	N (6)	475 P (6)	4.4 (±0.2)	N (6)	3.7 (±0.6)

* In general, no definite yield was observed in the tensile tests. Two of the hand-tight $\frac{1}{2}$ -10.BSW bolts yielded at 15.5 tons, and three of the hand-tight $\frac{1}{2}$ -10.UNC bolts at 15.7 tons approximately. All the $\frac{1}{2}$ -in. assemblies (BSW, BSF, UNC and UNF) gave a very indefinite yield at about 4 tons, and the $\frac{1}{2}$ -12 UNF assemblies at about 55 tons (thread bending).

† In addition, two bolts broke during pre-tightening before the torque of 450 lb.-in. was reached.

B—failure across core of threaded portion of bolt, with appreciable necking. No, or only slight, bending of bolt threads.

N—failure by stripping of nut threads, with considerable bending of bolt threads, generally accompanied by slight necking of bolt. Number in brackets indicates number of assemblies which failed in the manner indicated.

P—yield of bolt and/or nut occurred before reaching stated pre-tightening torque. Application of torque continued until latter was reached.

E—stated pre-tightening torque reached without appreciable yielding.

All threads were lubricated with Shell Retinax A, a light grease.

the total shank lengths. The sizes investigated, with symbols representing manufacturers, are listed in Table 1.

METALLOGRAPHIC EXAMINATION

One bolt was selected from each of the 13 types listed in the penultimate column of Table 1. (The $\frac{1}{2}$ -in. BSF bolts were from two manufacturers). An axial section was prepared through the threaded portion of each bolt, and this was polished and etched to reveal the grain structure. The $\frac{1}{2}$ -in. bolts showed evidence of having been produced by rolling, in that there were seams in some of the thread crests. None of the bolts, however, showed any tendency to "grain flow" following the thread contour, so that, in the bolts investigated, any such effect due to the threads being produced by rolling must have been removed during the heat-treatment normally carried out after rolling, in order to obtain the requisite static tensile strength. (Sometimes only a stress relief treatment is carried out after rolling, and this does not usually remove the "grain flow" completely). No serious decarburization was observed in any bolt. For a given size of bolt, the grain size was similar for all four types. It was rather finer for $\frac{1}{2}$ -in. bolts than for larger sizes.

There appears, therefore, to have been no significant metallurgical differences between the various

types of bolt investigated. All the nuts were obtained from a single manufacturer.

HARDNESS TESTS

Standard diamond pyramid hardness tests were carried out on most of the $\frac{1}{2}$ -in. and $\frac{3}{4}$ -in. bolts and nuts, and on six bolts and six nuts of each type




Fig. 1. Method of Testing Bolt and Nut Combinations. A, Tensile Test. B, Tightening Test. C, Tension Rod of Tensile Testing Machine. D, Grip of Torsion Testing Machine. E, Plate for Detecting Joint Separation

TABLE 3. SUMMARY OF RESULTS OF TIGHTENING AND TENSILE TESTS ON 1/4-IN. THREADS (Code R bolts + Code P nuts)

Type of Thread	Average hardness of Bolts/Nuts HD/30	Tightening torque test to failure (no external tensile load)			Tensile test to failure (no pre-tightening)*		Tensile test to failure of joint pre-tightened to 75 per cent of maximum torque (Col. 2)*				Tensile test to failure of joint pre-tightened to 90 per cent of maximum torque (Col. 3)*			
		Yield torque (lb.-in.)		Mode of failure	Maximum load (tons)	Mode of failure	Pre-tightening torque (lb.-in.)	Maximum load (tons)	Mode of failure	Load for joint separation (tons)	Pre-tightening torque (lb.-in.)	Maximum load (tons)	Mode of failure	Load for joint separation (tons)
		2	3											
½-10 BSW	250/200	2,650 (+450) (-400)	3,310 (+310) (-290)	B(6)	17.3 (+0.9) (-0.6)	B(6)	2,480 E(6)	17.2 (+0.9) (-1.0)	B(6)	9.4 (+0.5) (-1.1)	2,980 P(6)	16.8 (+0.7) (-0.5)	B(6)	9.7 (+0.5) (-0.3)
		3,210 (+290) (-310)	4,280 (+440) (-480)	B(6)	18.6 (+1.0) (-1.3)	B(6)	3,210 P(4) ± E(2)	17.8 (+1.2) (-1.6)	B(6)	12.0 (+1.0) (-0.7)	3,850 P(6)	18.4 (+1.6) (-0.9)	B(6)	14.0 (+1.5) (-1.3)
½-12 BSF	200/200													
¾-10 UNC	260/210	3,420 (+180) (-60)	4,130 (+210) (-230)	B(6)	17.6 (+0.9) (-0.9)	B(6)	3,100 E(6)	17.5 (+0.6)	B(6)	12.7 (+0.5) (-0.8)	3,715 P(6)	17.4 (+0.6) (-0.9)	B(6)	13.9 (+0.3) (-0.4)
		3,650 (+410) (-1080)	5,080 (+800) (-1060)	B(2) + N(4)	21.1 (+1.1) (-0.6)	B(4) + N(2)	3,810 P(2) ± E(4)	20.5 (+0.5) (-0.7)	B(3) + N(3)	17.0 (+1.0) (-0.8)	4,570 P(6)	20.6 (+1.1) (-0.7)	B(2) + N(5)	18.6 (+0.7) (-0.6)
¾-16 UNF	250/200													

* In general, no definite yield was observed in the tensile tests. Two of the hand-tight 1/4-10 BSW bolts yielded at 15.5 tons, and three of the hand-tight 1/4-10 UNC bolts at 15.7 tons approximately. All the 1/4-in. assemblies (BSW, UNC and UNF) gave a very indefinite yield at about 4 tons, and the 1/4-12 UNF assemblies at about 35 tons (thread bending).
 B—failure by stripping of nut threads, with considerable bending of bolt threads, generally accompanied by slight necking of bolt. Number in brackets indicates number of assemblies which failed in the manner indicated.
 P—yield of bolt and/or nut occurred before reaching stated pre-tightening torque. Application of torque continued until latter was reached.
 E—stated pre-tightening torque reached without appreciable yielding.
 All threads were lubricated with Shell Retinax A, a light grease.

in the 1/4-in. size. The hardness variations within any particular batch of nuts were not very great, and all the nuts were well within the values quoted in the above-mentioned British Standards for Code P material.

Large variations were often obtained in the hardness numbers for a particular bolt, and the average values for some of the bolts appeared to be below the minimum hardness for Code R material. However, in the tensile tests subsequently carried out, no case was found of a bolt below the minimum value* of 45 tons per sq. in. for

* Based on "stress area" = π (effective diameter + minor diameter)²/16.

Code R. The hardness values are not, therefore, a reliable guide to the strength of the bolts.

Average hardness values obtained are included in Table 2, 3 and 4.

TIGHTENING AND TENSILE TESTS

In the principal series of tests, a bolt and nut were used to fasten together a pair of steel adapters, which could be fitted to the grips of a tensile testing machine for applying external load to the joint (see Fig. 1). Torque could be applied to the combination by means of hexagon sockets fitting over the bolt head and nut and connected to a static torsion testing machine.

Six combinations of each type were tested, in each size. Before testing, the threads were brushed to clean off loose matter. This brushing did not disturb the scale on the bolts. The threads and the bearing faces of the nut and underlying washer were then coated with a light grease.

The main group of tests comprised tightening tests to failure, and tensile tests on pre-tightened joints, with a single tightening in each case. For the first test, the nut was tightened continuously on the bolt in a static torsion testing machine, at an approximately constant rotational speed of 90 deg. per min., to determine the yield torque and the maximum torque developed

TABLE 4. SUMMARY OF RESULTS OF TIGHTENING AND TENSILE TESTS ON $\frac{1}{4}$ -IN. THREADS
(Code R bolts+ Code P nuts)

Type of thread	Average hardness of bolts/nuts HD/30	Tightening torque test to failure (no external tensile load)			Tensile test to failure (no pre-tightening)*		Tensile test to failure of joint pre-tightened to 75 per cent of maximum torque (Col. 3)*			
		Yield torque (lb.-in.)	Maximum torque (lb.-in.)	Mode of failure	Maximum load (tons)	Mode of failure	Pre-tightening torque (lb.-in.)	Maximum load (tons)	Mode of failure	Load for joint separation (tons)
		1	2	3	4	5	6	7	8	9
1½-6.BSW	260/190	21,250 (+2,450) (-1,750)	34,200 (+4,800) (-3,400)	B (6)	72.7 (+3.4) (-2.9)	B (5) + N (1)	25,650 E (6)	70.6 (+5.8) (-3.7)	B (6)	54.9 (+5.8) (-2.9)
1½-8.BSF	240/200	27,420 (+2,980) (-3,020)	46,200 (+3,600) (-3,200)	B (6)	75.1 (+3.3) (-1.8)	N (6)	34,650 E (6)	78.4 (+4.1) (-5.0)	B (3) + N (3)	64.6 (+2.4) (-4.6)
1½-6.UNC	235/210	21,050 (+950) (-550)	38,850 (+1,850) (-2,850)	B (6)	73.0 (+3.4)	B (5) + N (1)	29,150 E (6)	72.2 (+5.05) (-2.8)	B (6)	54.0 (+1.8) (-1.5)
1½-12.UNF	235/200	21,230 (+1,470) (-1,430)	47,300 (+4,700) (-2,700)	N (6)	75.6 (+3.2) (-7.1)	N (6)	35,625 E (6)	75.1 (+3.3) (-3.4)	N (6)	62.15 (+3.35) (-3.65)

^a In general, no definite yield was observed in the tensile tests. Two of the hand-tight $\frac{1}{4}$ -10.BSW bolts yielded at 15.5 tons, and three of the hand-tight $\frac{1}{4}$ -10.UNC bolts at 15.7 tons approximately. All the $\frac{1}{4}$ -in. assemblies (BSW, BSF, UNC and UNF) gave a very indefinite yield at about 4 tons, and the $\frac{1}{4}$ -12 UNF assemblies at about 55 tons (thread bending).

B—failure across core of threaded portion of bolt, with appreciable necking. No, or only slight, bending of bolt threads.

N—failure by stripping of nut threads, with considerable bending of bolt threads, generally accompanied by slight necking of bolt. Number in brackets indicates number of assemblies which failed in the manner indicated.

P—yield of bolt and/or nut occurred before reaching stated pre-tightening torque. Application of torque continued until latter was reached.

E—stated pre-tightening torque reached without appreciable yielding.

All threads were lubricated with Shell Retinax A, a light grease.

before failure. For brevity, the latter is referred to below as "failure torque."

The tensile tests to failure were made on combinations tightened by hand only, and to 75 per cent and 90 per cent of the average failure torque for a particular size and type of thread. For these two conditions, the tensile load to separate the joint was determined, in addition to the maximum load, by noting when a flat plate, interposed between the adapters, just became loose.

It has been shown that tightening to yield develops maximum clamping load and has no adverse effects for coarse threads⁴. On the other hand, it is not desirable to tighten to far above the yield. Thus, for the $\frac{1}{4}$ -in. size, as the yield, for all types of thread, exceeded 75 per cent of average failure torque, this tightening condition was not investigated. On the other hand, for the $\frac{1}{4}$ -in. size, as the yield was invariably less than 75 per cent of average failure torque, this condition was investigated, and not the one involving a more severe tightening. Both conditions were investigated for the $\frac{1}{4}$ -in. size. The results of the above tests are reported in Tables 2, 3 and 4.

Some similar tightening and tensile tests were carried out on $\frac{1}{4}$ -in. combinations with bored-out nuts, to simulate conditions resulting from the use of an oversize tapping drill. For each type of thread, the nuts were bored out to a minor diameter which, in conjunction with the average

measured major diameters of the mating bolts, gave a depth of engagement equal to 50 per cent of the full thread height for a bolt of basic size, as given in B.S. 84/1956 for BSW and BSF, and in B.S. 1580:1953 for UNC and UNF threads. Determinations were made of failure torque, and of tensile loads for joint separation and failure after tightening to 75 per cent of failure torque for normal combinations. The latter type of test was also extended to include joints tightened up to a maximum of seven times. Joint separating loads were determined after each tightening, and tensile load to failure was finally applied. The results of the tests with bored-out nuts are given in Table 6.

A fuller investigation was also made of the effect of repeated tightening on normal combinations in the $\frac{1}{4}$ -in. size.

First, tests involving only seven tightenings were carried out, the nut being tightened on the bolt in a static torsion testing machine until yield occurred. After the sixth tightening, the tensile load for joint separation was determined. The nut was then completely removed to permit inspection of the threads (also after the fifth tightening). Finally, the combination was tightened to failure. The results of these tests are included in Table 5.

As these latter tests showed a tendency for thread bending to occur in the UNF combinations, it was decided to carry out further tests, involving a much greater number of tightenings. Three combinations

TABLE 5. RESULTS OF REPEATED TIGHTENING TESTS ON NORMAL $\frac{1}{4}$ -IN. COMBINATIONS

Combination	Applied torque for successive tightenings (lb.-in.)							Joint separating load after 6th tightening (tons)	Maximum torque on 7th tightening (lb.-in.)	Damage after [†] 5th tightening	Damage after [†] 6th tightening	Mode [*] of final failure
	1	2	3	4	5	6	7					
$\frac{1}{4}$ -10 BSW (1)	Yield Break-loose ... 3,100 2,100	3,000 1,950	3,000 1,920	2,900 1,840	3,000 1,840	3,300 2,130	3,000 —	13.3 —	3,120 —	No thread bending Bolt necked by 0.007 in.	As after 5th tightening	B
(2)	Yield Break-loose ... 3,000 2,000	2,900 2,040	2,900 1,960	2,820 1,900	2,860 1,940	3,200 2,360	3,300 —	13.7 —	3,860 —	No thread bending Bolt necked by 0.004 in.	As after 5th tightening	B
(3)	Yield Break-loose ... 3,150 2,000	2,900 1,980	2,900 1,900	2,900 1,900	2,900 1,900	2,800 1,600	2,600 —	13.9 —	3,040 —	No thread bending Bolt necked by 0.004 in.	As after 5th tightening	B
$\frac{1}{4}$ -12 BSF (1)	Yield Break-loose ... 4,200 3,000	4,000 2,800	4,100 3,000	3,910 2,750	4,300 3,000	4,500 2,900	3,100 —	18.7 —	3,290 —	No thread bending Bolt necked by 0.010 in.	As after 5th tightening	B
(2)	Yield Break-loose ... 4,700 3,400	4,380 3,200	4,400 3,200	4,300 3,200	4,280 3,200	4,450 3,450	3,150 —	17.6 —	3,780 —	No thread bending Bolt necked by 0.010 in.	No thread bending Bolt necked by 0.013 in.	B
(3)	Yield Break-loose ... 4,200 3,050	4,200 2,850	4,480 2,750	4,150 2,400	3,700 2,650	3,700 2,550	3,550 —	19.2 —	3,930 —	No thread bending Diameter not checked	No thread bending Bolt necked by 0.020 in.	B
$\frac{1}{4}$ -10 UNC (1)	Yield Break-loose ... 3,050 2,100	2,900 1,800	2,900 1,800	2,900 1,750	2,900 1,750	2,900 1,600	2,800 —	16.0 —	3,100 —	No thread bending Bolt necked by 0.009 in.	No thread bending Bolt necked by 0.013 in.	B
(2)	Yield Break-loose ... 2,700 1,880	2,740 1,760	2,720 1,740	2,780 1,700	2,740 1,700	2,480 1,350	2,700 —	14.4 —	2,990 —	No thread bending Bolt necked by 0.006 in.	No thread bending Bolt necked by 0.008 in.	B
(3)	Yield Break-loose ... 2,750 1,750	2,750 1,700	2,800 1,750	2,900 1,700	2,750 1,700	2,650 1,600	2,850 —	14.7 —	3,120 —	No thread bending Bolt necked by 0.007 in.	As after 5th tightening	B
$\frac{1}{4}$ -16 UNF (1)	Yield Break-loose ... 4,000 3,150	4,000 2,700	4,000 2,700	3,600 2,700	3,600 2,500	3,400 2,900	3,700 —	18.2 —	3,900 —	Bolt threads slightly bent Bolt necked by 0.009 in.	Bolt threads rather more bent. Bolt necked by 0.009 in.	N
(2)	Yield Break-loose ... 3,600 3,100	3,200 2,600	3,200 2,450	3,200 2,450	3,300 2,450	3,250 2,450	3,250 —	18.0 —	3,690 —	Bolt threads slightly bent Bolt necked by 0.009 in.	Bolt threads slightly bent. Bolt necked by 0.009 in.	N
(3)	Yield Break-loose ... 3,600 2,900	3,230 2,600	3,300 2,600	3,370 2,600	3,500 2,750	3,400 2,700	3,250 —	18.4 —	3,400 —	Bolt threads slightly bent Bolt necked by 0.005 in.	Bolt threads slightly bent Bolt necked by 0.006 in.	N

† Nut threads not easy to observe, but probably bent if bolt threads were bent.

* The necking of the bolt at fracture was considerable for BSW, BSF and UNC. No, or only slight, bending of bolt threads after the 6th tightening.

B—failure across core of threaded portion of bolt, with appreciable necking. N—failure by stripping of nut threads, with considerable bending of bolt threads, generally accompanied by slight necking of bolt.

of each type were tested. The first was repeatedly tightened to yield until failure occurred. The second and third combinations were repeatedly tightened in the same way, but for a somewhat smaller number of tightenings, after which the tensile loads for joint separation and for failure were

determined. In this manner, a check was obtained on the extent of the loss of clamping load due to a large number of tightening. The results of these tests are plotted in Fig. 2-5.

Finally, an attempt was made to obtain similar information for repeated tightening

to fixed torque values, again using $\frac{1}{4}$ -in. combinations. As the maximum speed of the torsion testing machine was only 1 turn per min., the torque was applied in these tests by a limiting-moment torque spanner, the setting of which was continually checked against the torsion testing

TABLE 6. SUMMARY OF RESULTS OF TIGHTENING AND TENSILE TESTS ON $\frac{1}{4}$ -IN. BOLTS ASSEMBLED WITH BORED-OUT NUTS¹

Type of thread	Tightening torque test to failure (no external tensile load)			Tensile test to failure, of joint pre-tightened once to 75 per cent of maximum torque for normal combinations			Tensile test to failure, of joint pre-tightened 7 times to 75 per cent of maximum torque for normal combinations (Col. 4)				
	Yield torque (lb.-in.)	Maximum torque (lb.-in.)	Mode of failure	Pre-tightening torque (lb.-in.)	Maximum tensile load, (tons)	Mode of failure	Load for joint separation, (tons)	Load for joint separation after 6th tightening (tons)	Load for joint separation after 7th tightening (tons)	Maximum tensile load after 7th tightening (tons)	Mode of failure
	1	2	3	4	5	6	7	8	9	10	11
$\frac{1}{4}$ -10.BSW	3,160 (+320) (-220)	3,750 (+240) (-220)	B (3)	2,480 E (6)	16.9 (+1.1) (-0.9)	B (6)	7.9 (+0.4) (-0.6)	8.8 (± 0.8)	8.5 (+0.7) (-0.5) (5 results) ²	17.4 (± 0.4) (5 results) ²	B (6)
$\frac{1}{4}$ -12.BSF	3,760 (+470) (-400)	5,180 (+40) (-50)	B (3)	3,210 E (6)	17.2 (+0.5) (-0.8)	B (5) + b (1)	11.1 (+0.6) (-0.9)	12.5 (+0.9) (-0.7)	12.8 (+0.8) (-0.6)	17.2 (+0.7) (-0.6)	B (3) + n (3)
$\frac{1}{4}$ -10.UNC	Indefinite	3,640 (+240) (-320)	B (2) + b (1) (severe necking)	3,100 P (4) (+2 indefinite)	16.6 (+0.9) (-1.8)	B (5) + b (1)	13.7 (+1.0) (-0.9)	13.2 (+0.8) (-1.2) (4 results) ³	14.5 (+0.4) (-0.2) (3 results) ³	16.9 (± 0.4) (3 results) ³	B (5) + b (1)
$\frac{1}{4}$ -16.UNF	Indefinite	4,190 (+270) (-240)	N (3)	3,810 (Yield indefinite)	19.3 (+1.0) (-1.5)	n (6)	16.5 (± 0.8)	Pre-tightening torque = 3,650 lb.-in. ⁴			
								15.2 (± 0.5)	15.8 (± 0.4) (2 results) ⁵	19.0 (+1.3) (-1.4) (2 results) ⁵	b (2) + n (1)
								Pre-tightening torque = 3,210 lb.-in.			
								12.6 (+1.0) (-0.6)	13.5 (+0.6) (-1.2)	18.5 (+0.5) (-0.6)	b (3) (necking very slight)

1—Code R bolts + Code P nuts, both class 2 or medium fit, except that the nut minor diameters were oversize, to give depths of engagement equal to 50 per cent of full thread height of basic size bolts.

2—One bolt broke during 7th tightening.

3—Two bolts failed on 2nd and 6th tightenings respectively, and a third bolt failed on 7th tightening.

4—Of three assemblies tightened to 3,810 lb.-in., two failed by stripping on the 2nd tightening and one at the tensile separating load of 14.5 tons, after the 6th tightening (b).

5—One bolt failed on 7th tightening (b).

B—failure across core of threaded portion of bolt, with marked necking.

N—failure by stripping (bending and shearing) of nut threads, with considerable bending of bolt threads and only slight necking of bolt.

b—failure by stripping of bolt threads. Both nut and bolt threads badly bent. Some necking of bolt.

n—failure by stripping of both bolt and nut threads, with only slight necking of bolt.

For items B, N, b, and n, the number in brackets shows the number of assemblies which failed in the manner indicated.

E—Stated pre-tightening torque reached without appreciable yielding.

P—Yield occurred before reaching stated pre-tightening torque. Application of torque continued until the latter was reached.

It should be noted that 3,650 lb.-in. = average yield torque for normal $\frac{1}{4}$ -16.UNF combinations.

3,210 lb.-in. = average yield torque for normal $\frac{1}{4}$ -12.BSF combinations.

machine. A plain steel block was used in place of the joint adapters, with a plain washer under the nut. The results of these tests are given in Table 7.

The bolt tensile strengths, determined during the main series of tests, were all within the Code R specification values of 45/55 tons per sq. in., and the hardness values of the nuts were all well within the Code P specification values.

VARIABILITY OF RESULTS

It should be observed, at the outset, that although the total number of tests was large, only six tests were, in general, carried out under any particular

set of conditions, and that there was considerable variability in the results obtained. It is possible, therefore, that the average values and limits of variation might have been somewhat different from those quoted in the tables, if the tests had covered a larger number of samples. Certain conclusions may still be drawn from the results, as to differences between the types and sizes of thread investigated, but the quoted values should only be taken as a general indication of those likely to be obtained in practice under a particular set of conditions, even if the latter are thought to approximate to those of the present tests.

The limits of variation for the different main

types of test (Tables 2 to 4) covering results on all three sizes, are summarized in Table 8 for each type of thread. Except for the case of pre-tightening to 90 per cent of maximum failure torque in the $\frac{3}{8}$ -in. size, which is not likely to occur very often in practice, the results for UNC are definitely the most consistent. The results for BSW and UNF were the most inconsistent, and abnormally low values seemed particularly likely to be encountered with UNF. Further reference to the scatter of results is made later in considering particular groups of tests.

MODE OF FAILURE

A definite yield, as indicated by a halt in the rise of load with approximately constant rate of strain, was often observed in the tightening tests, but not in the tensile tests. Even in the tightening tests, the onset of yield was generally ill-defined, and tended to be masked by the stick-slip movement of the threads. Quoted values of yield torque are those for which definite yield occurred.

The BSW and UNC combination in all three sizes, and the BSF combination in the $\frac{3}{8}$ -in. and $\frac{1}{2}$ -in. sizes, generally failed by breakage across the

core of the bolt. Many of the UNF combinations in the smaller sizes, and all in the $\frac{1}{2}$ -in. size, failed by stripping of the nut threads, with severe bending of the bolt threads. These differences may be largely explained, as in the Appendix, on a basis of pitch and diameter and of certain other factors. It may be mentioned here that the relatively low height of the $\frac{1}{2}$ -in. Unified nuts, as compared with that of the $\frac{1}{2}$ -in. Whitworth nuts, increased the tendency to stripping failure of UNF combinations, already most pronounced in the larger sizes.

The stripping failures took place more gradually than the bolt core failures, and for a given rate of strain, the torque or tensile load fell off more gradually when stripping occurred. It follows that severe over-tightening might occur during assembly without being detected, for those combinations susceptible to failure by thread stripping—the UNF combinations.

DEVELOPMENT OF CLAMPING LOAD

It will be seen from Tables 2 to 4 that the joint separation loads (indicated in Col. 10 and Col. 14 in Table 3), after a single pre-tightening to a given percentage of maximum failure torque, were not lower for the UNF than for the other types of combination. The same should apply to the initial clamping loads developed on tightening, since

$$P_i/P_s = K_m/(K_m + K_b)$$

where P_i = initial clamping load.

P_s = joint separating load.

K_m = stiffness of clamped members (load per unit deflection).

K_b = stiffness of bolt (load per unit deflection).

The same joint adapters were used throughout, for a given size of bolt, and K_b would not vary much as between the different types of bolt in a given size. An indication of the efficiency of an assembly in developing clamping load may thus be obtained by dividing the torque applied by the load for joint separation (Col. 7/Col. 10 and Col. 11/Col. 14 in Table 3). Assemblies with the higher values of torque per ton of separating load will be the least efficient. In this respect, no type of combination shows up consistently better than the others over the whole range of sizes. This result is not surprising, in view of the fact that only about 10 per cent of the total applied torque is effective in producing tensile load in the bolt. The remainder is used, in roughly equal amounts, in overcoming the friction in the threads and at the nut bearing




Fig. 2. Results of Repeated Tightening Tests to Yield on $\frac{3}{8}$ -10 B.S.W. Combinations (Group 6). All Failures Occurred Across Core of Bolt. X—Broke on 70th Tightening

TABLE 7. REPEATED TIGHTENING TESTS ON NORMAL $\frac{3}{4}$ -IN. COMBINATIONS, USING A TORQUE SPANNER

Type of combination	Tightening torque, (lb.-in.)	1st Combination			2nd Combination			3rd Combination		
		No. of tightenings	Necking of bolt, (in.)	Other damage to combination	No. of tightenings	Necking of bolt, (in.)	Other damage to combination	No. of tightenings	Necking of bolt, (in.)	Other damage to combination
$\frac{3}{4}$ -10.BSW ...	2,500	50 51	0-031 —	None Bolt core failure	70 80 150	0-023 0-024 0-024	None " "	40 120 160	0-023 0-023 0-024	None " "
	2,750	20 150	0-0005 0-0005	None "	60 150	0-0005 0-001	None "			
	3,000	50 150	0-001 0-0015	None "	50 150	0-003 0-004	None "			
	3,250	50 150	0-007 0-007	None "	50 150	0-002 0-0025	None "			
	3,500	50 150 250	0-013 0-040 0-060	None " "	50 100 150	0-008 0-008 0-010	None " "	20 50 150	0-011 0-014 0-015	None " "
$\frac{3}{4}$ -12.BSF ...	3,000	60 120 240	0-0005 0-004 0-006	None " "	100 150 200	0-0005 0-0005 0-0005	None " "			
	3,250	150	0-002	None	100 240 360	0-016 0-051 0-071	None " "	50 100 150	0-001 0-001 0-002	None " "
$\frac{3}{4}$ -10.UNC ...	3,000	20 180 240	0-012 0-027 0-028	None " "	150 200	0 0	None "			
	3,250	7	—	Bolt core failure	50 100 150	0-043 0-047 0-047	None " "	50 80	0-016 —	None Bolt core failure
$\frac{3}{4}$ -16.UNF ...	3,000	60 160	— 0-0005	None "	40 150	0-001 0-001	None "			
	3,250	40	0-0005	Bolt threads slightly bent	30	0-003	Bolt threads slightly bent			
		80	0-0005	Bolt threads more bent	60	0-004	Bolt threads slightly bent			
		87	0-0005	Thread stripping failure	70	0-0045	Bolt threads more bent			
					90	0-005	Bolt threads more bent			
					148	0-005	Thread stripping failure			
	3,500	10	0-011	Not inspected	15	0-014	Bolt threads slightly bent			
		20	0-011	Thread stripping failure	18	0-014	Bolt threads more bent			
					19	0-014	Thread stripping failure			

Note.—Where the bolt threads were bent, it is probable that the nut threads were also bent. Observation of the threads inside the nut was difficult.

face⁵. Variations in these frictional forces will thus tend to mask those due to differences in thread form and pitch. Heavy thread deformation occurring prior to failure by stripping may cause the thread friction to increase rapidly, and maximum failure torque would then not be a reliable guide to the clamping load developed.

An attempt was made, by making measurements of bolt elongation under given loads, and when tightened under a given torque, to estimate the stiffness of the joint adapters and the actual clamping loads developed. The results, however, were not very consistent. It appeared that, for the $\frac{3}{4}$ -in. combinations, a joint separating load of 10 tons

indicated an initial clamping load of about 8 tons. An interesting secondary result which emerged from measurements made in this connection was that, for these 3-in. long, $\frac{3}{4}$ -in. diameter combinations, the deflection of the bearing face of the nut, relative to the bolt at that point, was of the same order as the elongation of the bolt itself. Consequently, in assessing the effective stiffness of a bolt, the nut deflection should be taken into account.

TENSILE FAILURE LOADS

The loads for tensile failure were not significantly affected by pre-tightening. This result was to be expected, as the assembled joint separated before





Fig. 3. Results of Repeated Tightening Tests to Yield on 3-12 B.S.F. Combinations (Group 6). All Failures Occurred Across Core of Bolt. X—Broke on 43rd Tightening

failure in all cases, and any frictional torque would have been released by slight rotation of the joint adapters in the tensile testing machine. For a single pre-tightening, the tensile loads for failure of the UNF combinations compared favourably with those for the other types (Tables 2 to 4, Col. 8, and Table 3, Col. 12).

YIELD AND FAILURE TORQUES

The ratio of yield torque to failure torque was lowest for UNF in all three sizes (Col. 2/Col. 3). For

Fig. 4. Results of Repeated Tightening Tests to Yield on 3-10 U.N.C. Combinations (Group 6). All Failures Occurred Across Core of Bolt. X—Broke on 83rd Tightening



the 3-in. and 2-in. sizes, this ratio decreased over the four types in the following order: UNC, BSW, BSF, UNF. For a given type of combination, the ratio decreased as the size increased, i.e., for the cases investigated, as the D/p ratio increased. Some engineering handbooks give tables of failure torques as a guide to "safe" tightening torques for various kinds of combination. The results show that it is not possible to specify a fixed "safe" percentage of failure torque for all types of combination, or even for different sizes of any one type, without being unduly conservative in the case of relatively coarse threads (low D/p ratio).

REPEATED TIGHTENING TESTS ON NORMAL COMBINATIONS

The results of Table 5 on 3-in. combinations have been reported in detail to indicate the variations which can be obtained for successive tightenings of the same assembly. It will be seen that the "break-loose" torque (maximum unscrewing value) in all instances, and the tightening yield torque in about half the cases, decreased markedly after the first tightening, but did not undergo a further definite decrease on subsequent tightenings. There was sometimes a marked change after dismantling and reassembling for the sixth to seventh tightenings, but this change was not in the same direction in every instance. The average yield torque after the first, and after the sixth tightening, both differed appreciably from that after a single tightening as given in Table 3. These observations have an obvious relevance to the use of "standard" torque-tension relations in practice.

By comparing Table 5 with Table 3, Col. 10,

TABLE 8. LIMITS OF VARIATION OF RESULTS OF TIGHTENING AND TENSILE TESTS IN ALL THREE SIZES

	Maximum percentage variations from mean value of:				
	Yield torque	Maximum failure torque	Tensile failure load	Tensile load for joint separation after pre-tightening to 75 per cent of maximum failure torque	Tensile load for joint separation after pre-tightening to 90 per cent of maximum failure torque
BSW	+20 -15	+20 -10	+5 -9	+9 -12	+8 -16
BSF	±11	+10 -11	+5 -7	+8 -7	+11 -9
UNC	±5	±7	±5	+4 -6	+13 -19
UNF	+11 -30	+19 -24	+5 -20	±6	±16

it can be seen that the joint separating loads after the sixth tightening were invariably markedly higher than those after a single tightening. These higher values were, no doubt, partly or wholly due to decrease of friction owing to repeated rubbing down of high-spots, with the result that a greater proportion of the applied torque was available to develop clamping load. Some of the increase in separating load may have been due, in the BSW and BSF cases, to increase of tightening torque applied, but for UNC and UNF, the torques applied for the sixth tightening in Table 5 were actually lower than those for a single tightening (Table 3, Col. 7) although they resulted in higher separating loads than in the latter case. As the most marked change in yield and break-loose torques occurred after the first tightening, it seemed that the same might apply to joint separating load. A few tests were carried out on $\frac{1}{2}$ -12.BSF assemblies to check this point. Three combinations were each tightened twice, to the average value of yield torque, as given in Table 3, Col. 2 (3,210 lb.-in.), the joint separating load being determined after each tightening. One of the combinations yielded before the tightening torque was reached and two did not. The average joint separating load after the first tightening was 11.2 tons, and the increases of separating load after the second tightening were 0.7, 0.7 and 0.8 ton. These relatively small increases indicate that the joint separating load increases only gradually after each tightening, and not mainly on the second tightening, when a given torque is applied to the nut.

EFFECT OF MULTIPLE TIGHTENING

In order to check the effect on clamping load of a relatively large number of tightenings, the tests reported in Fig. 2 to 5 were carried out on three combinations of each type, using a procedure similar to that followed for the Table 5 tests, except that a much greater number of tightenings was applied—in each case until the occurrence of yield,

i.e., of appreciable plastic deformation. It is evident that the number of tightenings to yield, which could be withstood before failure, decreased with the pitch of thread. The 10 t.p.i. threads (UNC and BSW) required about the same torques up to about 50 tightenings, after which the torques for UNC were somewhat lower than for BSW, although the clamping loads were as high, and the number of tightenings to failure greater, than for BSW.

This difference in behaviour was similar to that observed in the Table 5 tests.

The BSF combinations withstood only about half, and the UNF combinations only about one




Fig. 5. Results of Repeated Tightening Tests to Yield on $\frac{1}{2}$ -16 U.N.F. Combinations (Group 6). All Failures by Thread Stripping

quarter, of the number of tightenings sustained by the UNC combinations, though the clamping loads developed were higher, corresponding to the higher yield torques.

Within about five tightenings from ultimate failure, there was no very serious reduction in the tensile loads for joint separation and failure for UNC, BSW and BSF. For UNF, it appears that a rapid reduction, corresponding to progressive thread bending, set in by about the 20th tightening, *i.e.*, at about 10 tightenings before the final one, at which thread stripping was not complete, slight clamping still being obtained. This result, again, illustrates the possibility of severe damage to a UNF combination through over-tightening, which might go undetected on assembly.

MULTIPLE TIGHTENING TESTS TO GIVEN TORQUE VALUES

The results of the repeated tightening tests on normal combinations, using a torque spanner, are given in Table 7. Each combination was repeatedly tightened to a given value of torque, instead of to yield, as in the Table 5 tests. The results for $\frac{1}{4}$ -10.BSW at 2,500 lb.-in. tightening torque are anomalous, the damage to the bolt being similar to that produced by a tightening torque of 3,500 lb.-in., and greater than that for intermediate torques. It can only be assumed either that the torque spanner was not applying correct torques, or that the frictional resistance was abnormally low in these tests. They were, in fact, made at a different time from the other tests on BSW combinations, although under ostensibly the same conditions. The results are included further to emphasize the uncertainty which attaches to the use of torque-tension relations. It seems unlikely that the yield torque for these BSW combinations was below 3,000 lb.-in., which agrees approximately with the values in Table 5, but is markedly higher than the value in Table 3.

Considering the remainder of the results, *i.e.*, not including those for $\frac{1}{4}$ -10.BSW at a nominal tightening torque of 2,500 lb.-in., there is still seen to be considerable variability, but certain broad conclusions may be drawn.

At a tightening torque of 3,000 lb.-in., all four types of combination could be tightened 150 times without serious damage. Some of the bolts with coarser threads, and therefore lower core area, had, at this stage, necked down by a few thousandths of an inch, representing only a few per cent loss of load-bearing area. No appreciable thread bending occurred in any of the bolts.

At a tightening torque of 3,250 lb.-in., the $\frac{1}{4}$ -10.UNC combinations were liable to suffer severe necking and core failure of the bolt after relatively few tightenings. The $\frac{1}{4}$ -10.BSW and $\frac{1}{4}$ -12.BSF combinations suffered a small reduction of bolt diameter after 150 tightenings, but could evidently have withstood many more tightenings without failure. In the $\frac{1}{4}$ -16.UNF combinations, bolt necking was slight, but progressive thread bending set

in at an early stage, and stripping failure occurred before reaching 150 tightenings. It is evident that serious thread damage could be caused to UNF combinations on assembly, which could not be detected by a change of resistance to tightening. Such damage might not be noticed on dismantling, especially if the threads were coated with grease. Replacement of a damaged bolt in a different nut or tapped hole, in which the threads did not match with the distorted bolt threads, would increase the damage.

At a tightening torque of 3,500 lb.-in. the $\frac{1}{4}$ -10.BSW combinations behaved surprisingly well, and no failure occurred, although bolt necking in one case was quite pronounced. The $\frac{1}{4}$ -16.UNF combinations withstood only a few tightenings at this torque before failure occurred by thread bending and stripping. The $\frac{1}{4}$ -10.UNC combinations would evidently not have withstood this torque satisfactorily, and it seems likely that the $\frac{1}{4}$ -12.BSF would have behaved similarly to the $\frac{1}{4}$ -10.BSW, judging from the results at lower torques.

It should be emphasized, however, that the higher torques withstood by the Whitworth combinations were not necessarily associated with higher clamping loads. The contrary was, in fact, indicated by the Table 5 tests.

For reasons already mentioned, it does not seem wise to place much reliance on the torque values, and the main conclusion from these torque spanner tests is that the $\frac{1}{4}$ -16.UNF combinations were liable to fail, by thread stripping, after relatively few tightenings to a torque appreciably less than the average yield torque, as determined from tests involving one, or only a small number of tightenings (see Tables 3 and 5).

It is usual for the nut to be somewhat softer than the bolt, and yield in bending will occur in the nut threads at least as soon as in the bolt threads. Removal of a nut after such bending had occurred would involve forcing the bent nut threads over undeformed threads near the free end of the bolt; this would cause further damage to the nut threads. Although the average value of bending stress at the thread roots does not depend on pitch/diameter ratio, its maximum value is greater for fine than for coarse threads, owing to the greater concentration, with the former, of the thread load towards the bearing face of the nut². Fine threads would, therefore, yield at a lower applied load than coarse threads, and this fact, in view of the thread deformation factor noted above, may partly account for the comparatively low resistance of fine threads to repeated heavy tightening.

EFFECT OF REDUCING DEPTH OF ENGAGEMENT OF THREADS

The tests with bored-out nuts were carried out because oversize tapping drills are sometimes used in order to facilitate tapping, especially in difficult materials. Results are given in Table 6, and may be compared with those of Table 3, for normal depths of engagement.

Differences in failure torques, Table 3, Col. 3, and Table 6, Col. 2, could be due to differences in thread friction, or to differences in strength, or to both these factors. The higher yield and failure torques for the BSW and BSF combinations with bored-out nuts, as compared with normal combinations of these types, were very probably due to increased thread friction. These combinations all suffered core failure of the bolt, outside the nut, and extra torsional stresses due to increased friction could only have reduced the tensile load for failure (developed by tightening). Confirmation is afforded by the fact that, on boring out the nuts, there was, for BSW and BSF, an increase in the torque required per ton of separating load (for a single tightening to 75 per cent of failure torque for normal combinations: Table 6, Col. 4/Col. 7, as compared with Table 3, Col. 10). The torque per ton of separating load was only slightly increased for UNF, and definitely decreased for UNC. It is probable, therefore, that the low failure torque for the UNC combinations with bored-out nuts was largely due to a decrease in thread friction as compared with that which was present with normal combinations.

That there was a decrease for UNC and not for BSW is difficult to explain, but it will be remembered that the repeated tightening tests on normal combinations (Table 5 and Fig. 2-5) gave indications of lower thread friction for UNC than for Whitworth threads. The tensile failure loads for the combinations with bored-out nuts (Table 6, Col. 5) were somewhat lower than for the normal combinations, but the difference is only sufficient partly to explain the lower maximum failure torque for UNC.

As already implied, on boring out the nuts, there was a small decrease of joint separating load for a given degree of tightening, in all cases except for UNC, for which there was an 8 per cent increase. On the other hand, the separating load after the sixth and seventh tightenings (Table 6, Col. 8 and 9) showed a definite increase over that after the first tightening for BSW and BSF, but not for UNC, although the latter still required the highest separating load after the seventh tightening. The UNF combinations could not withstand even a few tightenings to 75 per cent of failure torque for normal UNF combinations, and the tightening torque had to be reduced to below 3,650 lb.-in. (the average torque for yield of normal UNF combination) before failure was completely avoided on the seventh tightening. At a tightening torque of 3,210 lb.-in., however, which was the highest 75 per cent value for any of the other types of combinations (*viz.* for BSF), seven tightenings could be successfully applied, and the tensile separating load was then rather higher than for BSF, tightened to the same torque, but lower than for UNC combinations, which were only tightened to 3,100 lb.-in.

The stripping failures of the UNF combinations with bored-out nuts generally involved shearing of the bolt threads rather than of the nut threads, and the bending and distortion of both nut and bolt

threads was always very severe.

These tests, again, show the poor resistance to repeated tightening of the UNF combinations, compared with the other types. Boring out the nuts emphasized this difference in behaviour, and, with such reduction of depth of engagement, there would appear to be no advantage, with respect to clamping load developed after only a few tightenings, in using UNF in preference to BSF or UNC combinations.

NUMBER OF TURNS OF NUT

During the course of this investigation, numerous observations were made of the number of turns of the nut, relative to the bolt, required to develop various degrees of tightening, including tightening to yield and failure. The number of turns depends to some extent on the length of bolt and stiffness of the joint, but these factors are not as important as might at first appear, due to bolt elongation being concentrated in the threaded portion, and to the relatively high stiffness of most load-bearing joints. There was, however, considerable variation in the observed values, and often a marked decrease, after the first tightening, in the amount of turning of the nut to produce a given tightening torque. This decrease was no doubt due to flattening of high-spots on the bearing surfaces, with a consequent change in the datum (hand-tight) position of the nut.

The following broad conclusions could be drawn. After a preliminary tightening and unscrewing to obtain a proper seating, half a turn of the nut from the hand-tight position would generally be sufficient slightly to exceed the yield for the BSW, BSF and UNC combinations in all three sizes. A few cases were encountered of BSF combinations in the $\frac{3}{4}$ -in. size, for which yield was not quite reached. The amount of turning for failure was always more than one turn, ranging up to $1\frac{3}{4}$ turns for $\frac{3}{4}$ -in. diameter and up to $2\frac{1}{2}$ turns for $1\frac{1}{2}$ -in. diameter. For BSW, BSF and UNC combinations, therefore, a preliminary tightening to a little below yield, followed by the application of half a turn of the nut from the hand-tight position, should develop satisfactory clamping in circumstances where more accurate methods of tightening are not available. The preliminary tightening would be especially important where the bearing surfaces were coated with rust or dirt.

For UNF combinations, on the other hand, such a method is not recommended, as it is undesirable to tighten them to yield, which occurs due to thread bending. Half a turn of the nut would not exceed the yield for $\frac{3}{4}$ -in. and $1\frac{1}{2}$ -in. UNF combinations, although it might slightly exceed it for $\frac{1}{2}$ -in. UNF. It could thus be taken as a safe amount for UNF in sizes above $\frac{3}{4}$ -in., if it was not required to develop maximum safe clamping load in the larger sizes by more accurate means.

This method would not, of course, be suitable for joints incorporating soft gaskets or other flexible parts.

CONCLUSIONS

1. The BSW and UNC combinations in all three sizes, and the BSF combinations in the $\frac{3}{8}$ -in. and $\frac{1}{2}$ -in. sizes, generally failed by breakage across the core of the bolt, with pronounced necking. Many of the UNF combinations in the smaller sizes, and all in the $\frac{1}{2}$ -in. size, failed by stripping of the nut threads, with severe bending of the bolt threads. The latter mode of failure occurs gradually, during a single tightening if sufficiently severe, and during a relatively small number of tightenings if yielding of the threads in bending occurs. Severe over-tightening might thus be applied and not detected on assembly, possibly with serious consequences when service loads were imposed.

2. For a single pre-tightening, the clamping loads developed, as indicated by joint separating load, and the maximum tensile loads for failure, were not lower for the UNF than for the other assemblies, for all degrees of tightening employed, in all three sizes.

3. $\frac{3}{8}$ -16 UNF combinations satisfactorily withstood repeated assembly, if they were not tightened up to yield, which occurred at higher torques than for the other types. If these $\frac{3}{8}$ -16 UNF combinations were repeatedly tightened up to yield, progressive thread bending led to failure after a smaller number of tightenings than for the other types of combinations. Under these conditions, the number of tightenings withstood increased with the pitch of the thread. Where tightening is controlled, as by proper use of a well-designed torque-spanner, UNF combinations could be used to develop clamping loads about as high as for the other types of combination, even on repeated assembly, at least under laboratory conditions. The need for close control suggests, however, that the coarser threads would be more suitable for general service conditions.

4. In the $\frac{3}{8}$ -in. and $\frac{1}{2}$ -in. sizes, the ratios of yield torque to failure torque for the four types of combination were in the following descending order of magnitude: UNC, BSW, BSF, UNF. The ratio was also smallest for UNF in the $\frac{1}{2}$ -in. size. For a given type of combination, the ratio decreased with increase of size, i.e. with increase of diameter/pitch ratio.

It is not possible, therefore, to specify a fixed "safe" percentage of failure torque for all types of combination, or even for different sizes of one type, without being unduly conservative in the case of coarse threads, having low diameter/pitch ratios.

5. Taking the results of the main series of tightening and tensile tests for the three sizes as a whole, those for UNC were the most consistent, the maximum variations from mean values never exceeding ± 7 per cent, except in a single instance of pre-tightening to well above yield, which would normally be avoided in practice. The results for UNF and BSF were the most inconsistent, those for UNF particularly showing deviations of as much as 30 per cent below the mean value. The chances

of encountering an abnormally weak combination thus appear to be greatest for UNF.

6. Unified nut heights, for threads over 1-in. diameter, are calculated according to formulae given in B.S. 1768:1951, Appendix C, p. 28. The values so obtained are less than the corresponding values for Whitworth nuts, tabulated in B.S. 1083:1951, p. 21, for threads up to 2-in. diameter. Since failure of the $\frac{1}{2}$ -12 UNF combinations invariably occurred by stripping, it would appear desirable to increase the height (length of engagement) of Unified nuts, for threads over 1-in. diameter, to that of Whitworth nuts.

For similar reasons, it is suggested that, for UNF in all sizes, and for BSF in larger sizes (say over 1 in.), nuts for Code R bolts should be Code P and not Code A, as at present recommended in B.S. 1083 and 1768.

7. Reduction of the depth of engagement to about 50 per cent of basic, by boring out the nut, reduced the resistance to repeated tightening, especially of UNF combinations. Clamping loads for a small number of tightenings were not seriously affected, except that the UNF combinations were unable to withstand tightening torques as high as for normal UNF combinations, and thus could not develop such high clamping loads. Use of an oversize tapping drill is thus to be discouraged for UNF threads.

8. As a rough guide under field conditions, for stiff metal-to-metal joints, the nut should be first well tightened (say to somewhat below yield of the combination), then unscrewed and re-tightened half a turn from the new finger-tight position.

9. Hardness tests on the surface of the finished bolt are of little value for checking the quality of Code R bolts.

RECOMMENDATION

Where heavy loads must be transmitted, it is advisable to avoid the use of UNF threads unless tightening can be closely controlled, or unless their use is desirable for reasons other than those of strength. If such close control is possible, yielding of UNF threads, which occurs mainly by bending, should be avoided. It should be borne in mind that loss of fit due to wear, corrosion, and similar factors is especially serious in the case of fine threads.

The deficiency of UNF threads implied in this suggestion is due not to the form of thread, but to the fineness of this particular series. UNF was never intended as an automatic replacement for BSF. The coarse UNC series should be adequate for most purposes.

ACKNOWLEDGEMENTS

The author acknowledges the assistance of Mr. D. M. Waters and Mr. I. C. Craik, who carried out most of the experimental work. The work described above has been carried out as part of the research programme of the Mechanical Engineering Research

Board, and this article is published by permission of the Director of Mechanical Engineering Research.

APPENDIX: REASONS FOR DIFFERENT MODES OF FAILURE

As stated under "Mode of failure," the BSW and UNC combinations in all three sizes, and the BSF combinations in the $\frac{1}{2}$ -in. and $\frac{3}{4}$ -in. sizes, generally failed by breakage across the core of the bolt. Many of the UNF combinations in the smaller sizes, and all in the $1\frac{1}{2}$ -in. size, failed by stripping of the nut threads, with severe bending of the bolt threads. These differences may be qualitatively explained as follows.

Shear failure tends to occur at a diameter which is less than the major thread diameter by a small amount, proportional to the pitch, say at a diameter $D - ap$, where D = major diameter, p = pitch, and a = constant, for a given form of thread (there would not, in fact, be much difference between Unified and Whitworth threads). In other words, shear is assumed to occur at a distance below the major diameter equal to a given proportion of thread depth, which is itself proportional to pitch. The diameter of the cross-sectional area on which it is appropriate to base the tensile failure load (empirically found to be about the mean of the minor and effective diameters) is similarly equal to $D - bp$, where b = constant (b is greater than a). Now the tensile failure area is proportional to $(D - bp)^2$, and the shear failure area to $(D - ap)L$, where L is length of engagement, i.e. height of nut. The ratio T/S of tensile to shear failure load will therefore be proportional to:—

$(D - bp)^2 / (D - ap)L$ or to $(D - bp)^2 / (D - ap)D$ since nut height L is approximately proportional to nominal diameter D . Approximately, therefore,
 $T/S \propto 1 - 2bp/D + ap/D \propto 1 - p/D(2b - a)$
 since $a < b < 1$ and $p \ll D$.

For a given nominal size D , the T/S ratio will increase as the pitch decreases, and shear failure will become more likely. Thus, the UNF threads generally failed by stripping, whilst the coarser threads failed in tension across the core of the bolt.

Again, as size increases, the T/S ratio will increase as the p/D ratio decreases. This explains

why the BSF threads failed by stripping in the $1\frac{1}{2}$ -in. size but not in the smaller sizes.

It must also be noted that the nut heights were not, in fact, constant for a given size of thread. The specification values and the L/D ratios are given in Table 9.

As required by the specifications, there was, for each size, a difference of a few per cent between the height of the BSW and BSF nuts on the one hand, and that of the UNC and UNF nuts on the other. The Whitworth nuts were thicker than the Unified in the $\frac{3}{4}$ -in. and $1\frac{1}{2}$ -in. sizes, but thinner than the Unified in the $\frac{1}{2}$ -in. size. As the stripping strength of a combination is proportional to the nut height⁶, these differences probably explain the occasional stripping failures with $\frac{1}{2}$ -20.BSF combinations. They would also, of course, tend to increase the probability of stripping failure in the Unified combinations in the larger sizes. This is not important for UNC, but rather unfortunate in respect of UNF.

In the $1\frac{1}{2}$ -8.BSF case, all the combinations tightened to failure suffered breakage of the bolt, whilst those subjected to tensile load only failed by stripping of the threads. Similarly, there seemed to be a greater tendency to stripping failure in a pure tensile test for $\frac{1}{2}$ -24.UNF. This result may be due to the tightening failures occurring under conditions of combined tensile clamping load and frictional torque, although it is difficult to explain why other combinations did not behave similarly, e.g. $\frac{3}{4}$ -16.UNF.

Yet another factor involved in the stripping strength of a combination is the reduction caused by increase of effective diameter clearance between the external and internal threads³. Any factors tending, in effect, to increase this clearance, will probably tend to do so by an amount independent of the fineness of the thread, e.g. standard bolt diametral tolerances are a greater proportion of thread depth for fine than for coarse threads. Again, wear, corrosion and decarburization effects will tend to affect a certain depth of material which will be proportionately greater for fine than for coarse threads. Such factors might be important under some conditions of service. A further factor causing loss of diametral fit is the expansion of the nut under load. This expansion varies from

(Continued on p. 1425)

TABLE 9. SPECIFICATION MAXIMUM VALUES OF NUT HEIGHT, AND L/D RATIOS

Size, in.	Whitworth		Unified	
	Nut height, in.	Nut height Nom. diameter	Nut height, in.	Nut height Nom. diameter
$\frac{1}{2}$	0.312	0.83	0.33	0.88
$\frac{3}{4}$	0.687	0.92	0.66	0.88
$1\frac{1}{2}$	1.375	0.92	1.28*	0.85

* Calculated from formula given in B.S. 1768, Appendix C, page 28

REFERENCES

- Field, J. E. "Fatigue Strength of Screw Threads. Effect of Specimen Size and Hardness of Nut Material," *The Engineer*, **198**, 5139, 1954, July 23, pp. 123-124.
- Sopwith, D. G. "The Distribution of Load in Screw Threads," *Proc. Inst. Mech. Eng.*, **159**, 1948, pp. 373-383.
- Smith, C. W., and Low, A. C. "Effect of Fit and Truncation on the Strength of Whitworth Threads Under Static Tension," *Engineering*, **168**, 1949, July 22, pp. 93-95.
- "New Concepts in Structural Joint Design": Second progress report of Research Council on Riveted and Bolted Structural Joints of the Engineering Foundation, Chicago, Illinois, U.S.A. 1953, December 1, pp. 17, 18 and 21.
- Hancke, A. "Anzugsmoment, Reibungsbeiwert und Verspannkraft bei hochfesten Schrauben," *Drakt*, **6**, 2, 1955, February, pp. 39-42.
- Drakt, **6**, 3, 1955, March, pp. 86-93.
- Field, J. E. "Tensile Stripping Tests on B.S.W. $\frac{1}{2}$ in. by 10 t.p.i. threads," *The Engineer*, **200**, 5213, 1955, December 23, pp. 901-902.

East German Machine Tools at the Leipzig Fair

In MACHINERY, 92/1268—30/5/58 reference was made to some East German machine tool exhibits at this year's Leipzig Fair, and others are considered in the following pages, also some examples of induction heating equipment.

CIRCULAR-DIE THREAD ROLLING MACHINES

The type GAWR16, fully-automatic, circular-die, thread rolling machine, shown in Fig. 1, is a new development by VEB Werkzeugmaschinenfabrik Bad Duben. It is of the type in which the workpieces are fed from a magazine into an indexing carrier surrounding one of the rolls. The thread rolls operate at fixed centres, and are eccentrically-mounted so that a piece is threaded in slightly less than one revolution. During the idle part of the roll revolution, the carrier is indexed to

bring a fresh blank to the rolling position, and the finished piece falls out of the carrier into a container beneath.

A feature of interest on the machine illustrated is that a hopper with two magazine feed channels is fitted, together with a double-ended indexing carrier and two sets of thread rolls. With this arrangement for threading two pieces at each cycle, an output of 150 pieces per min. can be obtained when handling 12-mm. (0.472-in.) diameter by 1½-in. long steel hexagon bolts, with a thread length of 1 in. To provide for continuous running, with a minimum of attention by the operator, the supply to the overhead hopper on the machine is maintained by a vertical slot-type elevator, which picks up blanks from a large-capacity floor-mounted container.

Workpieces from 6 to 16 mm. (0.236 to 0.63 in.) diameter, with pitches from 0.5 to 2 mm. (0.020 to 0.080 in.), and up to 4 in. long under the head, can be handled on the machine, and a maximum thread length of 60 mm. (2.36 in.) can be rolled. The products of this factory also include the type GWR80 thread rolling machine, which is hydraulically operated and will handle workpieces from 3 to 80 mm. (¼ to 3¼ in.) diameter.

INTERNAL AND FACE GRINDER WITH MULTI-SPINDLE INDEXING WORK TURRET

A combined face and bore grinding machine, which is of interest because it incorporates a 4-spindle, horizontal, indexing work turret, has been introduced by VEB Schleifmaschinenwerk, Berlin. It is intended for handling, on a quantity production basis, types of components required, for example, in the motor car and ball and roller bearing industries. This machine, which is illustrated in Fig. 2, will grind bores from 1 to 3 in. diameter, up to 2 in. long, and the maximum diameter of workpiece that can be accommodated is 7 in.

The 4-station work turret mounted on the left-hand end of the bed indexes in a clockwise direction, and the workpieces are held in hydraulically-operated collets. Parts are loaded and unloaded at the upper front station, and at the next station, face grinding is carried out with the spindle head A which is mounted on a raised extension at the rear



Fig. 1. Fully-automatic, Circular-Die, Thread Rolling Machine, Arranged to Thread Two Workpieces at Each Cycle




Fig. 2. The Type SIXTP75 x 50 Combined Internal and Face Grinder, which Incorporates a 4-station Indexing Work Turret

of the bed. Rough- and finish-grinding of the bore, at the third and fourth stations, is performed with spindles in the head *B*, which is reciprocated hydraulically along the bed-ways. These spindles are mounted in eccentric sleeves, and the increments of feed are applied by an arrangement of cams.

The machine stops automatically at the end of the grinding cycle, and a guard, not shown in the illustration, is retracted to allow the work to be unloaded. Safety interlocks ensure that the machine cannot be started unless the workpiece is properly clamped and the guard is in position. After each piece has been ground, wheel dressing is carried out, and compensating increments of in-feed are applied automatically. The speed of the work spindles is selected to suit the particular application, and may range from 100 to 240 r.p.m. Steplessly-variable traverse rates from 40 to 400 in. per min. are obtainable for the internal grinding head. A coolant system, which incorporates a magnetic filter, is provided.

NILES VERTICAL TURNING AND BORING MILLS

The latest DKE range of Niles vertical turning and boring mills made by VEB Grossdrehmaschinenbau "7 October," Berlin Weissensee, includes machines with turning capacities of 31½, 39½, 49, and 63 in. diameter, which are available in normal and high speed types. A type DKE-1250

machine, with a turning capacity of 49 in., is shown in Fig. 3. Drive to the table is taken through a gearbox, and either eight or sixteen speeds are provided, which can be changed under load. For the 49-in. machine, here shown, speeds up to 280 r.p.m. are available when a 50-h.p. driving motor is fitted.

Steplessly - variable feed rates are available for turning, boring, and facing, and a side tool head, which can be clamped to the column by hand, or hydraulically, can be supplied. Automatic clamping can be provided for




Fig. 3. Niles Type DKE-1250 Vertical Turning and Boring Mill, of 49-in. Turning Capacity, Equipped with a Side Tool Head and an Electric Copying Attachment

locking the cross-slide and the tool ram, if required, also automatic depth stops for the ram movement. The ram can be fitted with either a single tool-post or a 5-station turret, and the latter can be arranged for automatic, electrical indexing.

Other features that can be incorporated include a thread cutting gearbox, an electric copy-turning attachment, and a coolant pump unit and guards. In accordance with modern practice, the various controls for the machine are conveniently centralized on a pendant panel.




Fig. 4. Mikrosa Centreless Grinder Set-up for Grinding Cylinder Liners on an Automatic Cycle

MIKROSA CENTRELESS GRINDERS

A Mikrosa type SASI 200 centreless grinder, built by VEB Werkzeugmaschinen-und Vorrichtungsbau, Leipzig, is shown in Fig. 4, set up for plunge grinding, with an automatic cycle, the peripheral lands on cast iron cylinder liners for diesel engines. There is a land at each end of the liner, and the machine is fitted with two grinding, and two control, wheels.

The liners are loaded into a slightly-inclined magazine mounted on top of the grinding wheel head, and are lowered, in turn, on to a work rest of V-form, by means of a cradle support, which moves vertically in guideways and is actuated by a hydraulic cylinder and piston. Size control is effected by an electric gauging head at A, which pivots down into contact with the periphery of the liner as soon as it is loaded. Upon completion of the grinding cycle, the liner is ejected along the work rest by means of a hydraulic cylinder and piston, and it moves down an inclined runway system to a discharge point. An output of 70 pieces per hour is obtained with this set-up.

Either through-feed or plunge-feed grinding can be carried out on the SASI 200 machine, and it will handle work from $\frac{1}{8}$ to 8 in. diameter. Drive to the 24-in. diameter grinding wheel is taken from a motor of 40 h.p., and the nitrided-steel spindle, which is ground and lapped, is supported in two plain bronze bearings on either side of the V-belt pulley. Ten working speeds, obtained

through change gears, are provided for the control wheel, and there is also a high speed for use when diamond truing, with a hydraulically-operated dressing attachment. The control wheel spindle, it may be noted, is mounted in a plain adjustable bearing at each end. In addition to the hydraulic plunge-feed and work ejection features, provision can be made for hydraulically-operated, short-stroke reciprocating movements of the grinding wheel spindle.

Reference may also be made to the type SAASI 125 Mikrosa centreless grinder, of smaller capacity, which is fully-automatic in operation, and was demonstrated plunge grinding a 1½-in. diameter by 2-in. long workpiece. The parts were delivered down a chute from a hopper, and were picked up, in turn, by a loading slide, which then moved transversely to allow the piece to be pushed on to the work rest by a hydraulic piston. At the end of the grinding cycle, the part was ejected towards the front of the machine, and passed beneath the loading slide into a container. For size control purposes, every ninth workpiece was discharged between the anvils of a Zeiss electronic measuring head, which was moved transversely into the gauging position at the appropriate point in the cycle, and any wheel-head adjustment required was then made automatically. After each 100 pieces had been ground, a diamond wheel-dressing device was brought into operation automatically.

HIGH-FREQUENCY INDUCTION HEATING EQUIPMENT

V E B Werkzeugmaschinenfabrik Hermann Schlimme, Berlin-Treptow, are engaged in the development of high-frequency induction and dielectric heating equipment, also units for spark-erosion and ultrasonic machining. Induction heating equipment, recently introduced, includes the type IHU500 universal machine, which is capable of handling gears and other circular workpieces, also shaft components. It is seen in Fig. 5 set up for hardening a large gear-wheel, one tooth at a time, by the indexing method, the inductor being arranged to traverse the tooth space.

The generator is rated at 20 kW., 50 Kc., and gears up to 3 ft. diameter by 8 in. face width, and from 2½ to 12 D.P., can be hardened by the indexing method. For indexing, an adjustable-throw crankpin, on the slotted disc A, engages a tooth space of the gear, the crank disc being rotated intermittently.

Two ranges of steplessly-variable, electronically-controlled, traversing speeds are available for the inductor head, namely 0.08 to 0.63 in. per sec. and 0.2 to 2 in. per sec. Hardening takes place on the




Fig. 5. Type IHU500 Induction Hardening Machine for Gears and Shafts. The Large Gear-wheel Seen in Position is Hardened by the Indexing Method




Fig. 6. Vacuum Induction Melting Furnace for Laboratory Use

upward stroke, and the inductor then returns and the workpiece is indexed. The rapid return stroke is at the rate of 1½ or 4½ in. per sec.

For hardening shafts and other workpieces from ⅝ to 2½ in. diameter, mounted vertically, brackets carrying centres are provided on the face of the machine column, the spindle in the upper bracket B being driven at a speed of 200 r.p.m. by means of a small geared motor. Provision is made for swinging the inductor head to the right, into line with the axis of the work centres. The maximum distance between centres is 26 in. and workpieces can be hardened over lengths up to 16½ in. Water for quenching is delivered through a solenoid-operated valve at pressures from 40 to 80 lb. per sq. in., and the rate of flow is 4½ gal. per min.

A machine has also been developed for hardening shafts, including camshafts, up to 63 in. long, and a prototype machine, of 100-kW. rating, for hardening the slideways on machine tool beds up to 12 ft. long, is now in operation in an East German machine tool factory. This machine incorporates a wheeled carriage, which is moved by a chain along guide rails to traverse the work past a stationary inductor head, the latter being adjustable for setting purposes in the vertical and transverse directions.

Another product of the organization is the vacuum induction melting furnace seen in Fig. 6, which has been designed for laboratory use and is fitted with a crucible of 800-gm. (28-oz.) capacity. Power is supplied by a 4-kW. generator, which is one of a new range covering ratings from 2 to 50 kW., and the pump fitted enables a vacuum of 10^{-6} mm. Hg to be drawn.

SPARK EROSION MACHINES

Shown in Fig. 7 is one of the range of spark erosion machines made by VEB Werkzeugmaschinenfabrik Hermann Schlimme. Designated the type ERFM15, it has an input rating of 12 kVA., and is fitted with a work table measuring 31½ by 19½ in. Screw adjustment is provided for the electrode head, longitudinally and transversely, so that the whole area of the work-table is covered, and fine settings can be made to 0.0004 in. A working stroke of 6 in. is provided for the electrode head by a patented electro-hydraulic feed system. In addition, the compound slide assembly can be adjusted through a distance of 6 in., ver-




Fig. 7. Spark Erosion Machine of 12-kVA. Rating Built in East Germany. Accurate Adjustment is Provided for the Electrode Head in Both Directions




Fig. 8. A Transportable Spark Erosion Unit of 1-kVA. Rating which can be Used on Both Large and Small Workpieces. The Stroke of the Electrode Spindle is 4 in.

tically, by handwheel and screw. Provision can be made for rotating the electrode for producing threads, and an attachment can be fitted for spark machining curved holes.

In addition to the machine illustrated, there is a smaller size, with an input rating of 3 kVA., which incorporates similar design features.

A portable spark erosion unit, with associated generator of 1 kVA. input rating, is shown in Fig. 8. When mounted on an adjustable tripod carrier, this unit can be conveniently used on the shop floor for removing broken taps or performing other operations on both large and small workpieces. Alternatively, the electrode head can be mounted in the spindle of a vertical drilling machine, for example.

The electrode feed can be varied to suit the application, and it is stated that metal removal rates up to 60 cu. mm. per min. can be obtained. The stroke of the electrode spindle is 4 in.

Reference may also be made to a small ultrasonic machining unit, illustrated in Fig. 9, which has been introduced. It operates at a frequency of 24,000 c.p.s., and incorporates a Zeiss compound worktable which is equipped with a micrometer adjustment.




Fig. 9. Small-capacity Ultrasonic Machining Unit Developed in East Germany

ROTARY TRANSFER GRINDING MACHINE

Fig. 10 shows a special-purpose machine of the rotary transfer type which has been built by Wotan-und Zimmerman-Werke A.G. for carrying out grinding operations on the inner face of a cast-iron cup-shaped component for a planetary gear. There are six work-heads mounted on the rotary table, which is indexed hydraulically, and the drive to the work-head spindles is taken from 2-speed pole-changing motors.

A high degree of surface finish is required on the component, and for this reason the operation is carried out in three stages, namely, rough grinding, finish grinding, and polishing. In addition, a close tolerance is specified on the dimension from the ground surface to the

face by which the component is located in the chuck. Rough grinding is carried out at the first working station, with a hydraulically-fed head, which is seen immediately to the left of the loading and unloading position. At the next station, the work is automatically gauged, and, by means of a feed-back system, any in-feed adjustment necessary is applied to the rough grinding head. A spindle head of the same unit design performs the finish-grinding operation at the second working station, and the piece is then checked by means of a gauging head at the next index position. Finally, the ground surface is polished by the spindle head seen on the right. With this machine, it is stated, a depth tolerance of 0.0006 in., and a very high surface finish, can be maintained. With these unit heads, which have been developed for grinding and gauging, machines can be built for finishing parts with several faces.

ROCKET TESTING TRACK. It is reported in *Mechanical Engineering* that a track of exceptional accuracy has been provided at the U.S. Air Force Missile Development Centre in New Mexico. Each 2-mile section of track was welded into a continuous length, stretched by as much as 5 ft. and then anchored. Interrupter blades used for speed measurement are installed at 13 ft. intervals, and the accumulated error must not exceed 1 in. over a 7-mile length. The minimum radius specified for "topographical" curves in the track is 2,000,000 ft.




Fig. 10. Rotary Transfer Machine for Carrying-out Face Grinding Operations on a Planetary Gear Component

Conference on Compressed Air as an Aid to Improving Productivity

Mention has already been made in MACHINERY, 92/925—18/4/58, of the conference organized by the Cornwall Section of the Institution of Production Engineers, which was held on April 9 and 10, and more detailed reference is made here to some of the papers presented. A total of five papers was read, and the first, which was delivered by Mr. J. Hodge, M.A., head of the Consultancy Department, Power Jets (Research and Developments), Ltd., was entitled "Industrial Uses of Rotary Compressors." Mr. Hodge explained that the title of his paper was a misnomer, in that he proposed to discuss the design and relative merits of various types of compressors—rotary, reciprocating and axial flow—rather than the uses to which they were put. In the past, the supply of compressed air at pressures up to 50 lb. per sq. in. has been achieved mainly by the use of reciprocating compressors, but in recent years there had been a growing tendency to use rotary compressors of various kinds. All types of compressors, whether rotary or reciprocating, could be sub-divided into two main groups, namely, positive-displacement and aerodynamic. With positive displacement compressors, the volume of air delivered was dependent almost entirely on, and was directly proportional to, the speed of the machine, and optimum efficiency was obtainable only in the region of the pressure ratio for which the compressor was designed. With any substantial departure from this zone, moreover, there was a serious loss of efficiency.

The most important advantage of the positive displacement type of compressor was its freedom from "surging," which was a form of instability frequently encountered with the aerodynamic type.

Rotary positive displacement machines were of four main types, namely, the Roots blower, the BICERA supercharger, the Lysholm compressor, and the vane-type compressor. The Roots blower, in single-stage form, was suitable for pressures of the order of 8 to 10 lb. per sq. in. Certain advantages were offered by the BICERA supercharger, as compared with the Roots-type, in that the greater part of the compression was achieved directly, by means of an internal volumetric change during rotation, and losses due to leakage were reduced.

Rotary-vane type compressors were of well-

established design, and could be used, in 2-stage form, for pressures up to 100 lb. per sq. in. The compression was achieved by direct internal volume change, and leakage losses were low because of the number of vanes which formed seals between the high- and low-pressure zones.

Finally, the Lysholm compressor, which was also known as the S.R.M. or Howden compressor, comprised two lobed rotors, meshing together, but geared so that they did not actually touch each other. Various limitations, associated with rotor stiffness and expansion, were imposed, and it appeared, at present, that with the single-stage design, a pressure ratio of 5:1, and a throughput of 10,000 cu. ft. per min., were the maxima for this type. With 2-stage units, however, pressures up to 100 lb. per sq. in. could be obtained.

One of the advantages of the Lysholm compressor was that, owing to the absence of rubbing parts, there was no need for any form of internal lubrication, and the air delivered was clean and free from oil.

Aerodynamic compressors, Mr. Hodge continued, were of two basic types, centrifugal and axial flow. A similarity existed between these types, in that the work input to the rotor caused a change in the whirl velocity of the air, which was then converted into pressure. The main difference was that centrifugal force was employed in one type to assist the energy conversion process, but not in the other.

With single-stage centrifugal compressors, the maximum pressure ratio obtainable was usually considered to be in the region of 4:1, with a rotor tip speed of about 1,500 ft. per sec. Recent unconfirmed reports of developments in the U.S.A., however, had mentioned pressure ratios of 7 or 8:1, with rotor tip speeds of the order of 1,900 ft. per sec.

Advantages of axial flow machines were considerable. Pressure ratios up to about 8:1 were possible with a single shaft, even without intercooling, and the multi-staging of normal centrifugal-type compressors to achieve the same result would be very cumbersome. On the other hand, the use of an axial flow machine could rarely be justified for an industrial application, as it was most efficient where large flow rates, of the order of 10,000 cu. ft. per min., and upwards, were required.

In the discussion which followed this paper, Mr. J. O. H. Mulhaus (Climax Rock Drill & Engineering Works, Ltd.) asked the speaker to comment on the relative merits of ball and plain-type bearings for compressors. In reply, Mr. Hodge said that the primary consideration was the anticipated life of the bearing, and that for applications involving speeds up to about 50,000 r.p.m. the use of ball bearings was recommended.

Mr. A. Dunn (Climax Rock Drill & Engineering Works, Ltd.) expressed the opinion that further development was required in connection with prime movers for driving compressors, particularly those of the aerodynamic type. With the latter, there was invariably a need for some form of step-up gearbox, as the running speed of the compressor was so much greater than that of the driver. The introduction of this gearbox necessarily increased the amount of maintenance required, and he felt that increased use of axial flow compressors would be delayed until gas turbine drives were practical.

AIR GAUGING

In opening his paper on air-gauging, Mr. C. J. Tanner [Solex (Gauges), Ltd.] reviewed, briefly, the basic principles of the subject, and pointed out that the greatest advantage of the method was that it enabled a measurement to be magnified without the use of any kind of mechanism, and thus eliminated errors caused by such factors as hysteresis, backlash, wear, and vibration. It was at first thought that the ability to take non-contact measurements was the principal merit of air-gauging, but, although this facility was still of

importance in connection with easily-deformable and delicate workpieces, the method was now generally used only where it was impractical to employ contact measurement, and never in preference to the latter.

The methods of taking measurements with air-gauges could be classified broadly under three headings, namely, restriction, direct, and indirect (contact). The indirect, or contact, system was used for the majority of air-gauging applications, and a typical contact measuring head incorporated a poppet-type valve, the stem of which was in contact with the surface of the workpiece. The size of the work at the point of measurement ensured a certain degree of opening of the valve, and consequently affected the flow of air. Such heads could be linked together to form multi-gauging set-ups, or to provide an indication of such conditions as out-of-roundness and straightness. The author then went on to discuss the design and details of some of the various control/indicating instruments, now generally referred to as "air-controllers."

Turning to present day applications of air-gauging, Mr. Tanner said that modern machines frequently incorporated hydraulic or pneumatic means for presenting the gauge to the part, and *vice versa*, and complete gauging installations had been built into conveyors and machine tools. As an example, Fig. 1 shows an in-line transfer machine for performing a number of operations on a motor car crankcase. Components can be seen mounted on the transfer mechanism at the loading station in the foreground, and the multi-column gauging station, which is built into the machine, is in the background. A close-up view of the gauging station is shown in Fig. 2, where a component is in position and the measuring heads are seen extended to enter the bores. This equipment checks the main and cam-shaft





Fig. 1. In-line Transfer Machine with Built-in Air-gauging Equipment for Checking the Main and Camshaft Bores of a Motor Car Crankcase

Fig. 2. Close-up View of the Gauging Installation on the Machine Shown in Fig. 1



bores, and provision is made for stopping the machine automatically if the machining limits are exceeded.

As a result of the rapid developments in air-gauging, the speaker continued, a number of terms had been introduced, and for a full understanding of the subject it was desirable that these should be properly defined. The following were among the expressions in most common use, and their definitions.

Production Gauge: Used by the machine operator or setter for measuring the part during or after the machining operation.

Setting Check Gauges: Used by the operator to translate the findings of the production gauge into the necessary slide adjustment of the machine.

Line Inspection Gauge: A combination of a production and setting gauge which determines rapidly one, or a number of, critical dimensions, thereby indicating the drift of tool wear and allowing the necessary corrective action to be taken.

Automatic Machine Control: Linking the production gauge with the machine movements so that the latter are stopped when the limits for the particular workpiece are exceeded.

Automatic sizing: Another method of machine control whereby the gauge automatically slows down, and stops, the in-feed of the tool slide when a given dimension is reached.

In conclusion, Mr. Tanner said that in the immediate future there must be much closer co-operation between the machine tool designer and the gauge designer if we, in this country, were not to fall behind others as regards rates and methods of high-quantity production.

APPLICATIONS OF COMPRESSED AIR

Some interesting examples of the use of compressed air were included in the paper entitled "A User's Experience," which was presented by

Mr. W. G. Wood (Rolls-Royce, Ltd.). The press seen in Fig. 3 is employed for both extruding and, subsequently, heading a component. After the extruding stage, the workpiece is pushed up through the die by means of an air-operated plunger which bears against the lower end. The speed at which the part is ejected can be regulated by varying the pressure of the air in the cylinder, by means of a pedal.

With this arrangement, the operator has complete control over ejection and has ample time to grip the workpiece with tongs and transfer it to the heading die which is housed in the same bolster. The part is ejected from the heading die by a blast of compressed air, which blows it clear through a distance of about 6 in.

After certain machining operations, the parts are transferred to a Brayshaw through-feed furnace, where they are heated prior to a stamping process. The entry side of this furnace is equipped with two horizontal conveyors, one on either side of the furnace door, which are arranged at right angles to the direction of flow through the furnace. Each conveyor is operated by an air cylinder, and incorporates a number of transverse troughs for holding the components. The conveyors are indexed alternately, to drop one workpiece at a time into one of a pair of troughs positioned in front of the furnace door, and a further pair of air cylinders is employed to push the parts endwise into the heating chamber. These cylinders are interlocked with those for operating the conveyors,

so that the left-hand conveyor and the right-hand loading ram operate in unison, or *vice versa*, depending on which loading trough was last filled.

When the furnace is charged to capacity, the entry of a new component causes a heated part to be discharged, and the movements of the conveyors and loading rams are under the control of the stamping press operator, who is stationed at the exit end of the furnace.

A considerable increase in productivity, it was stated, had been achieved by operating the furnace in this manner, as hitherto these parts had been heated in an open-face furnace, which had to be charged to capacity. While the parts were being heated, the stamping press stood idle, and, when they were brought to the required temperature, the entire batch had to be stamped before the furnace was re-loaded, as the soaking time for the particular part was critical. As no fresh parts could be loaded into the furnace during the stamping operation, there was again a delay while a fresh charge was heated.

The machine shown in Fig. 4 is used for polishing turbine blades by means of an abrasive belt, which is pulled backwards and forwards across a suitably-formed die. The particular set-up shown in the figure is for polishing the concave surface of a blade which is mounted in the fixture beneath the belt. Above the fixture can be seen the die, with the belt in place, and this die has a number of transverse slots along its entire length. Each of these slots is connected to a longitudinal hole




Fig. 4. On this Abrasive-band Machine for Polishing Turbine Blades, Compressed Air Serves to Keep the Band in Overall Intimate Contact with the Blade. Air is Supplied to the Die around which the Band is Flexed, and Escapes through Slots Machined in the Curved Surface




Fig. 3. On this Press, which is Used for an Extruding and a Heading Operation, the Component is Pushed up Through the Die, after the Extrusion Stage, by an Air-operated Plunger

in the body of the die, and this hole is connected to the compressed air supply. When the die and belt are lowered, so that the latter comes into contact with the blade, the compressed air ensures that the belt is kept in overall intimate contact with the workpiece. Moreover, as the air escapes, it provides a cushion between the face of the die and the back of the band, so that wear on both these items is reduced.

AIR-OPERATED EQUIPMENT

The final paper of the Conference, which was delivered by Mr. N. P. Watts, M.S.M.A. (Benton & Stone, Ltd.), was entitled "Air-operated Equipment." In his opening remarks, Mr. Watts commented on the fact that recent developments in the field of cutting tools had enabled spindle speeds and feed rates to be increased, with the result that hand-




Fig. 5. H.M.E. Crank Press with a 6-in. Air Cylinder for Counterbalancing the Slide. The Expansion Chamber seen Between the Frames Ensures a Constant Pressure of Air

ling time was tending to occupy a greater percentage of the production cycle. Appreciable savings could be effected in this respect by the use of pneumatically - operated loading, clamping, and ejecting mechanisms. Such mechanisms also ensured a more consistent production rate and reduced operator fatigue.

In connection with the latter point, Mr. Watts referred to a particular Taylor & Challen 200-ton press on which all the controls were air-operated. One advantage which had been obtained by controlling the press movements in this manner was that the operation of the main clutch was effected positively, and at a predetermined speed. Normally, all the force required to depress the clutch pedal was supplied by the operator,

and, when he became tired, there was a tendency to engage the clutch in a hesitant manner, which resulted in severe wear of the main driving key.

An H.M.E. crank press, a close-up view of which is given in Fig. 5, incorporates a 6-in. diameter air cylinder to counterbalance the weight of the slide and relieve the bearing load, so that the life is increased. Pressure of the air is adjusted to suit the weight to be carried, and the expansion chamber seen between the frames is provided to maintain a constant pressure. It may be noted that the guard on this machine is foot-operated, and that the final closing movement serves to actuate a control valve for the air supply to the clutch cylinder.

An example of air-operated equipment for automatic assembly is illustrated in Fig. 6. This machine, which was developed by a well-known radio manufacturing company, provides for assembling and clinching tags to the panel at the left in Fig. 7, at the rate of 30 per min. A completed panel, with the tags assembled and clinched, is seen at the right in this figure. It may be noted that with the previous method of assembly, which was entirely manual, the maximum output obtained was only two complete assemblies per min.

As can be seen from Fig. 6, the machine incorporates a 24-station, air-operated rotary table, and




Fig. 6. A 24-station, Pneumatically-operated, Fully-automatic Machine for Assembling and Clinching Radio Panel Tags




Fig. 7. (Left) A Blank Panel. (Right) A Panel with the Tags Assembled and Clinched. The Tags are Delivered to the Machine in Strip Form

the blank panels are fed to this table from the magazine at the extreme left. Adjacent to this unit there is mounted a "no-panel" control, in the form of a micro-switch, which gives a signal when the supply of blanks in the magazine has been exhausted, and automatically stops the operation of the machine.

Tags, for the right- and left-hand groups of holes in the blank panel, are fed in continuous strip form

from the two reels seen above the machine. After insertion in the panel, each tag is twisted, to clinch it in position, and the assembled section of strip is sheared, to separate it from the remainder of the coil. To ensure the specified clearance between the tags, when they have been twisted, the machine incorporates a siding plunger, which is operated by the air cylinder seen just to the left of the ejector chute, in Fig. 6.

In Fig. 8 is shown a rear view of this machine, in which most of the pneumatic equipment is visible. Here, may be seen the air cylinder for operating the shearing tool, also two silencers in the bottom left-hand corner. The top plate of the rotary table, the die assembly, and the magazine can be changed, to enable this machine to handle panels with either 8 or 12 tags. The control system, which is entirely electro-pneumatic, is sequentially arranged so that the completion of one movement initiates the next, and is fully-interlocked to ensure that the rotary table cannot index until the tools are clear, and that the tools cannot operate unless the rotary table has completed its indexing movement.

A LARGE SOLAR FURNACE INSTALLATION is being erected at the U.S. Quartermaster Research and Engineering Centre, Natick, Mass., U.S.A., to provide temperatures comparable to those generated near atomic explosions. This furnace will be employed for preliminary tests on materials intended for protection against the thermal effects of such explosions.

The installation, which will have an energy equivalent of about 28 kW., will comprise four principal units. At one end there will be a flat heliostat mirror measuring 40 by 36 ft., which will be automatically positioned so that the sun's rays will be constantly reflected on to a concentrating mirror, which is located at the opposite end of the installation, 96 ft. away.

The concentrating array will comprise 180 curved surface mirrors, each of 23.5 in. diameter, which will focus the beam in the test chamber, located between the two mirrors. An alternator, in the form of a venetian blind type shutter will be provided between the concentrator and the chamber, to enable temperature to be controlled. The heated area within the chamber will have a diameter of 4 in.





Fig. 8. A Rear View of the Machine Shown in Fig. 6

Blanking "Number" Anodes from Thin Strip



Some unusual production problems are encountered in connection with components for electronic computers. An example is afforded by a set of delicate "number" anodes, 0.005 in. thick, for an all-electronic numerical indicator tube. The width of the metal varies with the number, but

may be as little as 0.007 in. By means of tools of special design, and high quality tool-making, the Be Cu Manufacturing Co., Newark, N.J., U.S.A., are making these unusually narrow parts as stampings. A group of the number anodes is seen in the heading illustration.

Ten anodes, for the numbers from 0 to 9, are mounted in the glass envelope of the numerical indicator tube. When a tube of this type is connected in a suitable electronic circuit, any individual number can be made luminous by applying the proper voltage to the anode. This tube was specially developed for use in electronic instruments such as digital computers and counters.

Proportions of the anodes must be held within close limits to ensure clear reading of the one luminous numeral, despite the fact that all the anodes are arranged in a pack facing the viewing end of the tube. The form and limits for the number 8 anode are indicated in Fig. 1.

Design considerations demand that the numbers should have approximately equal surface areas. Since each number has a different developed length, the face width of the metal forming a digit is adjusted to obtain the desired area. Widths range from 0.032 to 0.034 in. for the number 1 to 0.007 to 0.008 in. for the number 8. Seven of the numbers have the same cross-sectional width, namely, 0.011 to 0.012 in. Although experimental numbers were subsequently made from several different metals, the dies were originally designed to stamp the anodes from 0.005-in. thick strips of an alloy containing 80 per cent nickel and 20 per cent chromium.

Owing to the extremely small clearances required between the punches and dies it was not possible




Fig. 1. Details of the Stamping for the Number 8 Anode Used in an All-electric Numerical Indicator Tube




Fig. 2. Number 2 Anodes (foreground) are Produced with this Tool. The Three Basic Parts are the Punch (centre), Die (right) and Punch Guide (left, lower face up)

to use standard die sets. Instead, progressive dies, of a type previously employed by the company for producing sub-miniature parts, were designed and constructed. Since the 6 and the 9 are made from the same die, only nine dies were required. Dies for the anodes 2 and 8 are shown in Fig. 2 and 3, respectively.

The tools were designed for operation in a short stroke press and each consists of three parts—the punch, a punch guide, and the die. The punch guide serves three purposes. It guides the punch, holds the workpiece in place during the stamping operation, and then strips the part.

Since the individual punches do not leave the punch guide, its thickness and the length of the punches both depend on the stroke of the press and the length of bearing required for satisfactory punch guidance. For the anode tools, the punch guides are approximately 1 in. thick. To permit of feeding the stock, two pairs of springs seated in the die lift the punch guide when the punch is in the raised position. This vertical movement is restricted by four relieved cap-screws secured to the die, and alignment is maintained by four pins mounted on

the punch guide. The downward motion of the punch is transmitted to the punch guide by means of two springs mounted between the two members. The lower and upper surfaces of punch guides are seen at the left in Fig. 2 and 3, respectively.

A small guide plate, with holes of the exact shapes of the individual punches, is part of the punch guide, and is secured to the underside of this member. When the punch descends, this plate is lowered between the stock guides, contacts the top of the work, and holds it securely in place with a force of about 50 lb.

The upper tool incorporates the individual punches, and a punch-holder which fits into a




Fig. 3. Four Stamping Operations are Required to Produce the Number 8 Anode. The Die with the Punch Guide in Position is Seen at the Left. In operation the Punch (right) Never Leaves the Punch Guide

T-slot in the ram of the press. A slight amount of float is permitted between the punch and the ram, so that the punch guide alone directs the motion of the punches. The latter are machined to the required anode shapes over a distance which is only a little greater than the stroke of the press. For convenience, the remaining length of each punch is made rectangular in section and serves for guidance and support. The punch guide (with the exception of the lower guide plate) is made to suit the rectangular portion of the punches.

Each lower tool consists of four parts: two guides for the strip stock, a die-plate, and the die-holder. The die for the number 2 anode is seen at the right in Fig. 2. Two punches straddle the strip stock and cut away a portion from each side at each stroke of the ram. When the metal is advanced, the forward edges of the untrimmed portion engage stops in the two guides.

In operation, as the press ram descends, the punch-holder compresses the springs in the upper face of the punch guide. The punch guide then moves down, against the action of the springs in the die, to contact and hold the stock firmly. With continued downward movement of the ram, the punches, directed by the punch guide, stamp out the workpiece. On the up-stroke, the punches are stripped from the work before the punch guide is allowed to rise.

Due to the delicate nature of the anodes, the strip stock is advanced manually along the work guides to the stop for the next stamping operation after each stroke of the ram. As many as four stations are employed for stamping a number. Stages required to produce the numbers 2 and 8 are indicated by the strips in the foreground in Fig. 2 and 3. Anodes are left in the strips for transport.

The dies are made entirely from a high-carbon high-chrome steel, with low warping characteristics. Punches, and the die plates, are hardened to 60 to 62 Rockwell C. The clearances between the punches and the dies are not easily measured but are of the order of 0.0002 in.

Anode shapes were first laid out on pieces of aluminium $\frac{1}{8}$ in. thick. These shapes were then cut out on a band saw and filed to within about 0.002 in. of the desired forms. Then, using the shapes as templates on a pantograph milling machine adjusted to a 5 to 1 ratio, the punches were produced.

After they had been hardened, the punches were used to lay out the holes in both the die-plate and the bottom plate for the punch guide. The material to be removed is machined and filed away until the punches can be employed as broaches to finish the holes.



Fig. 4. Set-up for Electric Discharge Machining a Square Hole of 0.052-in. Side in a Die Plate. A Brass Electrode is Employed

For convenience in machining the upper rectangular-shaped guide holes, each punch guide is made in a number of pieces. Spark machining also facilitated the production of the tools. In Fig. 4, an Elox electric discharge machine is shown set up for producing a small rectangular hole in one of the die plates.

DIAMOND HONING UNHARDENED STEEL. Diagrit Diamond Tools, Ltd., Pattenden Lane, Marden, Kent, report that considerable economies are being obtained by diamond honing bores in rocker arms for Rootes diesel engines. These rocker arms are machined from forgings of En 16T steel, and a special bond was developed to enable the bores to be honed with diamond, while in the soft state, without picking-up. It is stated that, as compared with the use of conventional abrasive sticks, the cost of honing the large centre bore has been reduced from 3.5 to 1.7d. The corresponding figures for the outer bores, which are of smaller diameter, are 2.5 and 1.1d. (each). Apart from this economy, there has been a saving in setting time, and rounder and more accurate holes are said to be obtained with the diamond hones.

Holbrook Precision Mould Maker's Lathe

The Holbrook Machine Tool Co., Ltd., Stratford, London, E.15, have introduced the Model M No. 15/20 precision mould maker's lathe, shown in Fig. 1, which has been developed from their Model D No. 15 toolroom lathe, and is noteworthy for its versatility. By the provision of a slow-speed unit for the headstock, a pitch variator, hydraulic copying slides, internal and external thread milling heads, and internal and external grinding attachments with diamond wheel dressers, it has been made possible to complete a mould in one setting.

Workpieces up to 30 in. long are admitted between centres, and the swing capacity over the bed is 21 in., and over the carriage, 14 in. For normal turning operations, 18 spindle speeds, from 15 to 1,000 r.p.m., are provided, the main drive being taken from a 5-h.p. motor. For thread milling, a range of 18 slow speeds, from 0.15 to 10 r.p.m., is obtainable through a worm

and worm-wheel and a separate motor, of 1 h.p., mounted on top of the headstock. A control lever on the headstock mechanically and electrically interlocks the two drives for safety purposes.

A panel on the front of the headstock houses push-buttons for "forward," "stop," "reverse" and "inching" control of both driving motors, and electric limit switches are provided on each side of the carriage whereby the motors can be automatically stopped by dynamic braking, when cutting threads in either direction of carriage traverse.




Fig. 1 (above). Holbrook Model M No. 15/20 Mould Maker's Lathe. The Design of this Machine and the Equipment Provided Enable a Mould to be Completed in One Setting




Fig. 2. Set-up on the Holbrook Lathe for an Internal Thread Milling Operation on a Mould, which is Shown in Section, for Clarity




Fig. 3. Rear View of the Lathe Showing the Application of a Rotating Master for Producing a Non-circular Form

The quick-change gearbox provides 60 threads from 1 to 60 t.p.i., and a range of sliding and surfacing feeds, from 0.001 to 0.062 in. per spindle rev.

Fig. 2 shows the lathe set up with the internal thread-milling attachment. The drive to the latter is taken by belt from a motor and bracket unit, not shown, which is applicable to the various other attachments that are available. In this illustration, the workpiece, shown in section for clarity, is mounted in a chuck, which, in turn, is carried on an index plate attached to the spindle nose. Adjustable trips are provided on the plate which operate a limit switch to stop the headstock motor when the workpiece has rotated through the required number of degrees, as required, for example, when a milled thread must start and finish in specified angular positions.

A pitch variator is

in. per inch for 12 in. of carriage travel, to 0.013 in. per inch for 30 in. of travel, is obtained.

Provision is made for hydraulic profiling from both the lower cross slide and the swivelling compound slide, and a 1 to 1 ratio gear drive from the headstock spindle to a chuck at the rear enables a rotating master to be employed when a non-circular

fitted at the tailstock end of the bed, which enables internal or external threads of increased or decreased pitch to be produced, as is necessary where provision must be made for moulding contraction. The variation is obtained by means of a hardened steel transverse slide, which is coupled to the lead screw by change gears, and produces an axial movement of the lead screw abutment, and therefore of the screw itself, during the carriage traverse. A built-in safety switch prevents over-run of the transverse slide. With this arrangement, an increase or decrease of pitch ranging from 0.033




Fig. 4. Set-up for Turning Shafts and Other Shouldered Workpieces

form is to be produced. Fig. 3 is a view from the rear of the lathe showing a rotating master. The shouldered form on the workpiece in the axial direction is produced by the hydraulic copying slide of the compound rest, which is set at an angle of 45 deg. and is controlled by a template mounted along the front of the carriage. The oval, rotating master is engaged by a stylus on the lower cross slide, which is actuated by a hydraulic piston and cylinder at the rear. For normal turning operations, the lower cross slide is anchored to the bed by the tapered stud which, for the application shown, couples the lower cross slide to the hydraulic cylinder.

Profiled workpieces, for example, bottle moulds, can be copy turned by mounting the stylus unit on the main cross slide, the form being controlled, during the carriage traverse, by a flat template attached to brackets at the rear of the bed. A mechanical taper turning attachment, for tapers up

to 14 in. long, is also included in the equipment.

With the swivelling hydraulic copying slide set at an angle of 45 deg., as seen in Fig. 4, shafts and other components with square shoulders can be turned, using a template holder which extends in front of the carriage, and is attached to brackets fastened to the bedways. Transverse copying, using the cross-slide traverse motion, can be performed under the control of a template mounted transversely on the carriage. A travel of 3 in. is provided for the swivelling hydraulic copying slide, and the top slide has a hand adjustment of 2½ in. The tool-post itself is also adjustable along dovetail ways for setting purposes.

Pressure oil for the hydraulic copying slides is supplied by the self-contained, motor-driven pump unit seen at the right-hand end of the machine. The electric contactor gear for the main drive and other units is housed in a separate cabinet, remote from the lathe.

Bedford Mobile Gauge Inspection Unit

James Bedford & Co. (Halifax), Ltd., Victoria Road, Sowerby Bridge, Yorks, have recently developed the mobile unit, here illustrated, to facilitate the inspection of gauges and tools. Its use avoids the need for withdrawing gauges and jigs from machine and assembly lines for periodic checking. Regular tours of inspection can be organized through a large factory, so that a close check can be kept on all gauges in current use. In this way, man-hours can be saved, and the number of gauges required can frequently be reduced.

There is a large foolscap drawer for filing records and a drawer and cupboard for carrying instruments and spare gauges. If required, a 50-ft. extension flex, with a spring-operated take-up reel, can be provided, to supply power for electric comparators and other types of electrically-operated instruments.

Measuring 42 by 24 in., the top of the unit is covered with green linoleum, and a chromium-plated

edging strip is fitted which prevents instruments from sliding off.


A pull-out writing shelf is provided and there is a folding stool for the inspector. The drawers have ball-bearing slides, and both the drawers and cupboard are fitted with locks. The unit, which is made of sheet steel and is 36 in. high, is mounted on ball-bearing, rubber-tyred wheels and can be easily manoeuvred.



**Bedford Mobile Inspection Unit which
Enables Gauges and Tools to be
Checked on Site**

Round Olympia with a Camera

The Gauge and Tool Exhibition





This combination tool, exhibited by Lenchs (Birmingham), Ltd., is fitted with inserts of a new wear-resisting grade of Oakaloy tungsten carbide, to withstand the severe conditions involved in the production of condenser laminations from silicon steel strip. The main shape of the laminations is produced by a punch having a one-piece carbide end surface, in conjunction with a die aperture lined with carbide strips. Solid carbide bush inserts in the die plate, and carbide-tipped punches, provide for the production of rivet holes




Among the exhibits on the stand of W. H. Marley & Co., Ltd., were these broaches for finishing wave-guide flanges and examples of components produced with them. The cutting teeth on the broaches are arranged to operate on opposite sides of the rectangular openings in succession. Two sides, which have been finished by the first sets of teeth, can thus be employed to guide the broach while the second sets are cutting. In this way it is ensured that the finished surfaces are exactly at 90 deg. to their adjacent sides

With this set-up on a British-built U.S. multi-slide machine, shown by Rockwell Machine Tool Co., Ltd., electrical switch contacts were being produced from 16-s.w.g. brass strip, 1½ in. wide. After piercing, slotting, cropping and forming operations have been completed in a press tool near the machine centre, the part is gripped by positively-acting fingers, and cropped from the strip. Next, the part is formed to a U-shape round a vertical post, and then pushed down the post to a position at which a long and a short slot are punched in the bottom of the U-shape, before the piece is ejected






This exhibit, by Hayes Engineers (Leeds), Ltd., was staged to demonstrate the accuracy with which the movements of machine slides can be controlled by the Hayes 180-deg. hydraulic tracer control valve. A vertical slide is moved down by a hydraulic cylinder, for which the supply of oil is controlled by a valve mounted on the slide, until the valve stylus touches the horizontal surface. A dial gauge carried on the slide is graduated in 0.0001-in. divisions and the accuracy with which the slide is stopped, normally within 0.001 in., is checked by successive readings of the gauge.



Solex (Gauges), Ltd., showed this unit which is designed for the inspection of three diameters on rear axle pinion shafts. Held between centres, the shafts are engaged by standard Solex caliper gauging units, and the readings are shown on the manometer tubes at the rear. In addition, there are three sets of coloured lights on an inclined surface below the manometers, labelled "all dimensions O.K.," "over size" and "under size," separate lamps being provided for the two latter conditions of each of the three diameters. The manometer tubes are automatically topped-up to compensate for evaporation.




The only parts of this fixture, shown on the stand of Wharton & Wilcocks, Ltd., which are not included in the kit for the basic Wharton system are the graduated indexing table and its associated jigs. When four $\frac{1}{8}$ -in. holes have been drilled in the top face of a light alloy valve body, the fixture is turned through 90 deg., so that it rests on feet on the further side, and four more holes of $\frac{1}{8}$ in. diameter are drilled in the outside bosses. The bush plates are hinged so that they can be swung aside for loading, and the partly-machined casting is positioned by a central bore and by the outside bosses.

Hot forging of T-pieces from brass and duralumin billets was demonstrated on this 100-ton press by Taylor & Challen, Ltd. As described in *Machinery*, 91/258-2/8/57, this machine incorporates a mechanism at the right-hand side whereby a punch slide can be reciprocated very rapidly to administer a stabbing blow. This action occurs immediately after the toggle vice has closed and the top and left-hand side punches have operated. The effect is to backward-extrude a solid portion of the billet, to produce the longer branch of the forging



Among examples of applications of Sintox ceramic cutting tool tips on the stand of the English Steel Tool Corporation, Ltd., was this 12-in. diameter face milling cutter. Equipped with 12 Sintox blades, the cutter is designed for milling operations on graphite blocks employed in nuclear reactor construction. The high abrasion resistance of the ceramic enables a life up to 10 times that of high-speed steel blades to be obtained. The blades are held by a patented clamping arrangement which allows for accurate adjustment, and they can quickly be changed

B.I.P. Tools, Ltd., showed this 64-cavity injection moulding tool for the production of hair curlers from polystyrene. The mould cavities were made from separate pieces of beryllium copper by the hot hobbing process and were subsequently machined to size before being fitted into the tool. Because of the higher heat conductivity of beryllium copper, the mould can be operated on a shorter time cycle than could a similar mould with steel cavities, resulting in an increase of about 20 per cent in productivity



New Equipment at the Fifth Gauge and Tool Exhibition

Attention has already been drawn in earlier issues of MACHINERY to some of the recently introduced items which were shown at the Gauge & Tool Exhibition, and some other new products displayed are here considered.

MATRIX 3-DIMENSIONAL MEASURING MACHINE

Developed from the Matrix No. 59 jig borer, the measuring machine shown in Fig. 1, which was exhibited by the Coventry Gauge & Tool Co., Ltd., Fletchamstead Highway, Coventry, is intended for checking a variety of workpieces in three planes to a high degree of accuracy.

The spindle is rotated by a handwheel only, and the quill in which it is mounted has 4 in. of axial adjustment in bearings of the ball-circulating type, settings being made to an accuracy of 0.0001 in. by means of an optical scale. The arrangement is such that there is no deflection of the spindle when sideways pressure is applied to the handwheel. An adjustable counterbalance system is provided which ensures easy movement of the quill, and enables the contact pressure between the workpiece and a stylus pin attached to the spindle to be varied down to 8 oz. The spindle nose has a taper bore to take different interchangeable stylus heads.

A Talymin (Taylor, Taylor & Hobson, Ltd.) measuring unit can be provided which gives magnifications of stylus movements from 100 to 5,000 \times in six steps. The amplifier is mounted on a platform at the side of the bed, as shown, and there is a second platform on the column to take the dial-type instrument whereby readings are obtained. The stylus head enables bores from 0.1 to 4 in. diameter to be checked.

A microscope, incorporating a setting square, is available, which permits templates and profile shapes, for instance, to be checked in relation to a datum face. A third attachment has a stylus pin with a $\frac{1}{2}$ -in. diameter ball end, and is intended for the inspection of aerofoil shapes. Cams and irregular shapes may also be checked on the machine with the aid of an optical dividing head or a rotary table.

As on the jig borer, the 18- by 12-in. work table has a longitudinal movement of 12 in. and a cross travel of 8 in., and settings to an accuracy of

0.001 in. are obtained by leadscrews and corrector bars in conjunction with vernier scales. Rapid power traverse at the rate of 32 in. per min., for coarse setting, is provided by separate push-button controlled motors. A third motor drive gives rapid power adjustment of the column vertically, and a maximum distance of 22 $\frac{1}{2}$ in. is obtainable between the spindle nose and the T-slotted working surface of the table. The distance between the centre line of the spindle and the column is 10 $\frac{1}{2}$ in.

PRECISIONAIRE AIR GAUGING EQUIPMENT

The exhibits of M.P.J. Gauge & Tool Co., Ltd., Hansons Bridge Road, Erdington, Birmingham 24, afforded an indication of some of the many applications of the Precisionaire range of air gauging equipment which they have recently started to




Fig. 1. Matrix 3-dimensional Measuring Machine




Fig. 2. The Sheffield Airetest Attachment for a Height Gauge is Here Shown Set Up in Conjunction with a Hommel Height Micrometer and a Precisionaire Column-type Indicator Unit

make under licence from the Sheffield Corporation, Dayton, Ohio, U.S.A.

Of particular interest was the new Airetest attachment, shown in Fig. 2 fitted to a height gauge, and set up in conjunction with a German-made Hommel height micrometer (Catmur Machine Tool Corporation, Ltd.). Alternatively, the attachment may be used, for example, on machine tools for checking workpiece bores for concentricity, and on lead testers and gear checkers. Measuring only $4\frac{1}{2}$ in. long by 1 in. wide by $\frac{1}{4}$ in. thick, the attachment may be connected by flexible hose to a Sheffield indicator unit of the dial type or the Precisionaire column type, as shown, and the latter can be supplied to give magnifications of 1,000, 2,000, 5,000 and 10,000 \times . The contact pressure between the stylus pin and the workpiece is approximately 3 oz. A setting block is provided for calibrating column-type indicator units with magnifications of 1,000 and 2,000 \times , and for adjusting the tolerance pointers. Calibration of indicator units with higher magnifications is carried out with the aid of slip gauges.

The Centrefind centring attachments, which were on view, are available in three designs designated types CF 100, CF 200, and CF 300, and may be used in conjunction with Sheffield dial or column indicator units. The CF 100 attachment, shown on the right-hand side in Fig. 3, has a clip-type mounting sleeve, and the CF 300 unit, seen in the demonstration rig on the left, is intended for use on jig grinders. Intended particularly for use on jig borers, the CF 200 attachment is of similar design to the CF 100, except that the stylus pin is carried in a hinged plate with screw adjustment, to facilitate fine radial setting.

The central portion, which incorporates a connecting piece for the flexible air hose, is prevented from rotating while centring is in progress, and since the indicator units give high magnification, very accurate settings can be made. Another advantage of the attachments is that, because a separate non-moving indicator is employed, readings can be observed conveniently during the entire 360 deg. movement of the stylus pin. Interchangeable stylus pins of different designs can be fitted quickly for checking internal and external surfaces for concentricity, also end faces of the work for squareness. The body of the attachment has a spherical seating to take the ball-shaped upper end of the stylus pin, which is retained by a knurled nut, and can thus swivel freely so that it can be brought into contact with the work.

Reference may also be made to a set-up which was demonstrated for checking workpiece surfaces for flatness. For this application, a Plunjet measuring head, connected to a high-magnification column-type indicator unit, is housed in a bore at the centre of a surface plate, so that its ball shaped



Fig. 3. Two Examples of Sheffield Centrefind Centring Attachments




Fig. 4. The "Precision Grinding" Wheel Dressing Attachment is Here Shown Mounted on the Wheelhead of a Jones & Shipman No. 1400 Surface Grinder

end projects slightly above the level of the plate. When a workpiece is passed over the measuring head, while in contact with the plate, any irregularities of surface flatness are shown by movement of the float in the indicator unit.

WHEEL DRESSING ATTACHMENT WITH OPTICAL RADIUS-SETTING FACILITIES

In Fig. 4 is shown a close-up view of a Jones & Shipman No. 1400 surface grinder, the wheelhead of which carries a new diamond dressing attachment introduced by Precision Grinding, Ltd., Mill Green Road, Mitcham, Surrey. On the worktable is mounted the P.G. optical dividing head and Profoscope equipment, the latter enabling accurate inspection of the work to be carried out while profile shapes are being ground.

This new wheel dressing attachment may also be used on the Jones & Shipman No. 1500 machine, and mounting brackets of different designs can be provided to suit other makes of surface grinders. An arm, which carries the diamond holder, is mounted on a compound slide, and the lower portion can be adjusted towards and away from the centre-line of the wheel by a knob, and secured in the required position by a clamping screw. Accurate settings of the diamond, for convex and concave radii up to $\frac{3}{8}$ -in., are made with reference to a graticule, which is viewed

through the eye-piece of a microscope.

The arm and compound slide assembly can be swivelled about the axis of the microscope, and angular movements are controlled by adjustable stops which can be set by means of a scale. When radius-dressing is being carried out, the upper part of the compound slide is held in the central position by two latches, which are swung downwards on each side of a stop pin on the slide. At the end of the swivelling motion, in either direction, one of these latches may be brought clear, and cross movement applied to the slide by a knob through a rack and pinion, for dressing an angular surface on the wheel, tangential with the radius. In this way, the angular portion may be smoothly blended with the radius.

A pair of screw-operated slides carry the microscope and compound slide assembly and it can thus be adjusted parallel with and at right angles to the wheel spindle, to suit grinding wheels with different diameters and face widths. These slides have micrometer adjustment, and the cross travel enables different settings of the diamond holder to be obtained, so that profile shapes can be dressed on fairly wide wheels in a number of stages.

A DIAL INDICATOR SCREW RING GAUGE

Among the exhibits of Tolimit Gauges, Ltd., Peterborough Road, London, S.W.6, was noted the new dial indicator screw ring gauge illustrated in Fig. 5, which enables external threads to be checked for both full form and effective diameter.

The gauging elements comprise two pairs of chaser-type pieces, which are set at right-angles, and are moved radially into and out of the gauging position by a lever-operated cam arrangement. When the lever is set in the central position, as shown, all the gauging elements are brought clear to permit of loading and unloading the workpiece. Movement of the lever in one direction causes the gauging elements for checking threads for full form to be brought into contact with the work. When the lever is swung in the opposite direction, these elements are moved clear, and the second pair is brought into use for gauging the effective diameter. The dial indicator is adjusted for zero with the aid of a setting master. This gauge is available in three sizes for checking threaded parts

up to $\frac{1}{8}$, from $\frac{1}{8}$ to $\frac{1}{4}$, and from $\frac{1}{4}$ to $\frac{1}{2}$ in. diameter, and the elements can be readily changed for others with different thread forms.

AIR-ELECTRONIC MATCHING CONTROL FOR A CYLINDRICAL GRINDER

Another interesting new development by this company is a differential air-electronic matching control system which was demonstrated on a modified Matrix type 1A cylindrical grinder (The Coventry Gauge & Tool Co., Ltd.). With this system, the diameters of male parts are automatically controlled during the grinding cycle, so that a predetermined clearance or interference fit is obtained when they are mated with female parts which may have bores of slightly different diameters.

The machine on which the demonstrations were given had been fitted with a servo motor drive for providing automatic in-feed, also rapid advance and return of the wheelhead at the beginning and the end of the working cycle. A view of the machine, also the cabinet which houses the equipment for controlling the grinding cycle, is given in Fig. 6. On top of the cabinet may be seen, at the right, the plug gauge unit on which the female part is mounted for reference purposes during the grinding cycle, and, at the left, the indicator head, of the liquid column type, for the gauging system.



Fig. 5. Tolimit Dial Indicator Screw Ring Gauge


The indicator head is connected by a flexible air hose to a caliper-type sizing attachment carried by the wheelhead, which is swung into engagement with the work, by hand, at the beginning of the grinding cycle.

The head incorporates two photo-transistor units which can be freely adjusted vertically in the body, and the liquid is contained in a transparent tube of triangular cross section. With this arrangement, when the level of the liquid falls below one of the transistor heads, the latter is energized by light rays which are transmitted by a built-in lamp and reflected from the tube.

For setting purposes, one of the female parts from a batch is mounted on the plug gauge unit, a male component, which has been previously ground to give the required clearance or interference fit, is held between the centres on the grinder, and the sizing attachment is swung into engagement with it. Next, a knob on the sizing attachment is adjusted until the level of the liquid in the tube coincides with the bottom edge of the lower photo-transistor unit. The upper photo-transistor unit is then adjusted independently so that the distance between it and the lower unit represents the amount by which the workpiece diameter will be reduced during the spark-out period of the grinding cycle. Since the gauging equipment, on the set-up which was demonstrated, gave a magnification of 7,500 to 1, and reduction of workpiece diameter during the spark out period was of the order of 0.0004 to 0.0005 in., the photo-transistor heads were set several inches apart.

When another female component has been loaded on to the plug gauge unit, and a fresh male part has been placed between the centres, the grinding cycle is started by depression of a push-button on a panel at the front of the bed. Thereupon, the wheel-head is moved, under rapid power traverse, towards the work, and the work-head drive motor is started. At a predetermined point of the wheel-head travel, in-feed is automatically brought into operation, and a signal lamp on the push-button panel is illuminated. During the final stage of the actual grinding cycle, the level of the liquid in the tube falls, and as it moves clear of the upper photo-transistor unit, a signal is transmitted to the control equipment which causes the in-feed motion to be interrupted. Sparking out then proceeds, and when the level of the liquid has fallen until it clears the lower photo-transistor, a second signal is transmitted to the control equipment, with the result that the wheel-head is rapidly traversed away from the work, and the work-head motor is stopped in readiness for unloading the piece. Four coloured signal lamps are mounted

Fig. 6. A Matrix Type 1A Cylindrical Grinder Fitted with the Tolimit Air-electronic Matching Control Equipment



on the side of the indicator head, and are automatically illuminated, in turn, at the beginning of each stage of the grinding cycle.

If required, a third photo-transistor unit can be provided for the indicator, and coarse and fine infeeds for rough and finish grinding, as well as a dwell period for sparking out, can then be obtained automatically.

Air-electronic sizing equipment of similar design, but without the matching control system, was

demonstrated on a second modified Matrix machine, which was set up for grinding parts to a predetermined diameter, on an automatic cycle.

Trade Publications

STERN & BELL, LTD., Stour Street, Birmingham, 18. Catalogue listing the wide range of types and sizes of steel which can be supplied from stock.

C.V.A. SMALL TOOLS, LTD., 161 Victoria Street, London S.W.1.—Leaflet describing the C.V.A. Electro-Etch marking pencil which is employed with a special tungsten needle. Three thicknesses of writing can be obtained by voltage adjustment.

SOAG MACHINE TOOLS, LTD., Juxon Street, Lambeth, London, S.E.11.—Stock list covering an extensive range of machine tools many of which have been rebuilt to Schlessinger limits. Machines are conveniently classified for ease of reference, and brief particulars are included for each item. Representative examples are illustrated.

JOSEPH BATSON & CO., LTD., Tiptone Works, Tipton, Staffs.—Folders concerned with the company's Tiptone Die lubes for use in connection with hot or cold metal working operations such as deep drawing, extrusion, die casting and forging, also with equipment for dispensing these lubricants. The latter includes self-contained automatic units which are supplied to suit particular machines, also hand-operated guns.

CREED & CO., LTD., Telegraph House, Croydon, Surrey. Illustrated folder No. DP.2, describing the type 25 high-speed re-perforator which is the latest addition to the

company's range of tape-punching equipment. There are two versions of this unit, one for punching 6- and 7-track tapes, and the other for the standard 5-track tape. This re-perforator may be used in conjunction with a digital computer; as an output tape-punch for a variety of office machines; and for automatic recording applications.

W. CHRISTIE & GREY, LTD., 4 Lloyds Avenue, London, E.C.3. Illustrated booklet, No. 957, dealing with the wide range of vibration isolating equipment made by the company. Photographs of typical industrial applications are given, and a section is devoted to the fundamental theory of the isolation of vibration in its two forms—free and forced. Details are given of steel spring and rubber unit mountings; rubber, cork, cork-rubber, and felt isolating materials; and steel spring suspension mountings for the isolation of concrete foundation blocks and bases.

KLAXON, LTD., 49 Upper Brook Street, London, W.1. Fully-illustrated publication covering Klaxon motors which are available in various types and in numerous capacities from 1/100 to 1 h.p. A separate brochure is devoted to geared motors which are offered with a wide choice of arrangements and speeds. In addition, a recently issued loose-leaf catalogue is concerned with such products as instrument motors, shaded pole motors, ironclad and flameproof signals, industrial motor-driven hooters, and industrial buzzers.

News of the Industry

Manchester and District

CONDITIONS UNCHANGED AT THE FOUNDRIES.—Foundry trade conditions in the Lancashire area continue more or less unchanged. Localized under-employment persists, and as reduced amounts of overtime are being worked, there is no great pressure upon the Midland blast-furnaces for pig-iron supplies. At the same time, fresh business continues to be confined to orders for delivery in the near future. There has been no change in the quotations for pig-iron and haematite iron, and demand for the latter material is quietly steady. Moderate buying interest is reported in the various grades of finished iron materials.

SLOWING DOWN OF STEEL DEMAND.—For most descriptions of steel materials, less pressure for supplies is reported. Heavy steel plates continue to be the most active section, followed by large-diameter mild steel bars, special alloy steels and semi-finished materials for the forges and wire-drawing industry. The heavy electrical engineering and heavy machine tool industries are among the principal buyers of steel products.

B. & S. MASSEY, LTD., Openshaw, are experiencing a good demand for a wide variety of steam and pneumatic hammers and presses, from customers at home, in the Commonwealth and on the Continent. Orders have been received from both home and overseas railway companies. Work in progress includes steam hammers of various capacities; Clear-space type pneumatic hammers, with hand and foot control; large high-speed forging presses for the mass production of close-limit die-forgings; Marathon automatic drop hammers for the mass production of drop forgings to close limits; batteries of friction drop hammers and double-acting drop hammers; trimming presses; and tyre fixing rolls for securing the retaining rings in tyres of railway locomotive, carriage and wagon wheels. Since our last visit, various additions have been made to plant, and a new machine shop is at present in course of erection.

ENGLISH STEEL TOOL CORPORATION, LTD., North Street Works, Openshaw, are well employed on the production of a wide range of engineers' cutting tools, including taps, dies and chasers; twist drills and sockets; centre- and slot-drills; gear cutters and hobs; broaches; hand, machine and adjustable

machine reamers; milling cutters; side and face cutters; slotting cutters; slitting saws; end mills; lathe tools; and boring cutters; as well as special cutters of various types. Our attention was drawn to the new blank preparation department which is being established for concentrating on the rapid machining of the blanks of all types of shank tools. In addition to copy-turning lathes, the company has installed a Wickman 6-spindle, 1-in. capacity, bar automatic and two special machines for squaring and coning the ends of drill blanks. It is hoped to make further reference to this new department in due course.

RELIANCE GEAR & ENGINEERING CO. (SALFORD), LTD., Dickinson Street, Salford, still find it necessary to work overtime in order to meet the big demand for all types of gear-cutting. Considerable reorganization and building extensions have been carried out at these works further to facilitate production. An increasing demand for precision gears is reported and we may note the recent completion of a number of intermittent spur gears. Among the recent additions to plant are a Sykes 3C gear generator for spur gears up to 40 in. diameter by 3 D.P., a Parkinson Sunderland No. 19 double-helical gear planing machine of 56-in. diameter capacity, and a Gleason Coniflex No. 24A straight bevel gear generator for gears up to 36 in. diameter by 1 D.P.

DAVID BROWN INDUSTRIES, LTD., JACKSON DIVISION, Salford, recently produced a cast steel spur gear of 25 ft. 10 in. diameter and weighing nearly 25 tons, for driving the largest Aerofall ball mill yet made. This mill is being built by Harland & Wolff, Ltd., Glasgow, to the order of Aerofall Mills, Ltd., Toronto, Canada, and will be installed at the Sinoia copper mine of Mangula, Ltd., Southern Rhodesia, where it will be used for breaking copper ore. It weighs 225 tons, and is driven by a 1,250-h.p. motor, to give a mill speed of 14.1 r.p.m. The gear was cast in four sections, each weighing 7½ tons as cast. On the 20 in. face were cut 308 teeth of 1 D.P., and a forged steel driving pinion with 29 teeth was also supplied. At the mine, the mill will reduce 100 to 200 tons of ore to a size suitable for smelting in one operation. The ore is carried to the highest point inside the mill on projecting arms, and crushing is effected by impact when the ore falls to the

base, the broken pieces then being ground by rotary action. Automatic removal of the ground material when it reaches a predetermined size is effected by blowing a controlled air blast through the drum.

CRAVEN BROTHERS (MANCHESTER), LTD., Reddish, Stockport, have recently built a special double-headed horizontal boring machine for Lancashire Dynamo & Crypto, Ltd., Trafford Park, Manchester, for boring, facing and grooving operations on electrical stator casings.

The work is held stationary on a central table while the machining operations are carried out on both ends simultaneously by right-hand and left-hand headstocks. These three units are adjustably mounted on a heavy box-type, 2-shear bed. Each head is driven by a 7-h.p. motor and 12-speed gearbox mounted at the end of the bed, and the spindle speeds range from 6 to 120 r.p.m. Longitudinal feeds for boring range from 0.08 to 0.0133 in. per rev., and facing feeds from 0.030 to 0.005 in. per rev. The work table has a T-slotted surface measuring 24 by 42 in., and the height from the table top to the spindle axis is 15 in.

Each headstock has a longitudinal traverse of 33 in. on the bed, and the facing slide has a radial traverse of 7 in. It is hoped to describe this machine more fully at a later date. **H. B.**

Osborn's Precision Castings Foundry

Samuel Osborn & Co., Ltd., Clyde Steel Works, Sheffield, have purchased 73 acres of land on the Holbrook Industrial Estate, at Halfway, 7 miles from the centre of Sheffield. This land is intended for future developments, and, recently, a visit was arranged to the new precision castings foundry that has been erected on the site. The foundry is now engaged in the production of Socast steel castings, and is operated as a subsidiary company, under the title Osborn Precision Castings, Ltd. Socast steel castings are produced by precision moulding techniques developed by the parent firm, which include the shell moulding, Osborn Shaw and Osborn CO₂ block processes.



General View of the New Precision Casting Foundry of Samuel Osborn & Co., Ltd.

A general view of the new foundry is given in the accompanying figure, and the buildings are arranged in two long bays, each 200 ft. long by 50 ft. wide, with a 30-ft. wide service annexe of the same length. One of the larger bays is devoted to melting and casting, also the production of moulds and cores, and fettling, heat treatment and scrap storage are confined to the second bay. As many different grades of steel are melted, provision has been made for the effective segregation of scrap. Melting capacity is provided by three Birlec 5-cwt. and one 1-cwt. high-frequency furnaces, powered by two 200-kVA. generators. Factory heating is provided by an oil-fired high-pressure hot-water system, and forced draught ventilation gives 10 changes of air per hour. In the service annexe are works' offices, laboratories, pattern shop, pattern store and boiler room, and an administration block houses offices, canteen, rest room and washing facilities for all employees.

Prior to the visit to the foundry, a luncheon was served at the Royal Victoria Station Hotel, Sheffield. Visitors were welcomed by Mr. Frank A. Hurst, chairman and managing director of the company, and Sir Frederick Pickworth, Master Cutler, and Mr. R. S. Fearnough, President of the Sheffield Chamber of Commerce, also spoke. A colour film of the new factory at work was shown and commented upon by Mr. J. H. Osborn, director.

Castings are being produced with weights ranging from a few ounces to 30 or 40 lb., in carbon steel, 13/14 per cent manganese steel, low-alloy and high-alloy steels. Complex shapes are produced which need the minimum of machining, and replace components hitherto machined from the solid, or from forgings, or sand castings.

New Laboratories for P.E.R.A.

The new workshops and laboratory block occupied some months ago by P.E.R.A. (Production Engineering Research Association of Great Britain), at Melton Mowbray, Leicestershire, were formally opened recently by Lord Chandos, chairman of the Associated Electrical Industries group of companies.

Built at a cost of £250,000, the new block provides some 45,000 sq. ft. of floor space, and the equipment it houses, much of which has been transferred from other buildings, is valued at about £500,000. A view of the new building is given in Fig. 1. The workshops, in which most of the research work undertaken by the Association on production methods in the metalworking industries is carried out, occupy a considerable part of the building. They have a floor area of 20,000 sq. ft., and incorporate a self-contained department equipped for investigating cutting tool life by means of radio-active tool tips. Another part of the workshops is devoted to research work associated with the effects of vibration on machines and cutting tools. Here, the shop floor comprises a number of separate sections which are insulated from each other, and the surrounding area, to eliminate the effects of vibration from adjacent machines. Current research on the impact extrusion of steel and non-ferrous metals covers investigations into the

properties of workpiece materials, slug lubrication and variations in extrusion pressure with percentage reduction in area, and to permit this work to be carried out on fairly large components, a Clearing (Rockwell Machine Tool Co., Ltd.) 100-ton single-action eccentric press has been installed.



Fig. 1 (above). A View of the New P.E.R.A. Workshop and Laboratory Building which Provides an Area of Some 45,000 sq. ft. Including 20,000 sq. ft. of Workshop Space. Fig. 2 (below). A View of the Metrology Laboratory which has a Specially Insulated Floor

Adjoining the main workshops, there is a machine tool laboratory, with a floor area of 1,150 sq. ft., where investigations into various aspects of slideway lubrication are being undertaken. A report is being prepared on the influence of different types of bearing surfaces, lubricant viscosity, load per unit area, and sliding speed, on the transition from boundary to hydro-dynamic lubrication. Practical tests are also being carried out to determine the frictional properties of various lubricants and machine tool slideway materials.

In Fig. 2 is shown a view of the well-equipped metrology laboratory, which has a floor area of 3,200 sq. ft. Between the foundations and the 1-in. thick concrete floor which is faced with wood blocks, there is a 1-in. thick glass fibre blanket, and with this construction, the risk of vibrations being transmitted from the adjoining workshops is reduced. The glass fibre blanket extends round the edges of the floor, which is thus insulated from the walls. Other facilities provided in the new building include metallurgical laboratories equipped for metallography and chemical analysis, an electronics laboratory and drawing and administrative offices.

At present, there are 640 member companies of the Association, who are engaged in the manufacture of a wide variety of products. In addition to general investigations, approximately 1,200 special problems have been examined for individual member firms, and some aspects of this work were considered in an article in *MACHINERY*, 92/277—31/1/58.

Fawcett Preston Bi-Centenary

To celebrate the bi-centenary of Fawcett Preston & Co., Ltd., Bromborough, Cheshire, a member firm of the Metal Industries Group, there was a large gathering of distinguished visitors at a luncheon held at Hulme Hall, Port Sunlight, on Thursday, June 5. After the loyal toast, the Lord Mayor of Liverpool, Alderman Harry Livermoor, J.P., proposed "Fawcett Preston & Company," to which Sir Charles Westlake, chairman of Metal Industries, Limited, and of Fawcett Preston & Co., Ltd., responded. Sir Charles then proposed a toast to the guests, and Mr. Hendrie Oakshott, M.B.E., M.P., responded.

To mark the occasion, an engraved silver salver was presented to the Corporation of Bebington by Mr. Leslie Davies, managing director of Fawcett Preston & Co., Ltd., and this was accepted by His Worship the Mayor of Bebington, Councillor S. F. Williams, J.P. The presentation of a painting of the paddle steamer *William Fawcett* was made to Fawcett Preston & Co. by Sir John Hathorn Hall,

G.C.M.G., D.S.O., O.B.E., M.C, a director of the P. & O. Steamship Co., Ltd., and this was accepted by Mr. Wilfred Padley, C.M.G., O.B.E., deputy chairman, on behalf of the company.

After the luncheon there were conducted tours of the factory and of the exhibition "Fawcett, Past and Present." A well-produced and liberally illustrated souvenir handbook, entitled "Fossets," has also been issued, in which the history of the company and its engineering activities during the past two hundred years are recorded.

Precision Sand Casting

(Continued from page 1371)

actual relationships have not yet been accurately established. Surface finish of Alphax castings is necessarily somewhat inferior to that obtainable by the investment processes, but it is said to be adequate for the majority of applications, particularly where larger parts are involved. The principal merit claimed for the process, however, is the assurance of metallurgical soundness, which will enable designers to specify castings with confidence for an increasing range of purposes.

Certainly this process appears to represent an important advance in a field where progress can yield results of great benefit to the metal working industries as a whole. What is particularly significant, however, is the author's remark that in this work he "can only see the beginning, for after all there is nothing particularly new about the process, unless it is the selective use of materials and adherence to sound principles in the manufacture and use of moulds."

Personal

MR. M. O. L. LYNTON has been appointed a director of Soag Machine Tools, Ltd., 7 Juxon Street, London, S.E.11.

MR. P. B. WARD has been appointed sales manager of Technical Designs, Ltd., 46 Brook Street, London, W.1. He formerly held a similar position with Danite Hard Metals, Ltd., Doncaster.

DR. W. D. SUTHERLAND, B.Sc., Ph.D., A.M.I.E.E., has been appointed chief engineer (electrical) to C.A.V., Ltd., Warple Way, Acton Vale, London, W.3. He joined the company in 1954, as product development engineer (electrical), and was responsible for the development of the C.A.V. automatic gear change control equipment.

DR. L. W. BROWN, B.Sc., Ph.D., M.I.E.E., F.Inst.P., has been appointed assistant chief electrical engineer (light current) of the Metropolitan-Vickers Electrical Co., Ltd., Trafford Park, Manchester. Dr. Brown, who joined the company in 1950, will retain his position as chief engineer of the electronics department, which he has held since its inception in 1955.

Machine Tool Trades Association

It is announced that Mr. W. J. Morgan, M.B.E., will retire from his appointment as general manager of the Machine Tool Trades Association on June 30. He joined the Association as secretary in July, 1939, after service with the Board of Trade and as technical adviser to the Import Duties Advisory Committee, and was made general manager in December, 1950. These two positions he has filled with distinction, and we are pleased to state that he is not completely severing his connection with the Association, his services having been retained in the non-executive capacity of adviser from the date of his retirement.

On July 1, Mr. H. O. Barrett, to whom we offer our congratulations and good wishes, will assume the overall responsibility for Association affairs.

Mr. Guy Chesham, whilst continuing his responsibilities as public relations officer, will also be concerned with the Association's European and other overseas activities.



Mr. W. J. Morgan

North London E.I.A. Luncheon Meeting

The North London Group of the Engineering Industries Association recently held a luncheon meeting which was attended by 40 representatives of member firms. A talk was given by a guest speaker, Mr. K. R. Sandiford, B.Sc., chief instrument engineer of the U.K.A.E.A., on the development of nuclear power plant and the use of special instruments associated with reactors and other apparatus. Reference was also made to the types of instruments used for detecting radioactive isotopes.

Correction

In MACHINERY, 92/1361—6/6/58 reference was made to the new premises of J. E. Baty & Co., Ltd., at Burgess Hill, Sussex. It was inadvertently stated that these premises provide more than 2,000 sq. ft. of production space, whereas the space available for this purpose is, in fact, 20,000 sq. ft. We are asked to point out that the company's London office at 39 Victoria Street, S.W.1, is still in operation for telephone enquiries, etc., and that stocks are carried at this address for urgent delivery.

Bronx Press Brake Sound Film

A new 16-mm. sound film, entitled "The Adaptable Giant," was made recently by Saga Services, Birmingham, for the Bronx Engineering Co., Ltd., Lye, Worcestershire. This film, which runs for 20 min., illustrates several applications of Bronx press brakes ranging in capacity

from 20 to 750 tons. The largest machine shown in the film is set up to bend $\frac{3}{4}$ -in. high carbon steel plate used in the construction of bodies for earth-moving vehicles. Other press brakes are shown producing switchgear cabinets, refrigerator panels, and parts for business machines. Several interesting tools are used for these bending operations, and in this connection it may be noted that Bronx Engineering provide a tool design service for users of all types of press brakes. Copies of the film may be obtained, on loan, from Bronx Engineering Co., Ltd.

Tightening and Tensile Tests on Joints

(continued from p. 1394)

a maximum at the bearing end to practically zero at the free end. Measurements across the flats of $\frac{3}{4}$ -in. and $1\frac{1}{2}$ -in. nuts after test showed that the maximum nut expansion, expressed as a percentage of initial depth of engagement, was greatest for UNF in both sizes, and averaged about 40 per cent. A similar result was obtained for those $1\frac{1}{2}$ -8.BSF nuts which had stripped, but in all other cases the values obtained averaged about 10 to 20 per cent.

The Price of a Subscription to MACHINERY is 52 Shillings per annum, post free, to any part of the world.

Subscribers are not bound for any definite period of subscription. We send MACHINERY, post free, each week until told to stop. Subscribers can pay yearly, half-yearly, or quarterly, pro rata. (Cash with order)

To MACHINERY, National House, 21 West Street, Brighton 1.

Please send me/us MACHINERY every week until I/we tell you to stop, for which I/we enclose remittance of 52 Shillings per annum or pro rata

Name

Address

* Position

* Firm

* For our mailing records only.

13/6/58

Industrial Notes

WILD-BARFIELD ELECTRIC FURNACES, LTD., Elecfurn Works, Otterspool Way, Watford By-Pass, Watford, inform us that the address of their branch office in Canada has been changed to 77 Grenville Street, Toronto, Ontario.

GEORGE KENT, LTD., Biscot Road, Luton, Beds., inform us that they are to open a branch office at Westparkstrasse, 54, Krefeld, Germany, with a comprehensive spares and service department for the complete range of their products.

MOTOR CAR PRODUCTION IN APRIL fell to 81,255 cars, against 87,406 in March. Exports were reduced to 38,586, but this total was nearly 4,000 greater than that for April last year.

AIRCRAFT INDUSTRY EXPORTS for the first four months of this year reached the record total of £50,257,246, which was over 50 per cent higher than in the same period of 1957, according to the Society of British Aircraft Constructors.

AN AUCTION SALE OF MACHINE TOOLS and miscellaneous stores from the Technical Stores Sub-Depot, Old Dalby, Melton Mowbray, Leics., will be held on July 2. The auctioneers will be Shouler & Son (Dept. N), 1 Norman Street, Melton Mowbray, Leics.

KELVIN & HUGHES (INDUSTRIAL), LTD., inform us that a specially-built demonstration unit has been despatched on a 4-month tour of Eastern Europe, and will visit Poland, Czechoslovakia, Hungary, Rumania, and Yugoslavia. Among the equipment which is being displayed are the Mk. 5 and 6 ultrasonic flaw-detection units, and a model of the Mk. 2 automatic flaw detector, complete with C.R.T. trace and pen recorder.

PRODUCTION OF IRON CASTINGS.—The total output of iron castings in the first quarter of 1958, at 961,000 tons, was virtually the same as in the previous quarter, and as in the first quarter of 1957. The requirements of the motor-car industry and railways showed an increase, as compared with the earlier quarters, but this was offset by a decline in the engineering, building and domestic demands.

AJAX ENGINEERING CO. (TECHNICAL DIVISION), 6/7 Kildare Close, Field End Road, Eastcote, Ruislip, Middlesex, announce that they will shortly be offering a micro-filming service for the copying of documents and plans, for example. Copying will be carried out on 8, 16, and 35 mm. film, according to the size of the original material, and, for drawing office work, the company anticipate installing 70-mm. film equipment in the future.

G.T.M.A. EXPORT CATALOGUE.—Reference to the fourth edition of this catalogue was made in MACHINERY, 92/1250—23/5/58. We are asked by The Gauge and Tool Makers' Association, Standbrook House, Old Bond Street, London, W.1, to point out that copies are available, free of charge, to all overseas buyers, and may be obtained by British firms and agencies on remittance of the cost of postage (8d.).

KING'S COLLEGE, NEWCASTLE-ON-TYNE.—Extensions to the metallurgy department of the College were officially opened recently by Mr. C. Cookson, chairman of the Consett Iron Co., Ltd. In his speech, Mr. Cookson referred to the need for closer co-operation between industry and the science departments of universities, and to the fact that, as the methods of processing steel became more complex, so would the demand for trained metallurgists increase.

FILMS ON MATERIALS HANDLING.—The National Joint Committee on Materials Handling, 20-21 Took's Court, Cursitor Street, London, E.C.4, a co-ordinating committee for professional and other bodies interested in materials handling, particularly from an educational standpoint, has compiled a list of films on this subject which will be supplied, upon receipt of a stamped addressed envelope, by The Secretariat at the above address. Some sixty titles are listed, and the size and running time (where known) are given, also the source of film and a brief synopsis of its purpose and audience suitability.

THE BIRMINGHAM ENGINEERING CENTRE, Stephenson Place, Birmingham, 2, in conjunction with, and on behalf of, the Board of Trade, will organize the British Engineering exhibit at the National Industrial Production Show of Canada, to be held in Toronto from May 4 to 8, 1959. This exhibition, which is held biennially, affords an opportunity for displaying all types of production equipment, and firms interested in acquiring stand space, which will be available in units of 120 sq. ft., or possibly less, should communicate with the general manager, Mr. A. J. Cox, at the above address.

FRANK WHITELEGG, LTD., 304 High Street, Sutton, Surrey, inform us that Emil Schenker A.-G., Schönenwerd, Switzerland, for whom they are sole agents, have developed special tooling for their type FA-1 automatic high-speed spring coiler. This machine, which has a capacity for wire from 38 to 19 s.w.g., and will produce coils up to 0.6 in. diameter, can now be employed for the production of single layer resistance and choke coils from copper wire and similar materials. High outputs are obtainable, and it is claimed that this method enables important economies to be effected as compared with the alternative of coiling on mandrels.

THE INDUSTRIAL FUEL EFFICIENCY EXHIBITION will be held at Olympia from September 24 to October 3, and the organizers, Provincial Exhibitions, Ltd., City Hall, Deansgate, Manchester, report that a wide variety of improved plant and equipment will be on show. The exhibits will range from conventional solid fuel appliances, to gas, oil, electric, and nuclear power plants, and there will be examples of the latest techniques in automatic control and instruments. A series of technical conferences has also been arranged, by the Institute of Fuel, and enquiries for details of these conferences, and for stand space, should be sent to the above address.

BRITISH MONORAIL, LTD., manufacturers of overhead lifting gear, are transferring their entire works from Chadderton, Oldham, to premises in Wakefield Road, Brighouse, Yorks., which were formerly occupied by Cengar, Ltd. The company, which was formed in 1952, was reorganized last year, with Mr. James Dallas, as chairman and managing director, and business has since more than doubled. At present there are 180 employees, and it is expected that the number will increase to 500 during the next three years. Twenty per cent of the capital is held by the American Monorail Company, whose wide experience in mechanical handling is at the disposal of the British firm.

THE L. S. STARRETT CO., LTD., it is reported, has been formed as a subsidiary of The L. S. Starrett Co., Athol, Massachusetts, U.S.A., to produce precision tools, hacksaws, and handsaws in Scotland. We are informed that a £270,000 factory is to be built for the new company at Hartrigge, Jedburgh, by the Roxburgh County Council, and it is hoped that production will begin in 1959. The company is recruiting for key posts and selected men will receive a year's training with the parent firm in the U.S.A. It is stated that 100 people will be employed initially, and that the number will subsequently be increased to 250. As European trade increases substantial expansion may be necessary.

LANDIS MACHINE-MAIDEN, LTD., Hyde, Cheshire.—It is announced that the Landis Machine Co., of Waynesboro, U.S.A., and Maiden & Co., Ltd., Cheshire, have amalgamated to form a new British company with the above title. The products of these firms are complementary, and while the new company will continue to build threading machines in the existing Maiden range, the scope of its activities will be widened to include the manufacture of tangential thread chasers and certain other Landis products. The area of the existing factory at Hyde, Cheshire, will be extended by a further 15,000 sq. ft., and, initially, additional plant and equipment will be installed for the production of tangential thread chasers.

CHARLES CHURCHILL & CO., LTD., Coventry Road, South Yardley, Birmingham, have recently been appointed the sole selling agents in the United Kingdom for a number of machines from the range built by Ernst Grob, Munich, Germany. These machines include the types RM0a and RM40d thread rolling machines, the latter being intended for long threading operations by either the in-feed or through-feed process, or a combination of both. Other machines in the Grob range include fully-automatic, electro-hydraulic, milling and centring machines, and a number of special-purpose machines which incorporate unit heads for milling, drilling, tapping, boring, and facing operations. These special machines are built to customers' requirements, and can be equipped for automatic loading and unloading, if required.

AN EXHIBITION OF FOREST MACHINERY held recently at Blackbushe Airport, Bramshill, Surrey, by the Forestry Commission, 25 Savile Row, London, W.1, served to draw attention to the wide variety of mechanized cultivating, drain-cutting, earth-moving, and sawing equipment, for example, for use in connection with estate forestry. Among the 70 exhibitors was E. P. Barrus, Ltd., 12 Brunel Road, London, W.3, who displayed the Blackhawk Featherweight

hydraulic pipe bender of 2 in. capacity. This company also showed examples of the use of Devcon "plastic steel" for repairing cracked castings. Holman Brothers, Ltd., Camborne, Cornwall, showed the Goodyear pump, which was described in *MACHINERY*, 92/455—21/2/58, and the Tractair portable compressor. The latter is intended for mounting on tractors such as the Fordson Major.

Scrap Metals

†LONDON.—†Prices per ton for non-ferrous scrap metals free from iron are as follows:—clean copper wire, untinned and free from lead and solder, £145; clean heavy copper, untinned and free from lead and solder, £140; second grade copper wire, £135; clean light copper, £130; brazing copper, £117; gunmetal, £121; brass mixed, £87; lead, net, £58; zinc, £28; cast aluminium, £82; old rolled aluminium £110; battery lead, £31; unsweated brass radiators, £70; hollow pewter, £495; black pewter, £365

MIDLANDS.—The difficulties of moving all grades of processed scrap to steelworks, blast furnaces and foundries has not eased during the past two weeks. Limited tonnages of scrap can be placed, against allocations, but far more processed scrap is in circulation in the Midlands than can be delivered, and, consequently, stocks in merchants' yards are excessively large.

Such grades as "bushy" turnings, light iron, and destructor scrap cannot be cleared regularly, and even though factories are prepared to accept very low prices for such scrap, few collections are being made.

Heavy steel scrap No. 2, which normally is delivered from merchants' yards every day, is hard to place in anything like the available quantities and yard men are preparing scrap for stock, against the day when normal trading is resumed. Steel turnings of a shovellable or chipped nature are moving more regularly, but more outlets are still required to absorb all supplies from local factories. The demand for borings is variable, and reduced prices are being offered under new contracts.

Compressed destructor bales are being produced in excess of market demand, and many tons are in stock at merchants' yards.

Odd parcels of scrap, offered by many builders and contractors, for example, cannot be handled, as the smaller scrap firms cannot obtain allocations for delivery.

Foundry trading in short steel and cast iron is very quiet.

Current maximum control prices, delivered consumers' works, are now: *Heavy steel No. 1, 217s. 6d.; *heavy steel No. 2, 196s.; *heavy steel No. 4, 207s. 6d.; *heavy steel No. 5, 195s. 6d.; light iron No. 8, 149s.; short turnings No. 9 (free from alloy), 167s. 3d.; light steel No. 11, 164s. 3d.; bushy turnings, 117s.; short alloy turnings, 160s. 9d.; short steel No. 2, 233s. 3d.; machinery cast, 233s.

Prices may be increased up to 2s. 6d. per ton according to quantities tendered over a given period.

* For use by Round Oak Steelworks, Brierley Hill, increase by 1s. 6d. per ton.

† George Cohen, Sons & Co., Ltd., 600 Commercial Road, E.14.

‡ Subject to market fluctuations.

Machine Tool Share Market

Quiet conditions prevailed on the Stock Exchange during the past week, but markets, as a whole, displayed a firm tone for the most part.

The gilt-edged section met with moderate but sustained investment support, and quotations of British Funds and kindred stocks steadily appreciated and finished at the highest levels.

Activity in the commercial and industrial sections remained at a low level, but a satisfactory tone was maintained, with the majority of price changes slightly higher on balance.

Among machine tool issues, Armstrong Stevens advanced 1½d. to 8s.; Samuel Osborn, 3d. to 17s.; Ambrose Shardlow, 4s. 6d. to 37s. 6d.; John Shaw & Sons (Wolverhampton), 1½d. to 12s. 4½d.; and Thos. W. Ward, 7½d. to 74s. 4½d. On the other hand, Asquith Machine Tool lost 7½d. at 18s. 1½d.; Alfred Herbert, 7½d. at 32s. 6d.; Noble & Lund, 3d. at 2s. 9d.; Modern Engineering, 6d. at 8s. 6d.; and Scottish Machine Tool, 9d. at 4s. 6d.

KITCHEN & WADE, LTD. Second interim dividend of 8½ per cent, plus a bonus of 4½ per cent, making a total distribution of 20½ per cent for the year ended March 31, last (same).

AMBROSE SHARDLOW & CO., LTD. Final dividend of

10½ per cent, making, with the interim, a total distribution of 15 per cent for the year to March 31, last, an increase of 2½ per cent as compared with the total for the preceding year.

New Companies Registered*

PARAMATTA TOOL & GAUGE CO., LTD., Blucher Street, Salford, 5. Registered May 13, 1958. Nominal capital: £5,000 in £1 shares. Directors: B. P. Sweeney and P. Grayson.

MURRAY ENGINEERING CO. (HAYES), LTD., 2 Finchley Road, London, N.W.8. Registered May 1, 1958. To take over the business of tool makers carried on at Printing House Lane, Hayes, Middlesex, by J. R. and A. P. Bell, etc. Nominal capital: £5,000 in £1 shares. Directors: John R. Bell and A. P. Bell.

S.W.F. MANUFACTURING CO., LTD., 42/52 Garrison Lane, Birmingham. Registered May 20, 1958. To take over the business of "S.W.F. Press Tool Company" carried on at Birmingham by Wilfred I. Fowler and Albert Simmons, etc. Nominal capital: £15,000 in £1 shares. Directors: W. I. Fowler, A. Simmons and W. C. Fowler.

* From the lists compiled by Jordan & Sons, Ltd., Company Registration Agents, 116-118 Chancery Lane, London, W.C.2.

COMPANY		Denom.	Middle Price	COMPANY		Denom.	Middle Price
Abwood Machine Tools, Ltd.	Ord.	1/-	9d.	Harper (John) & Co., Ltd.	Ord.	5/-	13/7½
Armstrong, Stevens & Son, Ltd.	Ord.	5/-	8/-	" "	4½% Red.	£1	13/1½
Allen (Edgar) & Co., Ltd.	Ord.	£1	27/-	" "	Cum Prf.		
" "	5% Prf.	£1	14/9*	Herbert (Alfred), Ltd.	Ord.	£1	32/6
Arnot & Harrison, Ltd.	Ord.	4/-	13/9xd	" "	" "		
Asquith Machine Tools Corp., Ltd.	Ord.	5/-	18/1½	Holroyd (John) & Co., Ltd.	"A" Ord.	5/-	10/3
" "	6% Cum. Prf.	£1	18/6xd	" "B" Ord.	5/-	9/9	
Birmingham Small Arms Co., Ltd.	Ord.	£1	28/3xd	Jones (A. A.) & Shipman, Ltd.	Ord.	5/-	21/3
" "	5% Cum.	£1	15/6	Kayser, Ellison & Co., Ltd.	7% Cum. Prf.	5/-	5/-xd
" "	"A" Prf.			" "	Ord.	£1	44/6
" "	6% Cum.	£1	17/6	Kendall & Gent, Ltd.	6% Cum. Prf.	£1	18/3
" "	"B" Prf.			" "	Ord.	5/-	7/9
" "	4% 1st Mort.	Stk.	85/-xd	Kerry's (Gt. Britain), Ltd.	Ord.	5/-	6/3
British Oxygen Co., Ltd.	Ord.	£1	34/6	Kitchen & Wade, Ltd.	Ord.	4/-	10/-
Brooke Tool Manufacturing Co., Ltd.	6½% Cum. Prf.	£1	21/3xd	Martin Bros. (Machinery), Ltd.	Ord.	2/-	2/4½
Broom & Wade, Ltd.	Ord.	5/-	4/7½	Massey, B. & S., Ltd.	Ord.	5/-	7/9
" "	Ord.	5/-	10/4½	Modern Engineering Machine Tools Ltd.	Ord.	5/-	8/6
Brown (David) Corporation Ltd.	6% Cum. Prf.	£1	14/-	Newall Engineering Co., Ltd.	Ord.	2/-	4/6
Buck & Hickman, Ltd.	6% Cum. Prf.	£1	17/9xd	Newman Industries, Ltd.	Ord.	2/-	2/3
Butler Machine Tool Co., Ltd.	Ord.	5/-	5/6	" "	6% Prf. Ord.	5/-	5/6
" "	5% Cum. Prf.	£1	13/9	Noble & Lund, Ltd.	Ord.	2/-	2/9
C.V.A. Jigs, Moulds & Tools, Ltd.	5½% Red.	£1	13/9	" "	" "		
" "	Cum. Prf.			Osborn (Samuel) & Co., Ltd.	Ord.	5/-	Exrights
Churchill (Charles) & Co., Ltd.	Ord.	2/-	4/4½xd	" "	5½% Cum. Prf.	£1	25/3
" "	6% Cum. Prf.	£1	26/3	Pratt (F.) & Co., Ltd.	Ord.	5/-	21/3
Churchill Machine Tool Co., Ltd.	Ord.	5/-	17/6	" "	Ord.	4/-	4/6
" "	6% Cum. Prf.	£1	18/6	Scottish Machine Tool Corporation, Ltd.	Ord.	£1	37/6
Clarkson (Engrs.), Ltd.	Ord.	5/-	12/3	" "	" "		
Cohen (George), Son & Co., Ltd.	Ord.	5/-	11/10½	Shardlow (Ambrose) & Co., Ltd.	Ord.	£1	37/6
" "	4½% Cum. Prf.	£1	14/6	" "	" "		
Coventry Gauge & Tool Co., Ltd.	Ord.	10/-	13/9	Shaw (John) & Sons, Wolverhampton, Ltd.	Ord.	5/-	12/4½
" "	5% Cum.	£1	16/3	" "	" "		
" "	Red. Prf.			Sheffield Twist Drill & Steel Co., Ltd.	Ord.	4/-	33/9xd
Coventry Machine Tool Works, Ltd.	Ord.	4/-	8/9	" "	5% Cum. Prf.	£1	15/-xd
Craven Bros. (Manchester), Ltd.	Ord.	5/-	6/7½	" "	Ord.	5/-	6/3
Elliott (B.) & Co., Ltd.	Ord.	1/-	3/-	Tap & Die Corporation, Ltd.	Ord.	5/-	7/6
" "	4½% Red.	£1	13/9xd	" "	4½% Deb.	Stk.	82/-
" "	Cum. Prf.			" "	1961-1977		
" "	" "			Wadkin, Ltd.	Ord.	10/-	18/9
Export Tool & Case Hardening Co., Ltd.	Ord.	2/-	1/3	Ward (Thos. W.), Ltd.	Ord.	£1	74/4½
" "	" "			" "	5% Cum.	£1	15/9
" "	" "			" "	1st Prf.		
Firth Brown Tools, Ltd.	4% Cum. Prf.	£1	12/-	" "	5% Cum.	£1	25/-
Greenwood & Batley, Ltd.	Ord.	£1	46/10½	" "	2nd Prf.		
" "	" "			Willson Lathes, Ltd.	Ord.	1/-	24/4


The Middle Prices given in the list are in several cases nominal prices only and not actual dealing prices. Every effort is made to ensure accuracy, but no liability can be accepted for any error.

* Sheffield price.

† Birmingham price.




GOULDER



NO. 2 ROLLING GEAR TESTER

**... reveals errors
immediately ...**

This machine accurately measures the highest class of gear used in the automobile, machine tool and aircraft industries. Features include: calibrated adjustable spring pressure, centralising lock, test discs for checking, hollow quill for shaft gears, provision for simultaneous indicating and recording of results. Capacity: 1in. to 14in. diameter, 4 to 40 D.P. Independent laboratory reports available. Send for particulars of the GOULDER range.



J. GOULDER & SONS, LTD.
KIRKHEATON • HUDDERSFIELD • ENG.

HEAP'S *Finest Quality* SCREWING DIES
TANGENTIAL OR RADIAL

IMMEDIATE DELIVERY OF DIES
TO BRITISH STANDARD
SPECIFICATION

SPECIALS AT SHORT NOTICE

JOSHUA HEAP & CO. LTD.
ASHTON-UNDER-LYNE

RE-CUTTING SERVICE
Radial type dies
re-cut equal to new
within a few days

PHONE No. 1548 GRAMS-HEAP, LIMITED, ASHTON-UNDER-LYNE.

When answering advertisements kindly mention MACHINERY.



STEPLESS VARIABLE SPEED GEARS

FOR THE MACHINE SHOP

INDUSTRIAL & COMMERCIAL ENGINEERING

Change of
SPEED
AT A TOUCH - *while*
machinery is in motion!

★ TO SPEED UP

*move forward*

TO SLOW DOWN

move backward

A COMPACT UNIT EASILY INSTALLED.
 AUTOMATIC BELT ALIGNMENT.
 USES STANDARD 'V' BELTS. LOW COST.

Write for descriptive literature.

Proprietors **GIB Precision Ltd** Barton Lane, Cirencester.

Telephone: Cirencester 726/7/8



Thos. Wm. Lench Ltd.

PHONE: BLACKHEATH 1151

BLACKHEATH
BIRMINGHAM
ENGLAND.

GRAMS: LENCHONIA,
 BLACKHEATH, BIRMINGHAM




MAKERS OF
Bolts, Screws, Rivets.

When answering advertisements kindly mention **MACHINERY**.

For controlling horse-power
in many directions -
use



'DIAMOND H'



Packet Switches

Also suitable for Rectifiers,
Transformers, Battery Chargers,
Machine Tools and Switchboards.

Designs available in 5 amp. to 60 amp.
capacity at 250 or 440 volts, AC/DC
and AC only.

'Diamond H' Packet-type
Rotary Switches have been
developed to meet the demand
for a reliable multi-circuit
rotary reciprocating unit of
extremely robust construction.
Why not therefore
incorporate these Switches
in equipment of your manu-
facture and be assured years
of trouble-free service under
the most arduous conditions.

'Diamond H' Switches are doing Trojan work in Industrial and Domestic fields all over the world

'DIAMOND H' SWITCHES LIMITED

GUNNERSBURY AVENUE, CHISWICK, LONDON, W.4

Telephone : Chiswick 6444 (5 lines) Grams and Cables : Diamondhart, Chisk, London


When answering advertisements kindly mention MACHINERY.

CENTRIFUGAL CASTINGS

made to measure

New techniques enable us to supply single or bi-metal centrifugally cast tubes of much greater length than hitherto—in all types of steel, including corrosion and heat resisting alloys.

(Also supplied in short lengths to suit your machining capacity).



for all types of rollers

Write for details to :

Sheepbridge Alloy Castings Ltd. Sutton-in-Ashfield, Notts. Telephone : Sutton-in-Ashfield 590
(One of the Sheepbridge Engineering Group)

SCAIFE

Milling Machine Arbors

STANDARD
OR
SPECIAL
ANY SIZE
ANY TYPE



SCAIFE ARBORS are manufactured from 50/60 tons nickel chrome heat-treated steel, whilst the bushes are made from mild steel—case-hardened and ground. We can supply all sizes of national standard taper arbors, and in addition can manufacture arbors for machines having MORSE, BROWN & SHARPE or JARNO taper spindles, upon receipt of sketch showing necessary dimensions.

ROBERT SCAIFE (COLNE) LTD.


SWANFIELD WORKS · COLNE · LANCASHIRE · Tel. : COLNE 50-51

When answering advertisements kindly mention MACHINERY.

for JIGS & FIXTURES
IN A FEW HOURS

WHARTON



Tooling



WHARTON & WILCOCKS LTD. • 20 BULL PLAIN • HERTFORD • ENG • Tel: Hertford 4041

When answering advertisements kindly mention MACHINERY.

lathe tools



This is just a selection from the large range of J & S Small Tools regularly exported all over the world.
Other tools in the J & S range include:

Sleeves and Sockets
Machine Vices
Bench Centres
Dividing Tables
Revolving Centres

Boring Heads
Balancing Units
Machine Clamps
Vee Blocks
"Throw-away"
Tip Toolholders



small tools

STOCKED BY ALL
J & S SMALL TOOL
DISTRIBUTING AGENTS

A. A. JONES & SHIPMAN LTD.

Narborough Road South, Leicester, England

Telephone 823222 (8 lines) Telegrams: "Chuck" Leicester

Taylor

AIR CLUTCHES

(Patented)

WITH COMBINED AUTOMATIC BRAKE

**— FOR SMOOTH, POSITIVE,
CUSHIONED POWER**

These clutches not only ensure full power with smooth, shock-free engagement at higher speeds, but also contribute to faster production and better all round performance on all types of Presses, Forging Machines, Press Brakes, Shears, etc. Synchronised, powerful, quick acting braking ensures positive safe stop, which means quick and accurate control with increased safety for operators and tool setters.

A standard range of sizes is available and details will be sent on request.



TAYLOR INDUSTRIAL CLUTCHES TROWS UPPER WORKS, CASTLETON, LANCs.

When answering advertisements kindly mention MACHINERY.


It's easier it's quicker it's cheaper — by permagic



CIRCULAR CHUCKS
for grinders and lathes. Ask
for Publication P.M. 133 —
"Circular Chucks in Action".



RECTANGULAR CHUCKS
in a range of sizes for all
metal cutting and grinding
machines. (P.M. 107)




MAGNETIC FLOATERS
provide speedy separation —
Publication P.M. 120.


MAGNETIC BASE
used the world over
to hold dial indica-
tors in the most
awkward places
(P.M. 122).



MAGNETIC HOLDER
The 'Welders Mate', pays for
itself in a week. (P.M. 118).



MAGNETIC LINKS
Fully adjustable to
hold plates at any
angle. Indispensable
to welders. (P.M.
143).



Photograph by courtesy of Rolls Royce Ltd.

Simple holding jobs suggest their own solution — more difficult jobs suggest "Eclipse" Permanent Magnet Chucks. Planning engineers can now call on more power, more adaptations and a bigger range for all types of machines. Learn why they have become so indispensable in "Some Facts about Permanent Magnet Chucks" — Publication P.M. 150 — Supplies through your usual "Eclipse" dealer.

STILL FIRST IN THE FIELD

Magnetic Devices to speed production

Made by JAMES NEILL & CO. (SHEFFIELD) LTD ENGLAND


PM 123

When answering advertisements kindly mention MACHINERY.


All publications listed above are available through your Eclipse Dealer

The valve that does too much...

Not from the users' point of view—they thank their lucky stars for HOPKINSONS' bronze Link Valves—but how can we hope to tell you about a valve that handles water, full of sand and grit, thick heavy liquids such as molasses, resin size or oils, soap lines, compressed-air lines in mines and quarries, process steam in textile and food factories, dye works, laundries, sugar refineries etc., and moreover is 'tough', easy to operate, reliable and has a long life—all in one advertisement? Write for leaflet 5704.



HOPKINSONS' LINK VALVES



One of HOPKINSONS' Small Bronze Valves



HOPKINSONS LIMITED • HUDDERSFIELD

LONDON OFFICE: 34 NORFOLK STREET • STRAND • W.C.2
HV104

HIGH DUTY CASTINGS for ROLLS-ROYCE

OIL ENGINES


C. & B. SMITH LTD.

IRONFOUNDERS


WOLVERHAMPTON



When answering advertisements kindly mention MACHINERY.

COLD HEADED BOLTS & SETSCREWS

Why look elsewhere, when all the benefits of long specialization plus the closest adherence to exacting quality standards, are yours when you decide it's "ORMOND" for Cold Headed Bolts and Set-screws.



The
ORMOND
Engineering
Co. Ltd.

Ormond House,
Rosebery Avenue,
London, E.C.1.

Telephone: TERminus 2888
Telegrams: "Ormوندengi, Smilk"

When answering advertisements kindly mention MACHINERY.

Completely New!!

The VERROLEC HAND BAND SAW



VERROLEC
PROVIDES
THE UNUSUAL

- ◀ Easy to operate
- ◀ Electrically driven
- ◀ Cuts bars 2½in. dia.
3½in. x 3½in. square
and sections up to 4½in. x 3½in.
- ◀ Ferrous and non-ferrous metals
- ◀ Dimensions approximately
22in. x 8in. x 7in.
- ◀ Weight approximately 22 lbs.

VERROLEC LTD.

27 BALFOUR HOUSE, FINSBURY PAVEMENT
LONDON, E.C.2. MONarch 6802

ANNOUNCING

A MAJOR BRITISH DEVELOPMENT IN BEARING TECHNOLOGY

**Bearings are now available
which operate**

- * Completely dry or in most liquids
- * Under heavy loads and high speeds
- * At temperatures from -200°C. to +250°C.
- * In the presence of dust or abrasive particles.

Nearly 1,000,000 of these bearings are already running in a wide range of mechanisms from gas turbines to textile machinery.

DU DU is a new development based on our original DP material which it now supersedes, and provides three times the load/speed carrying capacity of its predecessor,

DU

Three materials with different functions have been developed to assist those who wish to design machinery that avoids the use of lubricants.

Thin steel strip with a porous bronze coating impregnated with a mixture of a fluoro-carbon (P.T.F.E.) and lead. Supplied in flat lengths or as finished bushes and thrust washers in a range of sizes. Available at low cost from stock.

DQ

A fluoro-carbon (P.T.F.E.) strengthened with special fillers and supplied in bars and tubes. A range of diameters is available from stock. Non-standard or irregularly shaped dry bearings can be simply machined from this material.

DM

A process of applying an adherent layer about .002" thick utilising the bearing properties of a combination of fluoro-carbon and molybdenum disulphide to the bearing surface of any ferrous part. Such parts must be sent to us for process.

The basic material we use in all these bearings is the "Fluon" brand of Polytetrafluoroethylene supplied to us by I.C.I. Ltd.

GLACIER

Information sheets giving guidance on use, maximum loads, speeds etc., are available free on request. 'TEL: PERIVALE 6611. TELEX: GLAMET, WEMBLEY
THE GLACIER METAL COMPANY LIMITED · ALPERTON · WEMBLEY · MIDDLESEX

When answering advertisements kindly mention MACHINERY.

Now there are 4 new SURFORMS


FINE-CUT FILE No. 102

This SURFORM file has been developed specially for mild steel and other tough materials. The cutting principle is the same, but the teeth are set at a different cutting angle, giving a clean cut and a smooth finish. Price **12/6**. Replacement blades (No. 506) 3/6.



BLOCK PLANE No. 111

This fine cut tool is for quick, one-handed smoothing of edges and small surface areas on a wide variety of materials. You will find scores of uses for it round your workshops. Price **10/-**. Replacement blades (No. 520) 2/9



CONVEX PLANE No. 105

Although developed for the car-body repair trade and for spot-trimming, this fine cut convex SURFORM is very fast and efficient on wood too and is recommended for the furniture and cabinet making industry. Price **17/6**. Replacement blades (No. 506) 3/6.



HALF ROUND FILE No. 103

Here's another tool for which we've had plenty of requests. It gives first class results on concave surfaces and will serve many trades. Price **13/-**. Replacement blades (No. 507) 4/3.



The universal tool with hundreds of uses!
SURFORM

The above tools are supplementary to the original SURFORM plane and file, which remain the ideal all-purpose cutting and finishing tools for every industry. Plane type (No.107) **17/6**. File type (No.101) **12/6**. Replacement blades (No.505) **3/6**.

SURFORM blades (an invention of Firth Brown Tools Ltd.) are made from hardened and tempered Sheffield tool steel—they give controlled depth of cut and never clog with waste material.




A product of **SIMMONDS AEROCESSORIES LIMITED**, Treforest, Glamorgan.

A MEMBER OF THE **FIRTH CLEVELAND GROUP**



CRC295U

When answering advertisements kindly mention **MACHINERY**.



ONE OF MANY DIFFERENT TYPES OF MACHINES

SAVED!

by

BROCKHOUSE MACHINE TOOL REBUILDING SERVICE

Why not consult us about that one-time useful machine tool which is now standing idle? We have a comprehensive machine tool rebuilding service available for LATHES, AUTOMATICS, SHAPERS, PRESSES, and DIE CASTING MACHINES. Machines are completely stripped, parts replaced, and when rebuilt carry our six months' guarantee.

SEND FOR DESCRIPTIVE LEAFLET

BROCKHOUSE

J. BROCKHOUSE & CO. LTD.

Machine Tool Division

ELMS WORKS, WOLVERHAMPTON

Tel.: 23801

NUMBERING ON METAL

'LEDA'

NUMBERING MACHINES

NUMBERING HEAD FOR METAL

Consecutive and Repeat Actions

Power, Fly, Hand or Pneumatic Presses
and similar equipment.



It is used for marking Aircraft components with reference numbers, part and drawing numbers, date of manufacture, inspection mark, for marking Shells, Bombs, Cartridges, Engine Parts, Motor Car, Motor Cycle, Cycle, Wireless, Electrical, Clock, Watch and other instrument parts in all materials. Checks, Labels, Name Plates, Pigeon Rings, in fact, any article which requires an identification mark. Mass produced articles can only be satisfactorily identified by individual reference numbers.

W. LETHABY & Co. Ltd.

LEDA HOUSE, 124-132 CLERKENWELL ROAD, LONDON, E.C.1



Telephone: Terminus 1104 (5 lines)

When answering advertisements kindly mention MACHINERY.

IGRANIC-STROMAG CLUTCH

Compact design — short time response — high thermal capacity — low idling torque. These are some of the outstanding features of this electro-magnetic multi-disc clutch.

May we send you full details of these clutches and information about other Igranic products for which packaging machinery designers are finding many applications?




IGRANIC ELECTRIC CO LTD
HEAD OFFICE AND WORKS BEDFORD

LONDON & EXPORT OFFICES VICTORIA STN HOUSE 191 VICTORIA ST LONDON SW1
A Metal Industries Group Company



DISTRICT OFFICES BIRMINGHAM BRISTOL CARDIFF EAST ANGLIA GLASGOW LEEDS MANCHESTER NEWCASTLE SHEFFIELD
2954/10/78

When answering advertisements kindly mention MACHINERY.



Internationally Recognised


ERMETO fittings are the internationally recognised method of coupling high pressure pipe lines. Enormous numbers are in use throughout the world. Supplied in mild steel, stainless steel, brass, bronze and aluminium for all pipe sizes, standard and non-standard up to 2" o.d.

*A wide range of valves also available.
Catalogues on request.*



BRITISH ERMETO CORPORATION LTD
Beacon Works, Hargrave Road, Maidenhead
Tel: Maidenhead 5100 (10 lines)

WITH **Ballinger** INSTANT, EASY CUTTING-OFF WET-TYPE ABRASIVE WHEEL CUTTING-OFF MACHINES



ILLUSTRATING TYPE 'A' FULLY AUTOMATIC SINGLE BAR HYDRAULICALLY OPERATED MODEL. CAPACITY 3 in. SOLID BAR WITH 16 in. WHEEL.

This wet-type machine can be supplied with fully automatic single or triple bar stock feeds. Long wheel life. Clean, cool, fast cutting. Fitted with Eccentric Wheelhead for cutting difficult alloys. Full range of models available. Ask for details.

L. J. H. BALLINGER LTD.
WOODCHESTER, STROUD, GLOUCESTERSHIRE
Phone: AMBERLEY 2184/7

COXETER Revolving Centres



- Models for Bar or Tubular work
- Standard sizes, Morse taper and parallel shanks
- Best Cast Steel construction hardened and ground
- Heavy duty bearings
- Especially suitable for heavy cutting with tipped tools
- Special sizes quoted for
- Quick deliveries



IMPROVED TYPES
Price list on application


REVOLVING CENTRES LTD.
40-41 PARK END STREET, OXFORD
Phone: OXFORD 2275/6 Grams: COXETERS, OXFORD

When answering advertisements kindly mention MACHINERY.

high speed

SPIRAL BEVEL GEAR UNITS

The illustration shows a VSB 16in. Spiral Bevel Gear unit for a Turbine driven Vertical Centrifugal Pump. 200 h.p. at 2,900 r.p.m. 1/1 ratio. 24 hours rating. Oil Cooler, Pump, spray lubrication for Gears, Strainer, Check Valve.



Reid



**AND
SPIRAL
BEVELS
UP TO
34" DIA.**

Reid capacity for the manufacture and production of gears and gear units includes practically every modern engineering technique. Reid can expeditiously supply gears and gear units for every purpose, including Spiral Bevel Gear Units up to 1,500 h.p. and Spiral Bevel Gears up to 34in. diameter or even larger.

We can now quote quick delivery of all gear units. Write, or 'phone Johnstone 861 for full details.




Reid EVERY TYPE—EVERY SIZE—FOR EVERY NEED

THE REID GEAR CO. LTD., LINWOOD, N.R. PAISLEY

INTRODUCING The S & B ROTARY COLD TAGGING MACHINE

Backed by 30 years' experience in building rotary swagers, the makers have designed this new machine especially for cold tagging steel and non-ferrous tube or bar. Four dies are mounted in a fixed head and do not rotate. THERE IS NO POSSIBILITY OF THE DIES REVOLVING THE TUBE risking injury to the operator. Advantages are a uniform strong tag, no heating and furnace costs, higher production.

**OUTPUT UP TO
200 PER HOUR
ON 2in. TUBE.**




A short 16mm film describing this machine is available on application.

**STEVENS AND
BULLIVANT Ltd**

WESTERN ROAD BIRMINGHAM 13 ENGLAND

When answering advertisements kindly mention MACHINERY.

Whatever the
TOOL
LINDLEY'S
have it



Comprehensive stocks
of machines, tools
and accessories.

Main stockist and distrib-
utors for Black & Decker,
Wolf, and Bridges Electrical
Equipment.

C. LINDLEY & CO. LTD.
ENGLEFIELD RD., LONDON, N.I.

Phone: CLIssold 0643 (5 lines)

Grams: BEAUVOIR NORDO, LONDON



HORIZONTAL SURFACE GRINDER

FOR
TOOL ROOM
OR
PRODUCTION
SHOP

CAPACITY
18in. by 6in.
by 8½in.

- ▶ TAPER ROLLER SPINDLE
- ▶ TABLE SLIDEWAYS 34in.
- ▶ SMOOTH AND EASY
- ▶ TABLE OPERATION
- ▶ VERTICAL FEED .0005in.
- ▶ RIGID BUILD FOR
- ▶ PRECISION GRINDING

MODELS 15in. by 6in. . . £185
18in. by 6in. . . £190
(as illustrated)
24in. by 6in. . . £205
20in. by 8in. . . £215

VICTA ENGINEERING CO.

Offices: Thicket Corner,
Maidenhead. Tel.: 50.

and at
Eagle Works, Chester Rd., Boreham Wood, Herts. Tel.: Elstree 3146

PINS ON HEAVY DUTY

CHAIN LINK PINS

that are subjected to
severe conditions need
the right steel, the ideal
core treatment, and a
hard case in the right place.

Radio-frequency or Flame
Hardening may be best —
Perhaps we can advise you.

FLAME HARDENERS LTD.

Shorter Works, Bailey Lane,
SHEFFIELD, 1 Phone: Sheffield 21627

When answering advertisements kindly mention MACHINERY.

REGALOX

REGALOX TEST PIECE
SENT ON APPLICATION

HARD CERAMICS FOR ENGINEERING

Let our "REGALOX" technical development advisory service tell you how "REGALOX" can be applied to your products, your production and maintenance.



NEARLY DIAMOND HARD

WEAR & HEAT RESISTANT • DIMENSIONALLY STABLE UNDER ALL CONDITIONS • LOW CO-EFFICIENT OF FRICTION • HIGH PHYSICAL PROPERTIES


With a hardness between diamond and sapphire, highly resistant to wear and possessing excellent physical properties, "REGALOX" hard ceramics now open up new possibilities in the fields of Chemical, Electrical and Mechanical Engineering.

Unaffected by high working temperature, "REGALOX" remains dimensionally stable under all conditions. It holds close dimensional tolerances and concentricity. It is impervious to moisture and withstands the action of practically all chemicals. Where required, components can be high temperature metallised—a process which has already had a wide application in the Electronics field.

The advantages of "REGALOX" particularly its wear resistant quality, reduce machine maintenance and replacement of parts.

"REGALOX" is already operating successfully in the Textile, Wire, Paint, Brickmaking, Grinding, Copper, Tin, Mechanical, Chemical, Nucleonic, and General Engineering Industries. Typical applications include:—Drill Bush Liners—Plug Gauges—Jig Bases—Textile and Wire Guides—Sand Blast Nozzles—Pump Seals and General Machine Components—Fuse Cores—Tiles—Grinding Balls—Brickmould Liners—Insulators—Bushes—Rods and Tubes.

Industrial Ceramics Division




REGALOX, SEALED TO
METAL UNDER VACUUM
GIVING POSITIVE
ADHESION

THE WORCESTER ROYAL PORCELAIN CO. LTD
INDUSTRIAL CERAMICS DIVISION

Sales Department— TONYREFAIL
GLAMORGAN, SOUTH WALES.
Telephone: TONYREFAIL 135/136
Telegrams: PORCELAIN, TONYREFAIL



When answering advertisements kindly mention MACHINERY.



THE
"HYDETSO"
 British
 HYDRAULIC
 SHAPERS

•
 PLAIN OR
 UNIVERSAL TABLES

•
 EXTREMELY POWERFUL

•
 RAPID AND
 ACCURATE

•
 SAFETY OVERLOAD
 RELEASE

•
 EARLY DELIVERY

C. H. JOYCE, LTD. 32-40, MONKTON ST. (Kennington), LONDON, S.E.11.

*let VAUGHAN pulley blocks
 take care of the UPS and
 DOWNS of materials handling*

TYPE A.47

Sizes $\frac{1}{2}$, 1, 2, 3, 5 Tons

SPECIFICATION

FRAME.—All-steel of great rigidity.

GEARS.—Machine-cut with balanced tooth pressures, and high efficiency.

BEARINGS.—Hardened and ground.

CHAIN SPROCKET.—Cut from solid 0.4% carbon steel.

CHAIN.—High tensile chain with large factor of safety.

HOOK.—Made from special quality mild steel, fitted with ball-bearing swivel.

COVERS.—Pressed steel enclosing block and chain wheel.

CHAIN WHEEL.—Pressed steel, shrouded.

BRAKE.—Automatic in action, offers no resistance when hoisting comes into operation immediately hand chain is released, totally enclosed.

TEST.—Each block tested with 50% overload and certificate supplied.

TROLLEYS.—These blocks are all made to suit the standard range of VAUGHAN Trolleys.



THE VAUGHAN CRANE CO. LTD.
MANCHESTER 12 : : ENGLAND


TELEPHONE EAST 2771

When answering advertisements kindly mention MACHINERY.


GENERAL DUTY OR TOOLROOM

UNIVERSAL VERTICAL SHAPING & SLOTTING MACHINES

The BURDETT range for the toolroom includes high speed, versatile and accurate machines with 8", 10", 12" and 14" strokes. Tooling is uncomplicated and operation, simple. The BURDETT design features strength and rigidity, together with ample bearing surfaces, to withstand deflection under heavy loads, and preserve accuracy under the most arduous conditions of operation. The system of construction is such that all working parts are easily accessible for inspection and maintenance. The swivelling head can be inclined 10° either side of the vertical and the rotary table, which indexes 12 positions, has safety interlock of hand and power feeds. A dividing attachment can be fitted in a matter of a few minutes. The 10" model in this range is illustrated below.



Close-up showing dividing attachment on rotary table



GENERAL PURPOSE MACHINES

The machine above is available in two sizes, with 6½" and 8½" strokes. It possesses many features of the toolroom model described above but is intended primarily to accommodate the many jobs which do not require such extreme accuracy and versatility.

Full details of both types are available on application.

it's

BURDETT

FOR SLOTTERS!

Write for brochures:—

G. W. S. BURDETT & CO LTD · EASTGATE · PETERBOROUGH

When answering advertisements kindly mention **MACHINERY**.

**B&T***Standard and Special*

JIG BUSHES

ALSO—

DOWEL PINS (HARDENED AND PRECISION GROUND), LOCATING BUSHES, LOCATING PINS AND REST BUTTONS, GUIDE PINS AND BUSHES, TENONS, PUNCH SHANKS, JIG HAND NUTS.


Write for catalogue.

BONEHAM & TURNER LTD.
MANSFIELD - - - NOTTS

Telephone: Mansfield 896 (6 lines)

You can't beat 'Celastoid' TRADE MARK for transparent machine guards

For a clear view of operations and complete protection for the operator, use 'Celastoid' transparent acetate sheet. This wonderful material is shatterproof, flame resistant, washable, can be easily cut and machined, and inexpensively heat formed into simple or compound curves. Other uses include protection of drawings, charts, etc.



You can't beat G. H. BLOORE for quick delivery of 'Celastoid'

G. H. Bloore, Limited (Dept. A)
66 The Broadway, Mill Hill,
London, N.W.7

**POST
TO-DAY**

Please send me 'Celastoid' samples and details of sheet sizes and prices.

NAME

ADDRESS

T1816


This famous British Celanese material is stocked in quantity by G. H. Bloore, who can give you delivery by return. For samples, sizes and prices (which are the same as the manufacturer's), fill in and return the coupon. We also stock 'Perspex,' 'Darvic,' Rigid P.V.C. and 'Hardec' plastic faced hardboard, and will be glad to quote you for fabricating or moulding.

G. H. BLOORE LIMITED
66 The Broadway, Mill Hill, London, N.W.7

Telephone: Mill Hill 6833 (5 lines)
Birmingham Office: 46 Weaman Street

HYDRAULIC CONTROL

for GREATER
FLEXIBILITY
— GREATER
PRODUCTION
CAPACITY



BUTTERWORTH HYDRAULIC AUTOMATIC


cuts costs on short or long runs

- ADVANCED DESIGN
- NEW STANDARDS OF PRODUCTIVITY
- INFINITELY VARIABLE SPEED CONTROL
- NO SPECIAL CAMS

Here is a machine to meet to-day's demand for lower costs. Ample power, combined with foolproof hydraulic control of feed, elimination of special cams, and great flexibility ensure the highest possible production rates, even on small batches. Note, too, the chucking and bar feed are hydraulically operated.

The range of sizes covers work from 1½" to 2½" diameter bar. Hydraulic copy turning attachment and cross slide longitudinal turning attachment available.

Other sizes and models include 7" SD, 8"-1 1/8" SD, 1 1/4" AG, 3" AG and 3 1/2" AG.




Write for complete details:

BUTTERWORTH

BRITISH AUTOMATIC MACHINE TOOL CO. LTD.

LINCOLN STREET, ROCHDALE

When answering advertisements kindly mention **MACHINERY**.



A TYPE FOR
EVERY DUTY

ASK FOR
DETAILS

IMPREGNATED DIAMOND WHEELS

by

SHAW

FOREMOST IN QUALITY —
SUPREME IN PERFORMANCE

A. SHAW & SON (DIAMONDS) LTD

WATERLOO RD., NORTH CIRCULAR RD., LONDON N.W.2
PHONE: GLADSTONE 1171-2 GRAMS: SCINDERE, NORPHONE LON.



Rubber Components for the more Exacting Applications

Our wide experience in the field of precision rubber engineering qualifies us to advise on the rubber compounds and design of components to meet the more exacting applications. Our plant is fully equipped to deal with bulk production as well as small quantity requirements for prototype and development work.

Designers and Engineers will be interested in our new publication, 'Synthetic and Natural Rubbers and their Uses' — copy sent upon request.

High Grade Rubber Mouldings and Extrusions · 'O' Rings
Seals · Bushes · Grommets · Diaphragms · Bonded Parts
and Components in Natural, Synthetic and Silicone Rubbers

OUTSTANDING NEW DEVELOPMENTS

PRESCOLASTIK

Silicone Rubbers in general purpose, low temperature and low compression set grades, available in a range of hardnesses. New fuel resistant grade also available.

PRESCOLLAN

The new polyurethane rubber with remarkable tear and abrasion resisting properties, easily machinable. Ideally suited to heavy duty engineering applications.


Please write for technical leaflets

APPROVED A.I.D. AND A.R.B.
PRECISION RUBBERS LIMITED · BAGWORTH · LEICESTER Phone: BAGWORTH 241/2/3
Producers of Rubber Mouldings to fine dimensional tolerances and officially approved specifications

When answering advertisements kindly mention **MACHINERY**.





**MULTI SPINDLE DRILLING
AND TAPPING MACHINES**
Adjustable arms or fixed centre
heads.




RIVETING MACHINES
Hammering up to 1" rivet.
Spinning up to 1". Fine riveting
up to 1/2".

**VERTICAL MILLING
MACHINES**
with power feed. Table size:
8" x 29" also hand lever oper-
ated with table size 4 1/2" x 9 1/2".



**BENCH DRILLS & BENCH
TAPPING MACHINES**
up to 1" capacity.



**PRODUCTION MILLING
MACHINES**
Horizontal milling machines
with power feed, table size
8" x 29". Also hand lever
machines with table size
6 1/2" x 27 1/2" x 9 1/2"

See the **STEINEL** *range first!*

CRAFTSMAN BUILT MACHINE TOOLS

For continuous service over many years under
exacting conditions, there is no better choice
than Steinel machine tools.
Modern in design and exceptionally sturdy, it pays
you to invest in Steinel.

*Illustrated data available
on each of the items shown*

CATMUR


MACHINE TOOL CORPORATION LIMITED

103 Lancaster Road, Ladbroke Grove, London, W.11. 'Phone PARK 9451/2

Rainbow 1390

When answering advertisements kindly mention MACHINERY.

TUBE BENDING MACHINERY



Illustrated is model MD.46.
Produces full bore bends unfilled
on short radii up to 6in. dia.
non-ferrous tube and 4in. dia.
light gauge ferrous tube.

- ★ Portable Hydraulic Machines to bend Gas and steam tube, light gauge copper and steel, etc., tube.
- ★ Hand and Power operated general purpose machines to bend up to 5in. diameter light gauge tube.
- ★ Hand operated and motorised Mandrel machines to produce uniformly accurate full bore bends on extra short radii, cold and without filling.

Visit us at the Chemical
and Petroleum Engineer-
ing Exhibition, Olympia,
June 18-28.



HILMOR LTD. (Sales & Service), Caxton Way, Stevenage, Herts.
Phone: Stevenage 881 Grams: Tubenders, Stevenage

The Newall Finance Scheme

arranged to solve immediate and future problems
of plant replacement and extension, is worthy of the attention
of large or small organisations adversely affected by credit restrictions or
temporary lack of working capital.

Full particulars submitted in confidence.



NEWALL GROUP SALES LIMITED, HIGH STREET, OLD FLETON, PETERBOROUGH

***Manufacture cylindrical, internal and
universal grinding machines — a range of precision jig
borers, lapping machines—optical inspection equipment,
and offer a complete machine tool re-precisioning service***

PARK GATE

QUALITY STEELS
FOR RAPID MACHINING



**special
freecutting
quality bars**

THE PARK GATE IRON & STEEL COMPANY LIMITED ROTHERHAM

A  Company


TELEPHONE: ROTHERHAM 2161 (10 lines) • TELEGRAMS: YORKSHIRE, PARKGATE, YORKS

RACK CUTTING SERVICE


Rack supplied from 16 D.P. to 1½ D.P. and corresponding circular and metric Pitches. Accuracy and high quality finish guaranteed. Complete supply of blanks available, but customers material used, if preferred.

Estimates given on quantity supply together with free sample of work, or demonstration can be arranged. All enquiries receive prompt attention.

**KEEN PRICES
QUICK DELIVERY**



Samples of racks and the machines which cut them.



Enquiries to

**HALIFAX RACK &
SCREW CUTTING
CO LIMITED**

OVENDEN, HALIFAX

Telephone: Halifax 62078/9



For increased efficiency...

Flexello
put it on Castors



'Putting it on castors' is certainly the way to speed things up, and to an amazing extent when the right castors are used for the job. The varied uses of Flexello castors are virtually limitless. They are used in nurseries and steel mills, aircraft plants and beauty parlours. Flexello has the range, the service and facilities to make castors the true servant of the production manager, the hospital matron, the restaurant manager or the storekeeper. Closest inspection, superior design and up-to-date production methods have made Flexello the largest castor manufacturer in Europe.

Only a very small section of our range is shown here. Please send for catalogue No. 156 M or a technical representative for industrial advice.

Flexello

CONSTANT QUALITY
CASTORS



FLEXELLO CASTORS & WHEELS LTD., SLOUGH, BUCKS. Tel: SLOUGH 24121

When answering advertisements kindly mention MACHINERY.



The 'Bijur' system fitted to an Archdale Transfer machine at the Standard Motor Company's Banner Lane Factory.

STANDARD MOTOR COMPANY LIMITED

AUTOMATION

uses Tecalemit Lubrication

At the Standard Motor Company's Banner Lane factory in Coventry, the "Tecalemit-Bijur" Lubrication System is fitted to the three Archdale Multi-Station Transfer machines. These machines are used for machining the transmission housings for 100,000 Massey-Ferguson tractors each year.

Three "Tecalemit-Bijur" Lubricating Pumps are fitted to each machine, providing a measured quantity of oil for 170 lubrication points, at correct intervals, through calibrated metering valves. The "Tecalemit-Bijur" System, protects every bearing surface of the machine with a film of clean oil.

Tecalemit lubrication increases production time by doing away with oiling shut-downs, and by prolonging the life and precision of the machines. There's no oil wastage and maintenance costs are considerably cut.



The Authority on Lubrication

TECALEMIT LIMITED
PLYMOUTH · DEVON



When answering advertisements kindly mention MACHINERY.

T686A

KALTENBACH HYDRAULIC COLD SAWING MACHINE

High Efficiency with Low Initial Cost

Available in 20in., 30in., 48in.
blade sizes.

Typical cutting times:—

Solid Bars 3in.—48 sec.
 14in.—12 min.


RSJ's 16in. × 4in.— 4 min.
 30in. × 12in.—12 min.

Extras available.

Mitre cutting up to 45deg.

Turntable base for machine with
hydraulic elevation.

High speeds up to 2,000 f.p.m.
for light alloys.



SIZE 48"

Sole British Agents


F.J. Edwards Ltd

EDWARDS HOUSE, 359-361 EUSTON RD., LONDON, N.W.1

Tel: EUSTON 4481 & 3771 Telegrams: Bescotools, Norwest, London

LANDSOWNE HOUSE, 41 WATER ST., BIRMINGHAM, 3

Telephones: Central 7406/8 Telegrams: Bescotools Birmingham 3



does the trick again . . .

giving the best performance possible, with the aid of the Polygon Tool Box. This lathe attachment swings the balance of production in your favour. Time spent on shapes such as hexagons, octagons, squares etc., is reduced by as much as ONE THIRD.


Why not write NOW for a copy of our descriptive booklet "The tool for the job."

Thomas Chatwin & Co.

GT. TINDAL STREET, BIRMINGHAM, 16

Telephone: Edgbaston 3521

ONE OF THE **BROCKHOUSE** COMPANIES



largest Continuous Broaching Machine

built in this country by

LAPOINTE



A close-up of Fixture incorporating acceptance gauge.

The 40/160" Continuous Broaching Machine is equipped with automatic clamping and unclamping Fixtures.

In one operation this machine will broach the half bore, joint faces, locating width faces and backs of bolt bosses on Connecting Rods.

British Made




The Lapointe Machine Tool Co Ltd

Otterspool Watford-by-Pass Watford Herts
Telephone Gadebrook 3711 (4 lines) Cables Lapointe Watford
Also the Lapointe Machine Tool Company Hudson Mass. USA

When answering advertisements kindly mention MACHINERY.

THE BEST AT IT'S PRICE!



"WITHOUT A DOUBT"

This is a long-life pump, self pumping, with hardened steel or ph. bronze gears.

Body in robust cast iron or stainless steel.

Delivery from stock in $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ " and 1" delivery.



EDWARD DAWSON (PUMPS) LTD
SAWLEY, NOTTINGHAM

Phone: Long Eaton 3243



'CENTEC' 2A & 2B


Universal Precision Milling Machines with

① ② ③ Possibilities of table movement

ALL GEARED 6 spindle speeds

BRITISH
MADE

Calibrated
dial and
lead screw



① 4 Power feeds

② Capstan handle
rack and pinion

With big advantage of fast table approach by Capstan Handle followed by automatic feed on cut and fast return by Capstan Handle.


Dividing head.

Quick-action
swivel vice.

Rotary table.

Table
working surface
2A—16in. x 4 $\frac{1}{2}$ in.
2B—25in. x 5in.

Long
Traverse
8in.
13in.



Vertical swivelling head for MILLING
and DRILLING at all angles.


CENTEC MACHINE TOOLS LTD.

Hemel Hempstead, Herts.

Telephone: Boxmoor 584-5-6



TOOLS FROM HALLMAC



the progressive decision

Hallmac carry immense and comprehensive stock ranges of Engineers' Small Tools, Macrome Treated Tools, Hand and Power Tools. Their distribution and service network covers the country. Your entire current needs in this field and all future expansions and special problems can be taken care of by the single decision—tools from Hallmac.

HALLMAC TOOLS LIMITED

Head Office and Depot: PO Box No. 39, Macrome Road, Wolverhampton. Telephone 52001 (9 lines)

LONDON: 21, Ivor Place, N.W.1. Telephone PADdington 0204

MANCHESTER: Transport House, 1 The Crescent, Salford 5, Lancs. Telephone PENdleton 3656

GLASGOW: Central Chambers, 11 Bothwell Street, C.2. Telephone CENTral 5066

Sales Managers for the Hand Tool Division of the Bren Manufacturing Company

JW.Ad 4308

When answering advertisements kindly mention MACHINERY.

Flash weld your Band Saws *Automatically*

ON THE **STRYCO BAND SAW WELDER**

Heavy duty, for production or repair work. Motor driven cycle flash-welds all band saws from the heaviest to the lightest—quickly, simply, and in perfect alignment.

MF.1—4 kVA. 1" capacity. MF.2—6 kVA. 1½" capacity
MF.3—8 kVA. 2" capacity



SOLE U.K. DISTRIBUTORS:

**DOWDING & DOLL LTD**

346 KENSINGTON HIGH STREET, LONDON, W.14

Telephone WESTERN 8877 (8 lines)

Telegrams ACCURATOL HAMMER LONDON

Write for the
fully illustrated
folder

124

DING-DONG HACKSAW & BANDSAW BLADES

FOR FAST CUTTING & LONG LIFE

'DING-DONG' Hacksaw Blades are manufactured in two qualities—**REGULAR TUNGSTEN BLADES** in a combination giving excellent cutting, long endurance and an unusual degree of elasticity. **HIGH SPEED STEEL BLADES** contain a high percentage of Tungsten which gives less elasticity and although they have not the same flexibility they are tougher, more durable and definitely more suitable for the very hard, difficult metals used to-day.

**FLEXIBLE BACK
METAL - CUTTING
BANDSAW BLADE**

Used on all types of metal cutting Bandsaw and Jigsaw machines. Ideal for profiling steel, iron, aluminium, brass, copper, fibre and plastics in slab, sheet, tube, cast, extruded or rolled sections. First class Bandsaw Blades for toolroom or production requirements.


CHARLES BAYNES LTD • KNUZDEN BROOK

Telephone: BLACKBURN 6862

BLACKBURN

OBTAINABLE FROM ALL LEADING TOOL DEALERS

Telephone: Huddersfield 3897/8

'KEIGHLEY' GEARS

Offer a wide range of KEIGHLEY STOCK SPUR GEARS for immediate delivery. They cover drives up to 32 H.P., with ratios selected to meet almost any requirement. Publication E.321.2 lists complete design details.

If your requirements are for gears of your own design, our excellent gear-cutting service gives you attractive deliveries for complete gears or teeth only cut in your blanks.


THE
DAVID BROWN

CORPORATION (SALES) LIMITED
KEIGHLEY GEAR DIVISION
PROSPECT WORKS LOCKWOOD
HUDDERSFIELD

★ The SPECIALISTS for SPECIALS

- In addition to*
- ★ ANY TYPE OF MILLING CUTTERS
ARTHUR MARTIN have pioneered
 - ★ FORM RELIEF WORK
are still
 - ★ ACKNOWLEDGED EXPERTS
and have
 - ★ THE LARGEST CAPACITY
for
 - ★ FORM RELIEF CUTTERS
in the country enabling them to give
 - ★ QUICK DELIVERY


Sooner or later all who are outstanding in British Engineering use



★ ARTHUR MARTIN MILLING CUTTERS

AND SHANK TOOLS - ARTHUR MARTIN (MILLING CUTTERS) LTD
Westcombe Park Works, London, S.E.10. Tel. No. GREENwich 3826

When answering advertisements kindly mention MACHINERY.



STEPHENS BELTING COMPANY LTD.

SNOW HILL · BIRMINGHAM 4

associated with IRA STEPHENS LTD. Ashton-under-Lyne, Lancs.

STEPHENS Miraclo

"CONSISTENTLY SATISFACTORY SERVICE"


The conversion of this Bentley & Jackson Beater from lineshaft to short centre drive proved well worth while. A 30 h.p. motor with 10 $\frac{1}{2}$ in. by 9in. motor pulley running at 725 r.p.m. to a 48in. by 12in. Beater pulley at 158 r.p.m. with centre distance of 44in. is used and the first Miraclo belt gave "two years' consistently satisfactory service." The Directors have now specified Miraclo for all similar machines.



Write today for this 12-page colour Brochure No. 103 which tells you... **HOW TO DESIGN A MIRACLO DRIVE.**

S72

*You can see why appliances
which **MUST** be absolutely reliable
in operation are fitted with*
Drayton HYDROFLEX metal bellows



An instrument manufacturer writes:

"We think you might be interested in the enclosed bellows which were subjected to a violently fluctuating pressure of 1,500 lbs/sq" as the result of a technical hitch. The bellows did not leak which we think is a very great tribute to their manufacture".

★ HYDROFLEX metal bellows are suitable for all thermostatic and pressure sensitive applications. Write for List No. G800-1.

B.17
The Drayton Regulator & Instrument Co. Ltd., West Drayton, Middlesex



When answering advertisements kindly mention **MACHINERY**.



FOR HOLES AS SMALL AS 0.004in. YOU NEED— THE **BT & D** CAPILLARY DRILL

THE ANSWER TO
PRODUCTION
ENGINEERS'
'HEADACHES'
ON FINE HOLE
DRILLING

Holes 0.004in. to 0.0625in. diameter operated from the normal compressed air line—60lb. only per square inch required—inverted drill simple to operate and adjust by unskilled labour—fuel injection nozzle drilling worries entirely eliminated—work holder body swivels to angle required—drill body adjustable on horizontal slide. Price and delivery on application.

Demonstration by appointment.

We also design and manufacture Jigs, Fixtures, Press Tools, etc. A.I.D. and A.R.B. approved.

MEMBERS OF THE GAUGE & TOOL MAKERS' ASSOCIATION


SOLE MAKERS:—

BIRFIELD TOOLS LTD.

BODMIN ROAD, COVENTRY.

*Phone: Walsgrave-on-Sowe 2371





Introducing the new

RUBERT

HIGH PRECISION REFERENCE SQUARES


made in one solid piece

By eliminating any rivets or dowels these squares are extremely stable and keep their accuracy permanently. One outside face and one inside face are glass-hard knife-edges and the accuracies for all sizes conform to the reference grade of BSS.939, which is $\pm 0.000\ 05$ in. for squares up to 6 in. and $\pm 0.000\ 08$ in. from 6 in. to 12 in.

Delivery from stock :-

RUBERT & CO. LTD., Chapel St., Levenshulme,
Manchester 19.

Telephone : RUSholme 4613



ARBOGA

VERTICAL MILLING MACHINE
MODEL EM 825

Fills an outstanding requirement for small work.

- Table, 17½ in. by 9½ in. or 22 in. by 9½ in.
- Longitudinal traverse, 11 in. or 15 in.
- Eight speeds, 100 to 2,900 r.p.m.
- Table to Spindle 20 in.
- Swivelling head, Rigid Column, Cast-iron base, No. 3 Morse Taper, 1 in. bore.
- Price: £265, 17½ in. table. £277 10s., 22 in. table.

DISTRIBUTORS AND STOCKISTS FOR THE UNITED KINGDOM.



MORTIMER
ENGINEERING CO.
ROBROTH TOMES & QUINTERMAN & CO. LTD.



Showroom & Sales: 204-206 Acton Lane, Harlesden, N.W.10. Tel. ELG 3834

FAST AND ACCURATE MACHINING AJAX AJ8P MILLING MACHINE



TOOL ROOM ACCURACY WITH
LARGE SCALE OUTPUT
PEDESTAL OR BENCH MODELS
AVAILABLE


Gives accurate work from unskilled labour. Rack and pinion screw-feed and micrometer dial for transverse speed. Feed lengths 8 in. longitudinal, 3½ in. transverse, 6½ in. vertical. Table surface, 16 in. by 4½ in. Max. spindle centre to table 6½ in. Arbor dia. 1 in. Four speeds. Push button control of ½ h.p. motor.

AJAX

AJAX MACHINE TOOL Co. Ltd.
WEST MOUNT WORKS, HALIFAX, YORKS.
PROP.: ADA (HALIFAX) LTD.

When answering advertisements kindly mention MACHINERY.

Q★



*for Toolroom
and Production*

(TAYLOR)

**VERTICAL
MILLING MACHINE**

- ★ FOUR SPINDLE SPEEDS
430, 740, 1220 and 2090 R.P.M.
- ★ TWELVE TABLE POWER FEEDS
RANGE $\frac{1}{2}$ " to 10" PER MINUTE
- ★ $\frac{5}{8}$ " COLLET CAPACITY
- ★ WORKING SURFACE OF TABLE $17\frac{3}{4}$ " \times $5\frac{1}{2}$ "

HEIGHT 61"
DEPTH 33"
WIDTH 27"

Prompt Delivery £300 Ex-Works

GEO. TAYLOR & SON (ENGINEERS) LTD.


SWAN LANE, COVENTRY Telephone 64246

Available Ex-Stock from

ACBARS LTD. BUCK & HICKMAN LTD. M. C. LAYTON LTD.
PIDGEN BROS. LTD. STEDALL MACHINE TOOL CO.

Stationary Movement!

Faulty operation of your high speed machinery may easily be located with this HIGH SPEED STROBOSCOPE
Range: 7,000 — 40,000 r.p.m.



• HIRE FACILITIES AVAILABLE.

Dukes & Briggs Engineering Co. Ltd.

APPROACH ROAD, off BARTON DOCK ROAD,
URMSTON, MANCHESTER.

Telephone: URMston 6121

MANUFACTURERS OF PROCESS TIMERS,
POWER SUPPLIES, SPECIAL EQUIPMENT, ETC.

NYLON *Always in Stock*
NYLON
*In Rod
Tube, Sheet
or
Tape Form* **NYLON**

Also manufacturers of

**GEARS, BUSHES, BEARINGS
AND ROLLERS IN NYLON**

Gears cut in all materials from one off to a production run; Blanks supplied in Texolex, Nylon and non-ferrous metals; Gears cut from customer's own material; Reduction Gear Boxes from 5-1 to 80-1.

BRITISH RAWHIDE BELTING CO. LTD.
246 GT. PORTLAND ST., LONDON, W.1

Telephone: EUSton 6404


and at 15, Paradise St., Liverpool, 1.

When answering advertisements kindly mention MACHINERY.

STEEL KEY TO INDUSTRY

Credton, in Devon, has a church built in the 14th and 15th centuries. The church has a garden surrounded by a wall, and in that garden this key was found. Could it have been the key to the door shown in the illustration? Certainly the garden would be a natural place in which to lose the key which is a hand-wrought specimen of about that period. The church contains relics of "town armour". Was it the keeper of the armour who lost the key?

No. 29



We shall never know, but we do know that the development of steel made possible the growth of civilisation itself. For steel is the key to the good things of life as well as to the necessities; as essential to the maker of the precision watch as to the bridge builder. Hallamshire high-grade Alloy and Carbon steels serve a multitude of industries in many ways.

Manufacturers of:

ALLOY AND SPECIAL CARBON STEELS
BARS • SHEETS • PLATES • WIRE RODS


Hallamsteel

THE HALLAMSHIRE STEEL CO. LTD., SHEFFIELD 3, ENGLAND

Tel.: Sheffield 24304 (7 lines)
Grams: Hallamsteel, Sheffield



Tel: INGREBOURNE 3615



PRODUCTION TOOLS & MACHINERY
DESIGNED & MANUFACTURED



L. A. DREW & Co. Ltd. BRYANT AVENUE • ROMFORD

ESSEX

When answering advertisements kindly mention MACHINERY.

Q.K.2

MARLOW

Mk. IV VERTICAL MILLING MACHINE

- ▶ SWIVELLING AND DOWN FEED HEAD
- ▶ LARGE CAPACITY
- ▶ TABLE 28" × 8"
- ▶ 6 SPEEDS 85 to 1,450 r.p.m.
- ▶ SPINDLE TO TABLE 20"
- ▶ HEIGHT 80;

MARLOW Models

MK IV (Illustr.) £285

MK I 22" × 6" £198


MK II 28" × 6" £210

MK III 2" × 88" £225

VICTA ENGINEERING CO

Offices:
Thicket Corner, Maidenhead
Tel 50 and at: Eagle Works,
Chester Rd. Boreham Wood,
Herts.

Tel: Elstree 3146




**DIE CAST ALUMINIUM ALLOY
HAND WHEELS
WITH CAST IRON INSERTS**
CURVED AND STRAIGHT ARM TYPES

STANDARD RANGE OF SIZES FROM 3" TO 18" DIAMETER
GOOD DELIVERIES — SPECIALS TO ORDER

R.C. HARRISON & SONS (BRASSFOUNDERS) LTD.
GOUGH ROAD, LEICESTER
ESTABLISHED 1911 TELEPHONE 67805

MAXIMUM

GRIP



MEANS...

HUMPHREYS

MAGNETIC CHUCKS


New standard equipment in most leading engineering shops
HUMPHREYS magnetic chucks are available in a full range of
sizes and types: rectangular, circular or swivelling.
Ask for details.

J. H. HUMPHREYS & SONS LTD.
LACKRIDGE ELECTRICAL WORKS WERNETH OLDHAM

WIGGLESWORTH

short centre
V rope drive.
"TEXROPE"

*proved
best
by
test*



FRANK WIGGLESWORTH & CO. LTD.
SHIPLEY "Phone" SHIPLEY 53141 YORKS.
Grams: CLUTCH/SHIPLEY

When answering advertisements kindly mention MACHINERY.

COMPRESSION SPRINGS

This photograph shows a few examples of high-quality precision springs, made by Riley. Some were produced to customers own specifications, others were the result of recommendations by the Riley design and research department. If you have any kind of spring problem, Riley will find the answer to it.

(The diagram shows information required when ordering this type of spring.)



There are no finer springs than Springs by

Riley

ROBERT RILEY LTD., MILKSTONE SPRING WORKS, ROCHDALE, Tel: ROCHDALE 2237 (6 lines) Grams: 'RILOSPRING' ROCHDALE TELEX 63-362

**AUCTIONEERS & VALUERS
OF
PLANT, MACHINERY
AND FACTORIES**

SINCE 1807

**FULLER HORSEY
SONS & CASSELL**

10, LLOYDS AVENUE · LONDON · E.C.3. Phone ROYAL 4861



**BENSON
BOND** EDWARDS RD-ERDINGTON
BIRMINGHAM 24
PHONE
ERDINGTON 4216 (5 LINES)

**FOR
CLEVELAND**

MO-MAX  **MO-MAX COBALT**  **CLE  FORGE** 

**THE BEST PRESSINGS
ARE MADE FROM
SIMPLE TOOLING AND**



The universal drawing device
for any size and make of press

WORSON DIE CUSHIONS LTD.
RABONE LANE WORKS · SMETHWICK · STAFFS.



Cross
THE BRITISH
* **WIRE THREAD
INSERT**
MADE FROM D.T.D. 239 WIRE
HARDENED & TEMPERED

This material is suitable for use in parts made in all metals including aluminium or magnesium. We also make stainless steel inserts suitable for use in ferrous metal parts and bronze inserts for use where full non-magnetic properties are required.

CROSS MANUFACTURING CO. (1938) LTD.
BATH · SOMERSET

Telephone: Combe Down 2355-8 Telegrams: Circle, Bath.

When answering advertisements kindly mention MACHINERY.

If it's micrometers you want

**HOBBCO TOOL
COMPANY**

214 HATFIELD ROAD,
ST. ALBANS HERTS.
TEL: ST. ALBANS 51730, 57993

***over 1000
always in stock***

STRAUSAK DUPLEX PIVOT BURNISHING MACHINE

SWISS MADE

TYPES 119 & 119a



Type 119
Bench Model

Recommended for:

WATCHES · CLOCKS · DIAL GAUGES
METERS · INSTRUMENT MECHANISMS
PROMPT DELIVERY!

This highly efficient machine, widely used throughout the Swiss Precision Industries, has a productive capacity two to three times greater than anything hitherto available.

For burnishing both ends of a pinion simultaneously, the operator simply drops the part on to a pair of notched feed discs, after which the operation is entirely automatic.

The carbide laps are fully adjustable, permitting conical or pivots of different diameters at either end to be burnished at the same time.

SPECIFICATION:

- ★ PIVOT DIA. 0.002in. to 0.059in.
- ★ PINION LENGTH $1\frac{1}{8}$ in.
- ★ CUT (Type 119) or UNCUT (Type 119a) PINIONS
- ★ BENCH OR STAND MODELS
- ★ PRODUCTION RATE 600/900 per hour

Sole U.K. Agents:

Adam machine
equipment
limited

4 GRANGE STREET, ST. ALBANS, HERTS.
TELEPHONE: ST. ALBANS 56731-2


When answering advertisements kindly mention MACHINERY.



MEKELITE

GEARED  JOINT

INDUSTRIAL LIGHTING UNITS




To ensure satisfactory service extra friction surfaces are provided as required by the size of reflector used and its distance from the base. For light loads a single pair of links is sufficient. Bases for wall, bench, ceiling, floor or mounting direct on machines; also portable types. With pillar or short vertical pivot. Six sizes of reflector and various lengths of arm (maximum horizontal reach 54in.).

Catalogue sent free on request.

MEK-ELEK Engineering Ltd.

17, Western Road, Mitcham, Surrey
Telephone: MITcham 1072 Cables: MEK-ELEK, London



CAM BLANKS

For:
Brown & Sharpe Index, B.S.A. Tarex,
C.V.A. Manurhin, Wickman, Tornos,
Petermann and Bechler Automatics
CAMS DESIGNED & MACHINED

MOSER CAMS & TOOLS LTD.

465, HORNSEY ROAD, LONDON, N.19.



Tel.: ARCHWAY 1766 and 7017

Now available in this country

MECHANISED GAUGING

by LA PRECISION MECANIQUE

Effects substantial savings of time and skilled labour. Low in first cost, this equipment gives great accuracy with absolute reliability.



ESE will design and build to your specific requirements.



ENGINEERING & SCIENTIFIC EQUIPMENT LTD.
33 MINSTER ROAD, LONDON, N.W.2.
TELEPHONE: HAMPSTEAD 1459.

NRP 1872

BUCK & RYAN LTD

ESTABLISHED 1824

ENGINEERS' TOOLS

LARGE STOCKS OF
FINE TOOLS

Micrometers Height Gauges Verniers
Etc.

CUTTING TOOLS

Milling Cutters Taps Dies Reamers
Etc.

LIGHT MACHINE TOOLS

Lathes Millers Drillers Etc.

HAND TOOLS

A VERY LARGE SELECTION


DEPT. 5

310/312 EUSTON ROAD LONDON NW1

AND AT 261 EDGWARE ROAD W2

Telephone: EUSTON 4661

When answering advertisements kindly mention MACHINERY.



*precision
is the
background*

We have a standard range of Automotive and Industrial Gear Boxes, or can undertake the supply of loose gears and shafts to your own design.



THE GEAR SPECIALISTS

Cut, ground or shaved Spur and Helical Gears.
Ground Worms and Splines—Bevels—Reduction Units—Gear boxes for all Trades.

A.I.D. Approved

P. R. MOTORS LTD - ALDBOURNE ROAD
COVENTRY

Telephone : 2266 (3 lines)

Telegrams : Supagears, Coventry

When answering advertisements kindly mention MACHINERY.

HUNT'S

Machines we

Manufacture

TWIST DRILL SHARPENING MACHINES

Six sizes $\frac{1}{8}$ in. - 4 in.

TAP SHARPENING MACHINES

Three sizes $\frac{1}{8}$ in. x 6 in.

SURFACE GRINDING MACHINES

18 in. x 6 $\frac{1}{2}$ in. x 12 in.

TOOL & CUTTER SHARPENING MACHINES

10 in. x 20 in.

TWIST DRILL MANUFACTURING

For : Flute Milling, Clearance Milling, Clearance Grinding

TAP & REAMER MANUFACTURING MACHINES

For : Flute Milling, Relief Grinding, Flute Grinding

PEARNS TAPPING ATTACHMENTS AND ACCESSORIES

Write for full particulars :

HERBERT HUNT & SONS LTD.

ELSINORE RD., OLD TRAFFORD, MANCHESTER, 16

Phone: 0663-0664 Trafford Pk. 'Grams: Hunting Manchester



MODIFIED ACME THREAD

Master of precision


Every "Castle" craftsman knows his part to perfection. Give him the opportunity and he will solve your component production problems with that little extra skill and "know-how" in all things pertaining to **REPETITION WORK IN ALL METALS, PRECISION TURNED AND SCREWED, MACHINING AND LIGHT ASSEMBLIES.** Write for brochure.

The Castle Engineering Co.

(NOTTINGHAM) LTD.

HASLAM STREET,
CASTLE BOULEVARD,
NOTTINGHAM


Telephone:
Nottingham
49068 (3 lines)



We make our
own gauges and
jigs to supply our
customers' needs.




it's as simple as ABC on ...
The DAVID DOWLING
Model 713 Bench ENGRAVING MACHINE



Gives reductions from 1:2 to 1:8 as required. Exceptionally fast operation enabling engraving to be carried out nearly as fast as ordinary writing. Exceptionally sensitive balanced pantograph, giving automatic withdrawal of cutter and tracer. An independent hand down feed to the cutter spindle gives a fin. vertical movement. Other engraving machines and full range of equipment available; details will be sent on request.

DAVID DOWLING LTD., ROEBUCK ROAD, HAINAULT, ILFORD.
Tel. HAINAULT 4121


For Production
JACKMAN
Disc
GRINDERS



Speed up first operation flat
surface jobs—Discs 30" to 72" dia.

GEO. JACKMAN MACHINE TOOL CO. LTD.
73 EASTBOURNE AVENUE, LONDON, N.9.

When answering advertisements kindly mention **MACHINERY**.



MACHINERY'S

BOOKS ON MACHINE SHOP PRACTICE

MACHINERY'S HANDBOOK

(Latest Edition, Thumb-Indexed.)

Presents in one complete volume all the essential data for the entire field of shop practice and machine tool design. Amply illustrated by diagrams accompanied by proven data, the latest printing of this world-famous book gives not only all the old, tried and proved features of earlier editions, but, in addition, the most useful, recent and complete collection of data, standards, formulae and practical information.

Price 72s. cash and C.O.D. Instalments 80s., payable 13s. 4d. in 10 days, 13s. 4d. monthly. Overseas, cash with order, plus 3s. postage.

CAPSTAN AND TURRET LATHE PRACTICE

—C. Monday Machinery's Standard Reference Series

A treatise on the construction and application of modern capstan and turret lathes. Discusses various types of lathe and their operation, chucks, collets and other workholders, cutting tools, and the methods of turning, facing, profiling, drilling, boring, reaming and screw cutting in these lathes. Considerable space is devoted to tooling and setting-up examples with estimation of times.

Price 18s. 6d. cash and C.O.D. Instalments 20s., payable 6s. 8d. in 10 days, 6s. 8d. monthly. Overseas, cash with order, plus 2s. postage.

TOOL AND CUTTER GRINDING—R. S. Connell

Machinery's Standard Reference Series

A comprehensive text dealing with toolroom grinding. It describes equipment and special machines for tool and cutter grinding and gives detailed instructions for dealing with turning, planing, shaping and slotting tools, twist drills, milling cutters, thread-cutting tools, broaches and gear-cutting tools. Contains many illustrations and much useful data.

Price 18s. 6d. cash and C.O.D. Instalments 20s., payable 6s. 8d. in 10 days, 6s. 8d. monthly. Overseas, cash with order, plus 2s. postage.

CENTRE LATHE WORK—C. Monday

Machinery's Standard Reference Series

Covers all applications of the modern centre lathe, also its detailed construction and modifications, together with tools, chucks, collets, fixtures and attachments. Methods of producing typical workpieces to accurate dimension are fully dealt with, including the cutting of threads, turning tapers, form turning and the various systems of profile and copy turning.

Price 18s. 6d. cash and C.O.D. Instalments 20s., payable 6s. 8d. in 10 days, 6s. 8d. monthly. Overseas, cash with order, plus 2s. postage.

MANUAL ON CUTTING METALS

Much new material has been added to this latest edition. It constitutes a practical and comprehensive guide to the machining of metals, using single-point tools, taking into account the metallurgical and mechanical factors: choice and use of cutting fluids, the tool and work materials and the speeds, feeds, forces and power. Contains 322 data tables in 546 pages.

Price 84s. cash and C.O.D. Instalments 92s., payable 15s. 4d. in 10 days, 15s. 4d. monthly. Overseas, cash with order, plus 3s. postage.

FREE APPROVAL NO DEPOSIT INSTALMENTS

To MACHINERY, National House, 21 West Street, Brighton, 1.

Please send me books marked X above

For CASH herewith or by C.O.D. or

ON APPROVAL when I will either return in 5 days, or

pay FULL CASH, or by INSTALMENTS as stated above.

Name Position

Address Firm.....

Write for Book Catalogue and details of Instalment Terms.

When answering advertisements kindly mention MACHINERY.

From
London
Stock

The

DAVLA

Mark II
(British Made)



Motorised
9" Saw
Bench

Saw arm has instantaneous rise and fall movement and can be clamped in any position.


TABLE: Working surface 19in. by 14½in., tilts to 45°. Mitre fence swivels to 60° and can be used on EITHER side of sawblade. ALSO ON FLOOR STAND: Motorised for 3-phase, single phase or D.C.

Distributors and Stockists for the United Kingdom:



Showroom & Sales: 204/206 Acton Lane, Harlesden, N.W.10. Tel. Elgar 3834

MODEL MARK 'SPECIAL PROCESS' HAND STAMPS



The "SPECIAL PROCESS" yields an advantage over the common method of mark making in that it produces absolute uniformity of character. This ensures a fidelity throughout the range and forms an impression which is at once recognisable as a "MODEL MARK".

Send for our marking devices catalogue

THE STANDWELL EQUIPMENT CO. LIMITED
CAMBRIDGE GROVE ROAD, KINGSTON-ON-THAMES
Telephone: Kingston-on-Thames 4566 (3 lines)
Telegrams and Cables: IMPRESS, KINGSTON-ON-THAMES

INDUSTRIAL FIRST AID



For 60 years we have specialised in the First Aid requirements of Industry.

Our service is most comprehensive; whether you require a completely equipped ambulance room for a vast factory or a first aid box for a "one man" works we shall be pleased to advise and supply you.

A PRODUCT OF

Cuxson, Gerrard & Co. Ltd.
OLDBURY BIRMINGHAM

Pioneers of Industrial First Aid

MAKING OR CUTTING

GEARS

SPUR • BEVEL • WORM • SPIRAL
SPROCKETS • RACKS

RODGERS BROS. LTD.

LONDON GEAR WORKS
BLACKWELL ST., Brixton Rd., S.W.9
PHONE: RELIANCE 2851

INOPERATIVE

Skilled hands are soon out of action when dermatitis strikes. But dermatitis can be avoided—simply—by using Rozalex.


For over 25 years Rozalex have specialised in barrier creams for industry. They

have found the answer to most industrial skin irritants. Their full technical knowledge and experience are at your disposal on request to Rozalex Limited, 10 Norfolk Street, Manchester 2.

ROZALEX BARRIER CREAMS

RBSF

When answering advertisements kindly mention MACHINERY.



foot lever PRESSES

Specially designed for high output with unskilled labour. Foot operator's hands free for manipulation of the workpiece. Supplied for bench or stand mounting.
PROMPT DELIVERY.
Ask for details.

ASK FOR CATALOGUES OF COMPLETE RANGE OF DIAL GAUGES, PRESSES AND DRILLING MACHINES
GENEROUS TERMS TO MERCHANTS

MANUFACTURED SOLELY BY

ENGINEERING PRODUCTS LIMITED

GLENBROOK WORKS, LITTLERS CLOSE,
MERTON ABBEY, LONDON, S.W.19

Telephone: LIBERTY 1085 & 1084

GET OUR TEETH
INTO IT



All over the world gears are to be found with teeth cut by us. We cut thousands every year and we can cut teeth for you too.

Our technical representatives will be pleased to call and discuss your requirements.

AURORA GEARS

- GEARS OF EVERY DESCRIPTION
- COLLIERY GEARING A SPECIALITY

AURORA GEARING CO. (WILMOT NORTH) LTD.,
EDMUND ROAD SHEFFIELD


(A subsidiary of Aurora Gear & Engineering Co., Ltd.)

When answering advertisements kindly mention MACHINERY.

Cut SET-UP COSTS!



ALL SIZES
DELIVERED
EX-STOCK



Change to ROCKWELL HELICAL CLAMPS

BRITISH PATENT

Why waste time building up rickety, makeshift clamps with anything that's handy? Get on the phone today and ask for full information about Rockwell Helical Clamps. These ingenious clamps have been designed for simple quick and positive mounting, with negligible clamp projection over work piece. Each clamp is a complete unit, with no parts to lose.

• WRITE OR PHONE FOR LEAFLET GIVING PRICES
SIZES AND FULL TECHNICAL DETAILS
-TODAY!

WELSH HARP, EDGWARE ROAD,
LONDON, N.W.2. GLAdstone 0033

ROCKWELL
MACHINE TOOL CO. LTD.

Also at Birmingham—Springfield 1134/5. Stockport—Stockport 5241
Glasgow—Merrylye 2822

SC5


TOOLMAKER'S DRILL CHUCK



FOR GREATER
ACCURACY
in less time



MACHINE SHOP EQUIPMENT LIMITED
Spenser Street, London, S.W.1.
Telephone: VICtoria 6086



Surface & Localised Flame Hardening by the "Shorter Process"

We treat Gearing of All Types, Cams, Levers, Shafts, Drum
Rolls, Dogs, Clutches, Machine Beds, Slides, Spindles, etc.
In all Carbon and Alloy Steels, Plain and Alloy Cast Iron,
Meehanite and Malleable Steels.

THE JAY EFF FLAME HARDENING CO., LTD.
LITTLE HOLME STREET, LEICESTER
PHONE: LEICESTER 21998

These PARALLEL ACTION Pliers are FIRM FAVOURITES with all TRADESMEN



END CUTTING
NIPPER
No. 301



FLAT NOSE
PLIER
No. 486



SIDE CUTTING
PLIER
No. 495



CLAMPING
PLIER
No. 479



SNIPER NOSE
PLIER
No. 433

MAUN INDUSTRIES LIMITED MANSFIELD, NOTTS.

CLASSIFIED ADVERTISEMENTS

RATES: PLAIN ADVERTISEMENTS Except "Situations Wanted" (ALL TYPE): 2/2 per line. MINIMUM 8/P (4 lines) OR £1 8s. 2d. per inch (13 lines per inch). Box Nos. 1/3 extra per insertion. SITUATIONS WANTED: 1/6 per line. MINIMUM 6/8 plus 1/3 Box No. SPECIAL DISPLAY TYPE (with or without Blocks): 1/4 p. £1 10s.; 1/2 p. £3; 3/4 p. £6 or £2 per inch (min. 1/2 in.). Series rates on request.

CONTRACT WORK

...DESIGNS...

PRECISION PRODUCTS (ROMFORD) LTD.

TOOL DESIGNERS
AND MANUFACTURERS

For all your needs

IN
JIGS · FIXTURES
GAUGES · PRESS TOOLS
FORM TOOLS AND
SPECIAL MACHINES



Viking Works, London Rd.,
Romford, Essex. Tel: Romford 61991/2

CHIS R. E. CARDER LTD. CHIS
5842. 4611.
1 & 2, Chiswick Common Road, London, W.4
JIGS — TOOLS — AND PRESS TOOLS
UNIVERSAL GRINDING
—JIG BORING GENERAL
GOOD CLASS MACHINING WORK—
DESIGN OFFICE & DEVELOPMENT WORK

DESIGNING & MANUFACTURING TO
THE TOOL MAKING TRADE
INCLUDING JIG BORING & PROTOTYPE
WORK TO AIR MINISTRY STANDARDS
A.I.D. & A.R.B. APPROVED

Williams & Hiffe Ltd. Tel: 88944
IRON BRIDGE WORKS, MIDNORTH ROAD, LONGFORD, COVENTRY

Established Design Organisation
have capacity available for Production
planning and detailed design of Press Tools,
Jigs and Fixtures, Special Machines, etc.—
NORRIS BROS., LTD., 53, Victoria St.,
S.W.1. Phone: ABDeY 6132 and Brighton 55586.

PRODUCTION EQUIPMENT
DESIGN CONSULTANTS
In all Directions
DESIGNEX
(COVENTRY) Ltd.
can help
Phone 64049

PRESS TOOLS
LAMINATIONS—COMBINATION—PROGRESSION, ETC.
JIGS—FIXTURES
PROTOTYPE MACHINING
Designing—Short Order Work—Sub Assemblies Completely Tooled
JIG BORING AND PRECISION GRINDING
LANDEN (ENGINEERS) LTD.
1a, Aubert Park, Highbury, London, N.5
Phone: CANbury 1075

...GEARS...

Spur Gear and Sprocket Cutting
from blanks supplied or machined complete.
Phone: EUston 1354.

TURNER BROS.,
10, Pratt Mews, Camden Town, N.W.1

CAPACITY AVAILABLE for
CLOCKWORK MECHANISMS
INSTRUMENTS ASSEMBLIES
PRODUCTION OF SMALL GEARS
and TURNED PARTS

ROBERT PRINGLE & SONS
36-42 Clerkenwell Road, London, E.C.1
Telephone: CLerkenwell 2341

GEARING FOR INSTRUMENTS

CUSTOMER'S OWN BLANKS ACCEPTED

Capacity shortly available for:—
HIGH PRECISION GEAR CUTTING
(Max. O.D. 5in. Min. D.P. 120)
Bore/P.D. Concentricity .0005"
● **THREAD MILLING**
(Up to 1 1/2 in. dia. by 2 1/2 in. long)
(Over 1 1/2 in. dia. by 4 1/2 in. long)
● **BENCH LATHE TURNING**

F. BROWN (ESTABLISHED 1899)
150, Upper Street, Islington, N.1. CAN 4287

GEARS—PRECISION AND INSTRUMENT MACHINE CUT
Max. capacity 12 D.P. 8in. dia.
Blanks turned and cut.
SETON CREAGHE ENGINEERING LTD.,
TRADING ESTATE, PARK ROYAL ROAD, N.W.10
A.I.D. Phone: ELGor 3356/7 A.R.B.

● **ENGINEERING BUYERS NEED MACHINERY'S ANNUAL BUYERS' GUIDE**

When answering advertisements kindly mention **MACHINERY**.

Classified Advertisements (CONTRACT WORK, contd.)

Complete production of

GEARSSPURS · SPIRALS · BEVELS
WORMS · WHEELS · RACKS
SPROCKETS & CLUTCHESExtra rapid delivery
from Customers own BlanksA.I.D.
APPROVEDCOMPLETE
GEARED
ASSEMBLIES**THE DAVALL GEAR COMPANY LTD.**GEARWORKS · HIGH STREET · POTTERS BAR · MIDDLESEX
Telephone POTTERS BAR 2382/3**IMMEDIATE CAPACITY AVAILABLE**

- GEAR CUTTING to 24in.
- THREAD MILLING 6in. by 48in.
- PLANING 6ft. by 2ft. 6in.
- BROACHING

MAURALL ENG. CO.
38-40, Upper Clapton Road, E5

Telephone: AMHerst 6163.

Gear Cutting, Auto Turret, Capstan
and Centre Lathe Turning, Milling,
Planing, Hardening and Grinding,
Profile Cutting and Welding.**SMITH & NETHERWOOD,**
LTD.Tanyard Road, Quarmby,
HUDDERSFIELD.
Phone: MILNSBRIDGE 1865.**CUTTING****FOR SMALL QUANTITIES**

up to 24in. dia. by 12in.

face,

up to 15in. dia. by 9in.

face.

1 in. to 10 in. centres.


max. o/d. worm. 4 1/2 in. dia.

1/2 in. dia. to 6 in. dia.

up to 1 in. pitch chain.

**R.W. MUNRO, LTD.** Cline Road, N. 11

Telephone: ENT 4422-3

NAISH BROS. & CO., LTD.,
124, CHELTENHAM ROAD,
BRISTOL - Tel.: 25532-3.**PRESS TOOLS
FIXTURES
SPECIAL MACHINES
PRESSINGS
GEARS****CINETRA**
(A.I.D. approved)
for**FINE PRECISION
ENGINEERING**

Telephone: GULliver 2353 / 4085

GENERATED GEARS
10 to 100 DP, to finest
tolerances12, OVAL ROAD,
LONDON, N.W.1.When answering advertisements kindly mention **MACHINERY**.

A.M.D.

for
HIGH CLASS WORKMANSHIP
RELIABLE DELIVERY DATE
ECONOMIC PRICES

COMPLETE ASSEMBLIES
JIGS AND TOOLS
GEAR CUTTING
SHEET METAL WORK
GENERAL MACHINING

Send for
 copy of
 special brochure

A.M.D. ENGINEERING CO LTD · BEAUFORT ROAD · EAST TWICKENHAM

Telephone: POPESGROVE 2877.8

GEOLITE


non-metallic gears and pinions offer you the following advantages:—

Silence	33½ per cent. higher loads.
Shock absorption.	Uniform strength of tooth.
Strength.	Longer life.
Resistance to acids and heat.	Weight reduction.
Resilience.	Reduced face width.
Water and vermin proof.	Economy in cost.

Write for particulars of our GEOLITE Gears and Blanks

MacECHERN & COMPANY LIMITED

High Street, Chislehurst, Kent - - - (IMPerial 1103)



WEBLEY & SCOTT can
 make it for you...
and make it right

Plant includes—

Capstans, Automatics, Milling,
 Drilling, Profiling, Grinding,
 Deep hole drilling, Broaching,
 Heat Treatment, Brazing,
 Metal Colouring, Spraying,
 Phosphate Treatment, Assembly

MAY WE QUOTE FOR YOUR REQUIREMENTS

WEBLEY & SCOTT LTD.

WEAMAN ST., BIRMINGHAM, 4

EST. 1790

CASTINGS**ECLIPSE FOUNDRY**

& ENGINEERING CO. (DUDLEY) LTD.
 SEDGLEY ROAD WEST,
 TIPTON • STAFFS.

GREY IRON ALUMINIUM NON-FERROUS MAZAK
 Jobbing Cast- Sand & Die Gunmetals Pressure
 ing up to one Castings Phosphor- Castings
 ton Bronze

Repetition Machine
 Woulded Work


**RACKS
PINIONS**

CUT FROM 4 D.P. TO 50 D.P.

EAGLE MILLING Co. Ltd.

114-116, Lancefield Street, LONDON, W.18

Telephone LADBroke 0725 and 1294

**GENERAL ENG'G.
SERVICES**

Immediate Capacity Available,
 castings, non-ferrous, die, shell moulded,
 sand, etc. Also machining and stove-enamel-
 ling—**MILLS ENGINEERING PRODUCTS,**
 LTD., BARNET. Phone: Barnet 6741.

Centre Lathe Turning Up to
 74in. centres by 48in. b.c. Tool, Prototype
 and small batch work. Modern plant. A.I.D.
 approved.—**WARD ELECTRIC CO. (NOR-**
WOOD), LTD., 44, Chapel Road, W. Norwood,
 S.E.27. GIPsey Hill 1620.

PROTOTYPE & PRODUCTION

**ELECTRONIC WIRING, COIL WINDING,
 INSTRUMENTATION & TESTING**
SETON CREAHE ENGINEERING LTD.,
 G. W. Trading Estate, Park Royal Road,
 N.W.10.

A.I.D. ELGAR 3356.7 A.R.B.

A.I.D. — **THE** — CUN 5195
HEAT TREATMENT
PEOPLE OF LONDON
G.R.M. SERVICES LIMITED, PADDINGTON, W.9.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

REPAIRS By WELDING

BROKEN MACHINE TOOL PARTS
& DAMAGED PLANT IN ALLOY STEELS,
CAST IRON & NON-FERROUS METALS
SPECIALLY REPAIRED BY WELDING

ESTABLISHED OVER 40 YEARS

THE BLAKER MOTOR WELDING CO. LTD.

Welding Engineers

BUKES RD., PARK ROYAL, LONDON, W.3.
Phone: ACORN 4811. Grams: Belsford. Ebus London

**PROTOTYPES & SPECIAL
PURPOSE MACHINES**
REPAIRS & SALVAGE BY DEPOSITION
MACHINING, FORGING & FABRICATING
GEORGE MILLS (ENGINEERS) LTD.
BECKENHAM, KENT. TEL.: SYDENHAM 5255

Capacity Available for Proto-
types, design proving and component
machining in small, medium and large batches
in all materials including stainless and synthetic
products. We are used to precision limits and
delivery promises are a "must" at, of course,
competitive prices. A.I.D., A.R.B.
HUNTLEY & SPARKS, LTD., Deburgh
Road, London, S.W.18. Liberty 2446.

IDEAL
HARDENING CO., LTD.
DAVIS ROAD, CHESSINGTON, SURREY

**HEAT TREATMENT
SPECIALISTS
HARDENING OF
EVERY DESCRIPTION
AND SANDBLASTING**
Tel.: ELMBRIDGE 6556-4567

**GAUGES (Not Thread) —JIGS—FIXTURES, etc.
EXPERIMENTAL & PROTOTYPE WORK, A.I.D. Apd.**

NOVOGAGE LTD.

(For quality and precision)

JIG-BORING JIG-GRINDING, TOOL ROOM MACHINING

81, Bridge Road, (Nr. HAMPTON COURT STN.)
Tel.: MOLESEY 2763 & 4162 East Molesey, Surrey

CROYDON TOOL

AND CASE HARDENING SPECIALISTS

EXPERTS IN ALL HEAT TREATMENT OF METALS

CYANIDE HARDENING · ANNEALING · SHOT BLASTING

KEEN PRICES · WE COLLECT AND DELIVER

UNION ROAD, WEST CROYDON. PHONE: THORNTON HEATH 5223

**Induction hardening
and brazing, etc.** We collect
and deliver
Shot blasting.

PRECISION HEATING LTD.
142A Canbury Park Road, Kingston-on-Thames
Surrey. Phone: KINGSTON 1468

WOOD & METAL
PATTERNS

HAND MACHINE OR SHELL MOLDING
Keen Quotations Good Delivery

B. LEVY & Co. (Patterns) Ltd.
1-5 OSBERT ST., LONDON, S.W.1.
Telephone: VICTORIA 1073 & 7496.

**IMMEDIATE CAPACITY
AVAILABLE**

Capstan Work up to 1½ in. Bar
and 6 in. Chucking
Milling, Drilling, Grinding
Boring and Assembly Work
Also Hardening for the Trade

A.I.D. and A.R.B. approved

**B. TOONE
(NOTTINGHAM) LTD
NEWDIGATE ST.
NOTTINGHAM**

Tel.: 76661-2-3

ABBAY HEAT TREATMENTS LTD.
PLAZA WORKS, HIGH STREET, MERTON, S.W.19
FOR ALL TYPES OF HEAT TREATMENT.
WE COLLECT - WE DELIVER
TELEPHONE: CHERRYWOOD 2291

When answering advertisements kindly mention MACHINERY.

**STAINLESS STEEL
SPECIALISTS**

Fabrication, welding and X-ray
inspection, pressings and machined
parts.

**THE TAYLOR RUSTLESS
FITTINGS COMPANY, LIMITED**

Ring Road,

Lower Wortley,

Leeds, 12

Luton Engineering Pattern Co.
are prepared to undertake the manufacture
of all classes of wood and metal patterns and
accuracy and prompt delivery guaranteed.—
Send your enquiries to 80a, Princes Street,
Luton. 'Phone 961.

•• **MACHINING** ••

AUTO TURNED PARTS

FINE TOLERANCES, MAX. DIA. 1½ in.
INDEX SS & GRIDLEY MULTI AUTOS
THREAD CHASING MANUFACTURERS
ROLLER BOX TOOL HOLDERS

BENTON ENGINEERING CO. LTD.
Tonbridge Road, Harold Hill, Essex
Ingravehouse 4213

Multi-spindle and Single-spindle

Auto Turning up to 2 in. bar capacity,
capstan turning from the bar up to 2½ in. dia.,
chuck work up to 1½ in. dia., thread milling,
milling, shaping, drilling, etc., capacity available.
Any tolerance and quantity. Satisfaction
absolutely guaranteed.—UNICORN PRO-
DUCTS, Ltd., 119-121, Stanstead Road, Forest
Hill, S.E.25. 'Phone: FOREST Hill 7888 (3 lines).

Auto Screw Products, Ltd.,

Castle Works, Tipton Road, Dudley.
Tel.: Dudley 5103-4. Capacity available for
Automatic screw machine work, capstan milling,
drilling and presswork. Repetition products
for all industries made to customers' specifica-
tions in any quantity. Nuts, bolts, screws,
general turning, tool design and manufacture.

CAM CUTTING & track grinding

For
CAM FOLLOWERS
please write for
ZEDROL
leaflet

z e p h y r

ENGINEERS LIMITED

Telephone: Euston 7624/5

Grams: Camospec Phone London

24-32 EUSTON BUILDINGS, GOWER STREET, LONDON N.W.1

Precision



*Needle Rollers
Rollers & Pins*

The following can be delivered from Stock:—
Herbert 2in., 1½in., 1in., ½in. and ¼in. Chipstream Roller Assembly.
Ward 2in., 1½in., 1in. and ½in. Brown & Ward Auto, Brown & Sharpe OOG, OG, 2G Taylor, Hilco, B.S.A., Gridley, Cleveland, Cone, Index, Wickman, Ackworthie, Atlas, Warner & Swasey Needle Roller Assemblies.
Cam, Indexing, Turret Rollers, supplied to samples or drawings, 10 to 14 days.

Your Auto & Machine Shop Superintendent will be interested in this . . .

We specialise in the manufacture of needle rollers and rollers and pins for all types of box tools as listed in column on right. Made from highest quality tool steel, bores are lapped to 0.0003in., pins to 0.0002in.

Price List M 19 on request.


L. & T. I. BROCK & CO. LTD.
Stephen Street, Coventry

PRECISION
ENGINEERS
Tel.: 63534.

As supplied to
**ROLLS ROYCE
LTD.
DERBY**

CAPACITY FOR CENTRELESS GRINDING...

0.1in UP TO 3.50in. DIA.
TO PRECISION LIMITS
ON 'CINCINNATI' AND
OTHER WELL KNOWN
MAKES OF MACHINES



ALLEYNE FOSTER ENG CO LTD

ESTABLISHED IN 1924

59 South St., Epsom, Surrey, Epsom 2190

FOR THREAD MILLING

CONSULT

BROWN'S ENGINEERING WORKS,
Dudden Hill Lane, N.W.10.

'Phone: GLAdstone 4921

A. I. D.

A. R. B. APPROVED
CAPACITY AVAILABLE

Warwick
NORMAN
England

- MILLING
- CAPSTAN
- GRINDING
- CENTRE LATHE
- CRIDAN THREADING
- SHAPING
- DRILLING
- PROFILING

CLOSE LIMITS. PROMPT DELIVERIES

NORMAN ENGINEERING CO. LTD., WARWICK



T. J. HARRINGTON & SON LTD
AUTO. PRODUCTION MULTI & SINGLE SPINDLE
TRADING ESTATE · MOLESLEY RD · WALTON-ON-THAMES
SURREY

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

PRECISION TURNED PARTSA.I.D., A.R.B., C.I.A. & I.F.V., APPROVED
AUTO AND CAPSTAN QUANTITIES

Send your specifications to:

**AYLESBURY TURNED PARTS
(True Screws) LIMITED**Britannia St., Aylesbury, Bucks.
Tel.: Aylesbury 2424 (3 lines)A.I.D. & A.R.B.
APPROVEDTELEPHONE:
CRAWLEY 25211/8**The Alka Company**

(Proprietors: Wileanders (Great Britain) Ltd.)

PRECISION MACHINING CAPACITY

- COMBINATION LATHES AND CAPSTANS
- CENTRE LATHE TURNING UP TO 36in. SWING
- UNIVERSAL, HORIZONTAL, VERTICAL MILLING
- GRINDING, DRILLING, HEAT TREATMENT
- JIG AND FIXTURES
- SPECIAL PURPOSE MACHINES AND ASSEMBLIES UP TO 4 tons.

MAXWELL WAY, GATWICK RD., CRAWLEY, SUSSEX

E. R. LATTIMER LTD.

SHAKESPEARE STREET, SOUTHPORT

'Phone: Southport 4245

Offer a very comprehensive service for Small to Medium Component and Sub-Assembly Manufacture incorporating:

- Capstan, Auto & Centre Lathe Turning
- Horizontal, Vertical & Profile Milling
- Centreless, Surface & Internal Grinding
- Lapping and Honing
- Drilling, Tapping & 2nd Operation Lathe Work
- Mazak Pressure Die Casting up to 6 oz. weight.

Our new and extended Toolroom is now in operation with full facilities for TOOL DESIGN AND MANUFACTURE.

We are fully approved by A.I.D. and A.R.B.

**FINE LIMIT GRINDING
MILLING, TURNING, DRILLING.
Complete Service Offered.****SETON CREGHE ENGINEERING LTD.,**
Trading Estate, Park Royal Road, N.W.10
A.I.D. ELGar 3356/7 A.R.B.**AUTOPRODUCTIONS LTD.**Automatics: Single Spindle
Index "18" "24" "36" "52" "8.42"
Multi Spindle: 1in. and 1½in. WickmanCapstan
Drilling
MillingCentreless Grinding
Polygon Turning
Chemical Blacking**CAPACITY AVAILABLE**53, Green St. Sunbury-on-Thames
Phone 2499**Immediate Capacity Available,**
on single spindle Automatics up to 1½in.—
JAN PRECISION SCREWS, 33, Woodthorpe
Road, Ashford, Middlesex. 'Phone: Ashford 4524**PRECISION & GENERAL
MACHINING**including
Thread Milling • Radial Drilling
Metal SpinningA.I.D. and I.F.V. Approved. Enquiries invited.
Member of the Metropole Group of Companies**Surplice & Tozer Eng. Co., Ltd.**
Acre Works, Windsor
Windsor 1657 & 1844**WE WOULD WELCOME YOUR ENQUIRIES FOR:—**

- MILLING—Horizontal & Vertical.
- CENTRE LATHES to 38in. Dia.
- CAPSTANS to 2½in. Dia.
- PLANING TO 6ft. x 3ft. x 3ft.
- BORING—Horizontal & Vertical.
- Cylindrical Grinding to 20in. Dia. x 84in.
- Surface Grinding to 24in. x 8in.
- Drilling and Thread Tapping.

A.I.D. APPROVED

BOWES ROAD ENGINEERING CO. LTD.

BOWES ROAD, NEW SOUTHGATE, N.11. 'Phone BOW 2284/5/6

Automatic and CapstanCapacity Available up to 2in. dia.—
WILLIS ENGINEERING, 65A, High Street,
Hampton Hill, Middlesex. Molesey 4273.**Automatic Turned Parts, Press**

Work, Press Tool Making, Capstan and Centre Lathes, Milling, Drilling, Thread Milling. Capacity available.—PARKER ENGINEERING (KINGSTON), LTD., 200-202, Cambridge Road, Kingston-on-Thames. KIN. 5501.

Planing Capacity, Heavy or LightTurning up to 5ft. diameter.
Special machines to customers' design.
F. ATKINSON & SONS, London, LTD.,
65, King's Cross Road, W.C.1. Terminus 4050.**Immediate Capacity Turning,**

capstans, milling, drilling, die and tool making.—MILLS ENGINEERING PRODUCTS, LTD., Barnet. Tel.: BARNET 6744.

Metal Spinnings. Immediate

capacity for metal spinnings and sheet metal work. A.I.D. approved.—HIGHBURY METAL SPINNING CO. (1955), LTD., 36, Highbury Place, N.5. CANbury 2906.

Horizontal Production Milling

for the trade. Slots, flats, squares, etc., of all descriptions milled on latest plant. Keen prices for long runs, satisfaction guaranteed.—UNICORN PRODUCTS, LTD., 110-131, Stanstead Road, Forest Hill, London, S.E.23. Telephone: Forest Hill 7688 (3 lines).

ROSSER & RUSSELL LTD.Queen's Wharf, Hammersmith,
LONDON, W.4.

Telephone: RIVerside 4161.

**GENERAL ENGINEERS
AND
MANUFACTURERS OF
SPECIAL MACHINERY
TO
CUSTOMERS DESIGN****Automatic Work Up to 1½ in.**Immediate capacity available—
TRUE ENGINEERS, LTD.,
Wharf Lane, Bourne End, Bucks. 'Phone 1316.**Capstan and Turret Lathe**Capacity available up to 4½in. diameter bar and 22in. diameter chucking. Castings and Forgings a speciality. Milling, drilling and centre lathe turning. High class work with prompt delivery. Enquiries invited to—
WHITWAM & ELEY,
22/24, Stafford Road, W.3. Acorn 8364.**Automatic Capacity Available**

on Index single spindle autos, up to 2in. dia.—ARTHURS ENGINEERING, Hershham Trading Estate, Molesey Road, Hershham, Surrey. 'Phone: Walton-on-Thames 5119.

Capstan Capacity Immediatelyavailable, 8 B.A.—1½in. Steel or Brass.
Large stocks of raw materials—
SACRON, LTD.,
7, Chiswick High Road, W.4. Tel. CHiswick 3595.**Capstan Capacity Immediately**

available, 10 B.A. to 1½ diameter in R.M.S. Brass, High Tensile, Stainless, etc. All sizes of material actually in stock.—CHISWICK ENGINEERING, LTD., Pluckington Place, King Street, Southall, Middx. Tel.: Southall 2247.

High Precision Grinding ofTungsten Carbide and Steel Tools.
Accurate profile grinding and progression tools a speciality.—S. T. LTD., 22-26, Upper Mulgrave Road, Cheam, Surrey. 'Phone: Vigilant 0074/5.**SHEARING, BENDING,
ROLLING, STAMPING,**up to ½in. plate. Rotary coil slitting and allied services. Sheets and plate in stock.
SHELMERDINE & MULLEY LTD.
EDGWARE ROAD, CRICKLEWOOD,
N.W.2.

GLAdstone 7677-8-9.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

CAM CUTTING *by* MANIFOLD

ACCURATE CAM MILLING OF FINEST QUALITY



is being produced on our special-purpose machines which can cut up to 34in. diameter and to any form you may require—and—just to be different—3 dimensional cams too!



MANIFOLD MACHINERY

COMPANY LIMITED

SUFFOLK WORKS

660 GREAT CAMBRIDGE ROAD
ENFIELD · MIDDLESEX

ENFIELD S353



ACW/GH

**PLASTIC
MOULDINGS**

FREDERICK W. EVANS LTD.
Plastic Works, Long Acre, Birmingham 7
Tel.: East 3071-2-3

THE AVENUE ENGINEERING CO

GENERAL ENGINEERING CAPACITY

7, Warner Yard, Warner Street,
Mount Pleasant, Clerkenwell, E.C.1

Phone: TERminus 2209.

PRECISION TURNED COMPONENTS

TOOLS LIGHT PRESS WORK
JIGS SHORT RUNS
FIXTURES RELIABLE DELIVERIES
RADEK ENGINEERING
121, South Street, Braintree, Essex

Cylindrical and Internal Grind-

ing, max. swing 8in., capacity available.
Close limits. Modern plant. A.I.D. approved.—
WARD ELECTRIC CO. (NORWOOD), LTD.,
44, Chapel Road, West Norwood, S.E.27.
Gipsy Hill 1020.

Immediate Capstan Capacity

available up to 2 1/2in. dia. Also centre
lathe, milling, drilling, etc. Small well equipped
workshop offers personal attention and prompt
delivery.—C. D. F. MACHINE PRODUCTS,
26, Park Street, Hatfield Herts. Hatfield 2159.

Two Herbert 9B-30's (New).

Capacity immediately available. Also
Capstans, Centre Lathe, Milling, Grinding,
Threading, Assembly, etc. A.I.D. approved.
First class quality our speciality.—SPANDOR
ENGINEERING, LTD., 29, Violet Road,
Bow, E.S. Phone: EAST 4567.

Thread Milling for the Trade

up to 6in. O.D. and 5in. I.D. Any thread,
any quantity. Keen prices for long runs.
Satisfaction guaranteed.

UNICORN PRODUCTS LTD.

119-121, Stanstead Road, Forest Hill, London,
S.E.23. Telephone: Forest Hill 7688 (3 lines).

CAPACITY AVAILABLE

Nos. 3A, 7 and 10 WARDS; 36in.
Vertical BULLARDS MILLING
MACHINES and CENTRE LATHES

TASKERS OF ANDOVER

(1932) LTD.

WATERLOO IRON WORKS

ANDOVER HANTS.

TELEPHONE: ANDOVER 2312

Auto Capacity + Hydraulic Copying

J. M. HARGREAVE & CO. LTD.

Central Avenue, West Molesey, Surrey. Tel: Molesey 3180/2707

Our Torex
64 Type autos
include
Hydraulic
Copying, and
can produce
chucking
components to
close limits

Chucking 1" to
Swing 6" in
chuck

CENTRELESS GRINDING

ALL TYPES OF FORM, THROUGH AND PLUNGE

A.I.D. & A.R.B.
APPROVED

BAR GRINDING

Tel.: POP
6157 & 7088

1/2in. TO 5in. DIA. UP TO 15ft. LONG

IMMEDIATE CAPACITY ON CAPSTAN, MILLING

CENTRE LATHES, AUTO AND ALL TYPES OF GRINDING

REDCAR ENGINEERING CO. LTD.,

HOLLY ROAD WORKS, TWICKENHAM, MIDDLESEX

When answering advertisements kindly mention MACHINERY.

R2

LET US BE YOUR MACHINE SHOP

WE INVITE YOUR ENQUIRIES FOR:

Capstan, turret and centre lathe work: milling - all types - internal, surface and universal grinding, G.S.P. jig-boring, drilling, shaping, honing, etc. also for tool work. Ours is a complete machineshop to meet your every need.

A.I.D. and A.R.B. Approved



MARSDEN & SHIERS LTD. DAVIS ROAD · CHESSINGTON · SURREY · Phone ELMBRIDGE 5333-4

ASHTED

● CENTRELESS GRINDING
for ● EXTERNAL GRINDING
● THREAD MILLING
A.I.D. & A.R.B. APPROVED

ENGINEERING CO. LTD.

Grove Road, Ashted, Surrey

Phone: ASHTED 802.

Capstan and Centre Lathe Work
Milling · Drilling · Shaping · Slotting
ESTABLISHED 1920.

SWISSOMATIC LTD.

Green Street, Enfield, Middlesex.

Howard 2301/2996

**PRECISION TURNED PARTS
UP TO 1" DIA.**

AID & ARB APPROVED

PLOUGH GRINDING

24 hr. Service

High Speed Service Tool Co. Ltd.
Maple Road, Surbiton, Surrey.
Elmbridge 1135-6-7.

Capstan Capacity Available,
1in. to 4 1/2in. Stainless High Tensile B.M.S.
etc., no quantity too small or too large, stocks
all materials.—ACME WORKS.
Pluckington Place, King Street,
Southall, Middx. Tel.: Southall 2247.

CAPACITY AVAILABLE

High Precision Components
A.I.D. and A.R.B.
approved.

Capstans up to 2in.
Centre Lathes to 7 1/2in.
Milling and Tooling.

W. G. HEATH AND COMPANY, LTD.
5 Princess Square, Plymouth

CHUCKING AUTOS AND BAR AUTOS

Capacity available for Castings, Forgings, Billets, etc., up to 12in. diameter on Herbert 3A and Herbert Junior Chucking Automatics. Also Bar Autos and Capstans. Good deliveries.

STUART HEYWOOD ENGINEERING
46, Wendover Road, Staines, Middlesex
Telephone: Staines 5151

**LEYTON
ENG CO LTD
EST: 1929
BEEHCROFT ROAD**

Tel: WAN 5540 & 3343

Telegrams: LEQUIP LONDON E18
Cables: LEQUIP LONDON

Aircraft and engine
servicing tools
Machine tooling
equipment
Precision work
Machine parts
Turning, milling,
hardening, grinding
Complete machine-
unit assemblies

**SOUTH WOODFORD
LONDON E.18**

PLANING 12ft. 0in.

HORIZONTAL BORING	VERTICAL BORING	RADIAL DRILLING	CENTRE LATHES
COMBINATION TURRET LATHES	HORIZONTAL MILLING	VERTICAL MILLING	
GRINDING	DRILLING	WELDING	PROFILING
			HONING

D. A. GUNN (ENGINEERING) LTD

32, Park Road North, W.3 Tel.: ACOrn 4841/4

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

• PRESS WORK •

Pressings in All Metals Up to 60 tons. Press tools manufactured in our own toolroom. Light assemblies, Domestic Electrical and Mechanical. All finishes. A.I.D. and A.R.B. approved. Advice and estimates given free.—Inquiries to:

METAL COMPONENTS, LTD.,
Dolphin Road, Shoreham-by-Sea, Sussex.
Phone: Shoreham-by-Sea 2224/5.

Presswork Up to 40 Tons, Circular and surface grinding on latest J & S machines. Tools designed and made for the trade, or your article produced throughout in our works. A.I.D. approved. Enquiries welcomed.—WEMBLEY TOOL CO., LTD., 2, Bridge Road, Willesden, N.W.10. WIL. 6567/8.

SUB-MINIATURE PRESSINGS
and multi-stage precision press work
in all materials

PROMPT DELIVERIES

G. A. PRECISION PRODUCTS LTD
No. 2 Factory, Darkes Lane
Potters Bar, Middlesex
Potters Bar 6895

PRESSWORK
SMALL AND MEDIUM
(Including Deep Drawing)

We can provide:

MATERIAL · TOOLING · METHOD
PRODUCTION & FINISHING

Free Delivery Greater London Area
A.I.D. Approved.

**H. G. SANDERS & SON
LIMITED**

Gordon Road, Southall, Middlesex
Telephone: SOUTHALL 5611

Presswork

Firm with modern plant has capacity for Presswork up to 150 tons.

Enquiries invited to:—

VULCAN MANUFACTURING
(Wolverhampton) Ltd.
New Griffin Works - Wolverhampton

TREVENA & GLOVER LTD
Specialists in Intricate Presswork

809-312 ICKNIELD STREET
BIRMINGHAM 18.

Quality contacts for the Electrical Industry.

Small and Medium Presswork in
all ferrous and non-ferrous metals.

Telephone: B'ham Northern 0258.

ON AIR MINISTRY LIST
CONTRACTORS TO THE G.P.O.

**A.I.D., C.I.A., A.R.B.,
APPROVED**

**WELDING &
FABRICATIONS**

PRESSINGS
PRESS CAPACITY UP TO 1000 TONS
• ALL MATERIALS •

POLARCOLD LTD.,
CONGLETON · CHESHIRE TEL. 2401/3

Presswork Up to 50 Tons, In-
cluding deep drawing. Long or short runs.
Customers' tools and materials acceptable.
Tooling and designing available.—BIRCH &
JACQUES (TOOLMAKING) LTD., Hensham
Trading Estate, Walton-on-Thames. Telephone:
Walton-on-Thames 5379.

Metal Pressings

TO ANY TOLERANCE
SHAPE OR QUANTITY

SERVICE and PRECISION
at COMPETITIVE PRICES

ECONOMIC STAMPINGS LTD.
DISRAELI STREET, LEICESTER · TELEPHONE 32233

MEMBER OF THE BENTLEY GROUP

Pressings and Stampings, Ltd.,
Eccleston Road, West Ealing, W.13.
Presswork up to 150 tons. Double action deep-
drawing—guillotine sft. by 10 S.W.G. Spot
welding—Assembly. Tool making and electro-
plating.—Phone: Ealing 3667-8.

• TOOLMAKING •

Capacity Available for Moulds,
press tools, jigs and fixtures, general
machining and light assemblies. High-class
work with prompt delivery.—Enquiries to
PERFECTOOLS, 131, Croydon Road, Caterham.
Telephone: Caterham 3042.

**CENTRAL ENGINEERS
(HERNE HILL) LTD.**

• JIGS—FIXTURES
• PRESS TOOLS—GAUGES
• PRECISION GRINDING

Enquiries Invited

Forsyth Rd., Sheerwater Estate, Woking,
Surrey. Phone: Woking 5192-5193

ESTD
1889

R. STEPHENS & SON LTD
PRESS TOOLS · JIGS
FIXTURES · MOULDS
GAUGES · DESIGNS
115 CHURCH ROAD
UPPER NORWOOD
LONDON S.E.12
PHONE
LIVINGSTONE
2265-6

JIG GRINDING CAPACITY
Available on new Hauser Machine.
STEEL CRAFT JIG & TOOL CO.
Horton Bridge Road, West Drayton.
Phone: West Drayton 2580

PRECISION PRESS WORK

- Double action
deep drawing
- Double roll feeds
- ★ Own tool room

HOLLY ENGINEERING (Drayton) LTD
Colham Avenue, Yiewsley, Middlesex
Telephone: West Drayton 2870

JIG BORING

ON SIP JIG BORERS
EDMONTON TOOL & ENG. CO. LTD
141, HERTFORD ROAD, EDMONTON N.9
TELEPHONE: EDMONTON 4412/3
SPURS, SPIRALS, BEVELS, WORMS
& WORMWHEELS

GEAR CUTTING

When answering advertisements kindly mention MACHINERY.



THE FIRM WITH HALF A DOZEN JIG BORERS for PRESS TOOLS etc.

HIGH SPEED SERVICE TOOL CO. LTD.
Maple Road, Surbiton, Surrey. Elmbridge 1135-6-7
STUDER PROFILE GRINDING A SPECIALITY.

MacDowall

JIGS, FIXTURES
PRESS TOOLS &
GAUGES
PRECISION ENGINEERS
SPECIAL MACHINERY

MACDOWALL EQUIPMENT COMPANY LIMITED
NORTH STREET ROMFORD ESSEX

ROMFORD 61981

Capacity Available, Press Tools,
Jigs, Fixtures, Production of Metal
Pressings, Prototypes and Jobbing. Light
Assemblies.

ELLIOTT & WEST.
487, Liverpool Road, N.7. Phone: NORTH 2366.

Press Tools, Press Work, Jigs

Fixtures, Capstan and Auto. Turning.
Special H.S. Cutters. Components manufactured
and assembled to spec.—L. PERSON & SON,
83, Shaftesbury Street, N.1. CLE 7139.

COVENTRY GRINDERS LIMITED

A.I.D. Approved

Phone: 60736, 60174

PRECISION GROUND COPYING LATHE
TEMPLATES OPTICAL FORM GROUND
UP TO 48 ins. LONG

Send us your Enquiries for Gauges, Form, Depth, Gap,
Plug, Ring, Splines, Taper, Receiver, Circular and Flat
Form Tools. Good deliveries.

TOOLROOM AND PROFILE
GRINDING CAPACITY
AVAILABLE
FORM CUTTERS A SPECIALITY
PROTOTYPE WORK
GOOD DELIVERIES:
FIRST CLASS WORK

S. E. WAKELIN & CO. LTD.,
204, Birchfield Road,
Birmingham, 19.

EST. 1893 Phone Nor. 8201/3

A.I.D. Member of the Gauge & Toolmakers Association

- MOULDS Compression and Injection Plastic
- MOULDS Pressure Diecasting
- MOULDS Rubber and Gravity
- JIG & FIXTURES
- PRESS TOOLS
- PRESS WORK up to 25 tons
- AUTOMATIC & CAPSTAN TURNED PARTS

TO BE PRECISE IT'S

Camdentools

21-22, HONYWOOD ROAD,
BASILDON, ESSEX.
Phone: Basildon 20506/7.

Press Tools


JIGS
FIXTURES
GAUGES

MITCHAM JIG & PRESS TOOL Co. Ltd.
BENEDICT RD., MITCHAM, SURREY
Telephone: Mitcham 3635

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

**TO GET
OVER THAT
TOOLING
PROBLEM**



call in **SMITH & CRABB**
TOOLMAKERS & PRECISION ENGINEERS
53 KING STREET, BRIGHTON 1, SUSSEX. Tel. B'TON 26220



**Send Us
Your
Enquiries**

'PHONE:
LIBERTY 5203

THE KEMWORTHY JIG & PRESS TOOL COMPANY LTD.
HIGH STREET, COLLIER'S WOOD, LONDON, S.W.1

KEMP

PRECISION TOOLING LTD

**37 JUNCTION ROAD,
CROYDON, SURREY**

TELEPHONE: CROYDON 5658

PRESS TOOLS, JIGS
GAUGES, MOULDS
SPECIAL PURPOSE
MACHINES
PROFILE GRINDING
PRECISION
COMPONENT
PRODUCTION
JIG BORING

**HIGH QUALITY
PRESS TOOLS**

**MULTI-OPERATION TOOL
• SPECIALISTS •
STAMPINGS IN ALL MATERIALS
FIXTURES - JIGS - MOULDS
SPECIAL PURPOSE MACHINES**

W.T. Atkin (TOT) Ltd.

178 ST. ANN'S ROAD, LONDON N.15

Telephone: STAMFORD HILL 6684/7

PRECONOMY CO LTD

PRECISION

Moulds
and
Press
tools



Jigs
and
Fixtures

ECONOMY

Eastfield Side, Sutton-in-Ashfield, Notts

Press Tools, Jigs and Fixtures,
light Pressings up to 10 tons.—SPENCE
TOOLS, LTD., 361a, Oxford Avenue, Trading
Estate, Slough. Tel.: Slough 22394.

PRESS TOOLS

GROSVENOR WKS. 253, SUSSEX WAY, HOLLOWAY, N.19.

Phone: ARCHWAY 1033/9

METAL
STAMPING,
JIG BORING,
PRODUCTION HEAT
TREATMENT OF STEEL.

JIGS & FIXTURES

Kellering and Profile Milling in
all Metals. Send us your Die Blocks to
Copy from wood or plaster masters. Up to
5ft. by 3ft. maximum size. We are Die Copiers
to the Trade.
ARMYTAGH BROS. (KNOTTINGLEY)
Jrtd., The Foundry, Knottingley, Yorkshire.
Tel.: Knottingley 2026

DORMER & WADSWORTH


PLASTIC
MOULDS
PRESS TOOLS
JIGS
FIXTURES, ETC.

31-33
BICKERSTETH RD.,
MITCHAM RD.,
TOOTING,
LONDON, S.W.17

TELEPHONE: BALHAM 1006 (2 LINES)

When answering advertisements kindly mention **MACHINERY**.

SPECIALITIES



KENNAMETAL

The Super Grade
Carbide of World
Wide Reputation

GEORGE H. ALEXANDER
MACHINERY LTD.

Guns Lane, West Bromwich, Staffs.
Telephone: West Bromwich 1931 (5 lines)
Telegrams: "Viking, West Bromwich"



**FLEXIBLE
METALLIC CONDUIT**
and solderless couplings
For protecting cables leading to
motors, switchboards,
starters, etc.
All sizes from 1/4 in. to 3 in.
THE DONOVAN ELECTRICAL CO. LTD.
(Wholesaling Division)
GRANVILLE STREET · BIRMINGHAM 1

"RUBURY"
ROTARY COMPRESSORS & EXHAUSTERS
Manufactured by
THE HAMMOND ENG. CO., LTD.,
Chase Side, Enfield, Middx.
Telephone: ENF. 1323 (4 lines)




**'SUPER'
PIPE UNIONS**

with Patent Conical Joint.
Can be used on Super-
heated steam.

WALTER SLINGSBY & CO., LTD.
WASK WORKS KEIGHLEY

Tungsten Carbide Tool
Manufacturers of standard and special form
tools in high speed steel and tungsten Carbide.
Our range includes reamers, cutters, workrest
blades and wear-resistant parts.
Carbide supplied to customers' specification
and express service given for emergency tooling.

DIAGRIT GRINDING CO., LTD.,
Marden, Kent.
Phone: Marden 362.



**AN IMPROVED
PLATE WORKING MACHINE**

This illustration shows the improved
"Nibbler" Universal Sheet Steel and
Plate Working Machine.
It will perform the following operations:—
Straight Cutting. Circle Cutting.
Beading. Folding or Joggling.
Figure Cutting. Planishing.
Louver Cutting. Nibbling.
Slot Cutting. Flanging.
Made in three sizes.
We will gladly quote you times on your own work.

**GEORGE H. ALEXANDER
MACHINERY LTD.**

82-84 Colleshill Street, Birmingham, 4, England

**BRITISH SPRINGS
& WASHERS**



WILLIAM FINUCANE
(SPRINGS & PRESSINGS)
LTD. A.I.D. A.R.B.

ELGAR 3757/8/9

16A HILLSIDE,
STONEBRIDGE PARK,
LONDON, N.W.16.

**MACHINE ENGRAVED
RULES**

WHITTAM & CO.

Specialists in

Machine Rules, Scales, Circular
Dividing, Standards, and all
types of Steel Rules, for the
machine tool trades.

Established 1860

Telephone: Pendleton 3117
Claremont Works, Salford, 6.



**Universal
Ball Bearing Co.**
111-115 Hammersmith
Grove, London, W.6
**FACTORS
MANUFACTURERS
AND REPAIRERS**
Phone: Riverside 3262-3-4. Grams: "Universal Bearing
Hammersmith"

TIME RECORDERS — Sales —
Rental Service. Tel. HOP 2239.
**TIME RECORDER SUPPLY &
MAINTENANCE CO., LTD.**
157/59, Borough High Street, London, S.E.1.

Machine Engraved Feed Dials,
Scales, Nameplates, Labels, etc., in Metal
and Plastics. — Quick Delivery. — O. H. KAMPP
& CO., Tanvard Works, Beaminster, Dorset.
Phone: Beaminster 440.

The "Coxeter" Revolving
Centre, from 76s. All sizes from stock. —
REVOLVING CENTRES, LTD., Oxford.



BRAND NEW BALL & ROLLER BEARINGS
OVER 4,000,000 IN STOCK IN MORE THAN 4,000 TYPES
BRITAIN'S LARGEST STOCKS
STOCK LIST AVAILABLE
CLAUDE RYE BEARINGS 895-921 FULHAM RD., LONDON S.W.6
RENOVN 6174 (EXT. 24) TELEX 2-3453



When answering advertisements kindly mention MACHINERY.

MCCROSKY

(BRITISH MADE)

**INSERTED BLADE
MILLING CUTTERS**
Easy accurate setting with
unique Jack-Lock wedge
Sample cutter on request



Write for full details to Small Tools Department.

GEORGE H. ALEXANDER MACHINERY LTD.
82, 83, 84, COLESHILL STREET, BIRMINGHAM 4.

PHOTOGRAPHY

Miles & Kaye, Ltd., 102, South-
ampton Row, London, W.C.1. Holborn
6858. Specialists in commercial and industrial
photography for over 60 years. All branches of
photographic work undertaken.

Photographs by MACHINERY
set the standard in engineering publicity.
Our studio is one of the best equipped in the
country. Ideal for really good photographs of
tools, attachments and portable equipment.
Mobile units available for taking photographs
in black and white or in natural colour in your
own or your customers' works. Specimens of
work submitted on request.—Full particulars
from the **SERVICE MANAGER, MACHINERY
PUBLISHING COMPANY, LTD.,** National
House, West Street, Brighton, 1.

ANNOUNCEMENTS

BUSINESS OPPORTUNITIES

Sheffield Engineering Firm with
comprehensive engineering plant and
extensive experience in the design and production
of all types of machinery, including special
purpose plant, wishes to undertake the manu-
facture of complete or part assemblies, including
assembly line production. Own Drawing Office
and Pattern Shop. Technical Representatives
in all areas.—**BOX L771, MACHINERY, Clifton
House, Euston Road, N.W.1.**

For Patterns, Blocks, Jigs,
Repetition Work in Wood, "Jabroc,"
"Tufnel," etc. No job too small.—Send your
enquiries to P.M., 29, Sixth Avenue, Bristol, 7.

Capable Man with Manufactur-
ing and selling experience of specialised
engineering field requires capital to manufacture
and market product with vast potential. Partic-
ulars at interview.—**BOX V986, MACHINERY,
Clifton House, Euston Road, N.W.1.**

PACKING AND SHIPPING

R. & J. PARK, LTD., Dominion
Works, Chiswick, England. Export
packers, shippers and forwarding agents.
Specialists in packing heavy machinery.

WORK TO PLACE

Plastic Manufacturers Seek an
engineering firm who can do some of their
toolmaking efficiently at a very competitive
price, London area.—**BOX V1000, MACHINERY,
Clifton House, Euston Road, N.W.1.**

PATENTS—TRADE MARKS

Kings Patent Agency, Ltd.
T. R. KING, A.M.I.Mech.E.,
Registered Patent Agent,
146A, Queen Victoria Street, London, E.C.4.
City 6161. Booklet on Request.

BUSINESS FOR SALE

Light Engineering Business
for sale. 30 miles London. 8,000 sq. ft.
freehold factory; running contracts. Owner
retiring.—**BOX V999, MACHINERY, Clifton
House, Euston Road, N.W.1.**

MATERIALS FOR SALE

Surplus Mild Steel For Sale,
20G to 14G. Offcuts 20G to 14G. Cold,
reduced and Hot Rolled Strip Mill 6 by 3 by
22G. template.—**R. STEPHENS & SONS,
LTD., Bath Street, E.C.1. CLE. 1731/4.**

MATERIALS WANTED

Steel, Aluminium, Brass, Sheets
and Offcuts 10 to 24g. Small or large
quantities. Cash payments.—**DYAS & FOWLE
41, Loudoun Rd., N.W.8. MAIDA Vale 2711, 5477.**

BRITAIN'S BIGGEST BUYERS

WANT

NEW BALL & ROLLER BEARINGS

OF ALL TYPES & SIZES

CLAUDE RYE BEARINGS

895-921 FULHAM RD. LONDON, S.W.6
REOWN 6174 (EXT. 24) · TELEX 2-3453

PLANT WANTED

Machine Tools and Sheet Metal
Working Machinery, modern items of all
types required.—**CHARLES E. MATTHEWS
(MACHINE TOOLS), LTD., 34, Gladstone
Road, Croydon. (Thornton Heath 1785.)**

CENTAUR TOOL WORKS,
Birmingham, 18, pay best prices for good
modern secondhand Machine Tools by first-class
makers. Write or 'phone and our representative
will call. 'Phone: EDGBASTON 1118 and 1119.
'Grams: Capetan, Birmingham.

Wanted, Slideway Grinder,
Churchill VA or similar, 8ft. capacity or
larger.—**BOX V643, MACHINERY, Clifton House,
Euston Road, N.W.1**

WANTED
GOOD CLASS MACHINE
tools and sheet metal
machinery.

EDWIN MILLEN

70 Clerkenwell Road, London, E.C.1
'Phone: CLERKENWELL 6064

Surplus Machine Tools and
Sheet Metal plant of modern design wanted
by—**H. BELL (MACHINE TOOLS), LTD.,
Walter Street, Leeds, 4. Tel.: 63-7398.**

B.G. MACHINERY, LTD.,
Montgomery Street, Sparkbrook,
Birmingham, 11, will pay good prices for
Machine Tools of first-class make and in good
condition.—'Phone: VICTORIA 2351/9.

Wanted. Reasonably Modern
machine tools and sheet metal working
machinery. Best prices paid.—**W. FOREST
& CO., LTD.,** Industry Works, Sylvester Gardens,
Sheffield, 1. Sheffield 23314/5.

When answering advertisements kindly mention **MACHINERY.**

Classified Advertisements (PLANT WANTED, contd.)

WANTED GOOD MACHINE TOOLS

Offer your Surplus Tools to us. We pay a good price

M. WARD

(MACHINE TOOLS) LTD.
1, KILBURN HIGH ROAD,
LONDON, N.W.6

MAIDA VALE 1195-96
Telegrams: Emwarneer, Kil., London
One minute from Kilburn Park Station
Bakerloo Railway

2 us.

WANTED

ALL TYPES OF MODERN
MACHINE TOOLS

Please write or phone details to:
THE MIDLAND MACHINE TOOL CO.
BRADLEY, BILSTON, STAFFS.
Tel.: Bilston 41953

**A. LAWRENCE & CO.
(MACHINE TOOLS) LTD.**

will be pleased to purchase
your surplus Modern
Machine Tools either on a
cash or part exchange basis.
Ask our representative to
call and inspect.

Welsh Harp, Edgware Road,
London, N.W.2

Telephone: GLAdstone 0033

**SURPLUS MACHINE
TOOLS REQUIRED**

OFFER YOUR MACHINES TO

J. E. RAISTRICK LTD.

POYLE TRADING ESTATE
COLNBROOK, SLOUGH,
BUCKS.

TEL: COLNBROOK 421

Harry Kirk Will Purchase
modern quality machine tools for cash.
Whole plants or individual items.—Full details
to:—

HARRY KIRK ENGINEERING, LTD.,
Machine Tool Division,
Brandon Road Works,
Brandon Road, Coventry.
Telephone: Walsgrave-on-Sowe 2213/4.



WANTED!**USED MACHINE TOOLS**

We offer generous prices for your plant or
accept in part exchange for modern equipment

**E. H. JONES
(MACHINE TOOLS) LTD**

48, HIGH ST. EDGWARE, MIDDX
Telephone: EDGware 4488/9
BIRMINGHAM: MIDLAND 5393

Machine Tools, Power Presses
and Sheet Metal Machinery. Single
machines or complete plants purchased.
Immediate inspection.—**ALBERT EDWARDS**
(MACHINERY), LTD., 79/89, Pentonville Road,
London, N.1.

WILLIAM
URQUHART
Proprs: Exors.
M. & R. Urquhart
MODERN MACHINE TOOLS
of all types.
GOOD PRICES. Send details to
WM. URQUHART,
1923/27, Garratt Lane, London, S.W.17
Tel: BALHAM 8551

Secondhand Unit Construction

Face Plate Lathe, swing diameter 13ft. 0in.,
length of tool post bed 17ft. 0in. Approximate
horse-power 60.—**BOX V998, MACHINERY,**
Clifton House, Euston Road, N.W.1.

25 Ton Blanking Press, Variable
stroke, 400-440 volts.—**S.S. TOOL &
PRODUCTION CO., LTD.,** Croydon Road,
Beckenham, Kent. BEC. 1998.

*Wanted
urgently*

Late Type Machine Tools
Best Prices are offered for
latest types of Machine Tools.
Send us details of what you
have and our representative
will call to inspect.

J. B. MACHINE TOOL CO. LTD.
312 BRADFORD ST., BIRMINGHAM 5
Telephone: MIDland 4375

WE BUY
Good class
**MACHINE
TOOLS**

• We invite particulars of your surplus Machines
SOAG MACHINE TOOLS LTD.
7, JUXON ST., LAMBETH, LONDON, S.E.11
Phone: RELiance 7201
Grams: "Sotoolsag," London

Deckel or Similar 3-dimensional
Pantograph Machine wanted.—**BOX V952,**
MACHINERY, Clifton House, Euston Road,
N.W.1.

Wanted, Complete Third Slide
for 2G B. & S. Auto.—**BOX V995,**
MACHINERY, Clifton House, Euston Road,
N.W.1.

**HIGHEST PRICES
PAID FOR**

F. J. Edwards Ltd

**MACHINE TOOLS • PRESSES • PLATE & SHEET
METAL WORKING MACHINERY • TIN BOX
MAKING MACHINERY • WOODWORKING MACHINERY**

Outright purchase or in part exchange

EDWARDS HOUSE, 359-361, EUSTON RD., LONDON, N.W.1
Telephones: Euston 4681 (7 lines) 3771 (4 lines)
41, WATER STREET, BIRMINGHAM 3 Telephones: CENtral 7606/8

When answering advertisements kindly mention **MACHINERY.**

Classified Advertisements (PLANT WANTED, contd.)

WANTED.....**MODERN MACHINE
TOOLS OF ALL
TYPES**

Prompt inspection arranged
Write or 'phone:

NEWMAN INDUSTRIES LIMITED
YATE • BRISTOL

Telephone: CHIPPING SODBURY 3311

Branches:

London Birmingham Manchester Glasgow



**WE ARE KEEN BUYERS
OF GOOD MODERN
MACHINE TOOLS.**

**INSPECTION WILL BE
ARRANGED AT ONCE.**

M. C. LAYTON LTD.
96-98 VICTORIA STREET,
LONDON, S.W.1

Telephone: VICTORIA 7778/9.

**WANTED
MODERN MACHINE
TOOLS**

We pay cash for single machines
or complete plants

SEND US DETAILS
IMMEDIATE INSPECTION ARRANGED
**SOUTHERN ENGINEERING
AND MACHINERY CO.**

CONNAUGHT BUILDINGS
TANNERS BROOK, MILLBROOK
SOUTHAMPTON

Telephone: Southampton 73101/2/3

Press Brake, 6ft. by 14 Gauge
capacity Press Brake urgently required.
Secondhand motorised machine in good condition.—Details including price to KIMBER-ALLEN, LTD., Myron Place, S.E.13. Lee Green 4271.

Le Blond 8½in. Manufacturing
Lathes, Piston Ring Type and Heald, Churchill or similar Rotary Table Grinders with horizontal spindle, having chuck about 28/30in. dia.—BOX V983, MACHINERY, Clifton House, Euston Road, N.W.1.

PLANT FOR SALE**HENRY BUTCHER & CO.**

Specialists in the

• **VALUATION AND SALE OF FACTORIES, PLANT AND MACHINERY** •

73 CHANCERY LANE, LONDON, W.C.2

TEL: HOLBORN 8411 (8 lines) GRAMS: PENETRANCY, HOLB., LONDON

A Good Number of High-class
Machine Tools always in stock.—
ELLISON, Cook Street, off Chapel Street,
Salford 3, Lancs.

New Sheet Metal Grinding and

Polishing Machines by Johanssen for sale. Motor driven 400/440/3/50. Single and double belt models in four sizes to take all kinds of sheet metal up to 9ft. 11in. by 4ft. 11in.—Full details and illustration from F. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1. Euston 4681, or 41, Water Street, Birmingham, 8. Central 7606.

New Richmond SR2 36in. Radial

Drill, motorised 400/3/50. IN STOCK for your inspection.—JAMES W. CARR & CO., LTD., 7-15, Rosebery Avenue, E.C.1. 'Phone: TERminus 8866 (P.B.E.).

Snow P24 Hydraulic Horizontal

Surface Grinding Machine, capacity 24in. by 5in., motorised 400/3/50. Two machines available.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Croft Reduction Gearboxes, Size

3in., ratio 60:1, weight 65 lb. Equal new. 100 available. £5 each.—ROLAND KYLE, Coinbrook, Bucks.

WIDDOWSON'S specialise in re-building your **CINCINNATI** MILLING MACHINE

HERBERT WIDDOWSON & SONS LIMITED
CANAL STREET WORKS • NOTTINGHAM • ENGLAND TELEPHONE 47061

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

**A SELECTION OF
USED MACHINE
TOOLS
AVAILABLE FOR
IMMEDIATE
DELIVERY**

LANG 16in. x 20ft. Lathe, twin saddles.
LANG 63in. Swing Boring and Facing Lathe.
MILWAUKEE 2H Vertical Miller, 1,400 r.p.m.
CINCINNATI No. 2 Dial Type Vertical and Horizontal Millers.
CHURCHILL 14in. x 36in. Plain Cyl. Grinder.
MATRIX 10 and 21 Thread Grinders.
SNOW OS120 Surface Grinder.
6ft. 0in. x 4in. Bending Rolls (New).
KITCHEN & WADE 4ft. 6in. Radial Drill twin motors.
ASQUITH 3ft. 6in. ODI Radial Drill.

W. FORREST & CO. LTD.
INDUSTRY WORKS,
SYLVESTER GARDENS,
SHEFFIELD, 1.
'Phone 23314/5.

Archdale 2-spindle Drilling and Boring Machine. A.G.H., No. 5 M.T. spindles. Motorised.—**WILCOX & CO.**, Barr Street, Birmingham 19. **NORthern** 1234/5.

One Kendall & Gent Vertical Milling Machine Type CVM40. Purchased new 1955. Serial No. 11852C.—**BOX V969, MACHINERY**, Clifton House, Euston Road, N.W.1.

Electric Motors, New and Secondhand, over 1,000 always available for sale, part exchange or hire. Prompt repairing service in event of breakdowns.—**JOHN RODWELL, LTD.**, Vicarage Road, Hornchurch 8877/8.

**NEWALL
Type L.A. 10in. by 48in.
Heavy Duty Hydraulic
Plain Cylindrical
GRINDING MACHINE**

With oscillating wheelhead and equipment

F. J. EDWARDS LTD.,
359-361, Euston Road, London, N.W.1
EUSton 4681 & 3771



104in. **MITCHELL** S.S. & S.C. Lathe, 5ft. b.c.
No. 4 CINCINNATI Plain Miller. Dial type.
No. 2 CINCINNATI Plain Miller. Dial type.
25 A.V.M. KENDALL & GENT Vertical Miller.
No. 2M CINCINNATI Vertical Miller.
No. 1 KEARNS Horizontal Borer. Facing head and spindle.
No. 7 WARD Bar Feed Capstan. Covered bed.
3A WARD Bar Feed Capstan. Overhauled.
No. 8 WARD Combination Turret Lathe.
540 JONES & SHIPMAN Surface Grinder.
6 x 18 **THOMPSON** Toolroom Grinder. Type F.
10in. x 24in. **NEWALL** Universal Grinder.
CHURCHILL HBY Internal Grinder.
No. 3 WARNER & SWASEY Capstan.
No. 3 and 5 GISHOLTS. Bar feed.
24in. **DEAN, SMITH & GRACE** Boring and Facing Lathe.
4in. Spindle **UNION** Model BFT.100.
15, 25, 2D, 2B, 4B **HERBERTS.** TO CLEAR CHEAP.
PLATE Drilling Machine, 2 spindle, No. 5 M.T.
24in. **BULLARD** Vertical Borer.
4in. **B.S.A.** Auto, Long Stroke. Slotting attachment.

DIMCO (Gt. Britain) LTD.
415-417, OXFORD STREET.
LONDON W.1
Tel.: Mayfair 1585.



URGENT?

REMEMBER...

WARDS might have it!

THOS. W. WARD LTD
UNION WORKS, SHEFFIELD



**HAVE CAPACITY AVAILABLE
FOR REBUILDING MACHINE
TOOLS UP TO A CAPACITY
OF 30 TONS.**

**INVITE ENQUIRIES FOR
THIS CLASS OF WORK
AT THE FOLLOWING
ADDRESS**



**The Newall Used
Machine Division**

Oundle Road Works,
ORTON LONGUEVILLE,
PETERBOROUGH,
Telephone 6116

AUTOMATICS—½in. to 3½in.

Makers Butterworth, Brown & Sharpe, Cleveland, Gridley.
Also Lathes, Milling and Grinding Machines.
List on request.

A. BUTTERWORTH & CO.
ST. JOHN STREET, ROCHDALE
(Telephone : 48015)

Mitchell of Keighley S.S. & S.C.
Gap Bed Centre Lathe, 84in. height by 4ft. 3in. between centres, 32in. swing in gap. Motorised 400/3/50.—**SOUTHERN ENGINEERING & MACHINERY CO.**, Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

NEW MACHINES FOR OLD!!!

Reconditioned

Ward 2a and Ward 3a
Capstan Lathes available in exchange
for your worn machines

Immediate Delivery

HELIOT MACHINE TOOL CO

35, Greenwich Church Street, London, S.E.10
Phone : GREENWICH 1222

When answering advertisements kindly mention **MACHINERY**.

Classified Advertisements (PLANT FOR SALE, contd.)



USED LATE TYPE MACHINES

LATHES

LANG, Late Type 8in. centre by 54in., in gap, 28in. Norton Feed Box, Camlock Nose, heavy duty, motorised.
 LE BLOND, Regal A.G.H. 6½in. by 26in., motorised.
 WILSON 7½in. by 40in., gap bed, motorised.
 BERRY A.G.H., 6½in. centre by 32in., in gap 26in., motorised.
 MITCHELL 7½in. by 42in. by 25in. gap, A.G.H., motorised.
 CHURCHILL CUB Lathe, 6in. by 24in., A.G.H., mot. 415/3/50.

CAPSTANS AND AUTOS

WICKMAN Autos, Vinco model, cap. 4mm., motorised. £95.
 WARD No. 7 A.G.H. Bar feed, ball chuck, etc. Motorised.
 WARD 1A Capstans, 1in. collet cap. H.S. range up to 4,130 r.p.m. Ball chuck, bar feed, mot. coolant pump, 400-440/3/50 A.C.
 HERBERT 18 Capstans, ½in. collet cap. Draw-in collet and bar feed, 16 speeds 18/4,020 r.p.m. Hand feed turret and cross slide. Mot. coolant pump, 415/3/50.
 HERBERT No. 0 Capstans, ½in. cap. Dead length air chucks, 12 speeds 93/6,000 r.p.m., mot. coolant pump, 415/3/50.
 BOLEY & LEINEN Precision Capstan. Model S.R.26. Collet cap. 1in., mot. 415/3/50.

MILLING MACHINES

WADKIN High-speed Vert. Mill, table 12in. by 36in., mot. 415/3/50.
 LEINHARD Engraver, ratio 0-0 to 20-1, mot. ARCHDALE 28in., table 40in. by 13in., mot. in base.
 ARCHDALE 20in. Horizontal. Table 40in. by 10in. Dial type speed change 30 to 615 r.p.m. Dial feed. Mot. 415/3/50.
 ARCHDALE 18in. High-speed Vertical WB30. Table 34in. by 10in., 6 speeds 500/2,000 r.p.m. Mot. 415/3/50.

GRINDING MACHINES

ABRASIVE Surface, No. 3, motorised.
 CHURCHILL Hyd. Vert. Surface (plough), cap. 18in. by 36in., segmental wheel 18in. dia. Humphrey mag. chuck, 12in. by 36in., mot. 415/3/50.
 LANDIS Hydraulic Cylindrical Grinder, 12in. by 48in., mot., reconditioned.
 NEWALL Hydraulic Cylindrical Grinder 12in. by 24in., mot.
 SNOW P.24 Surface Grinder. Cap. 24in. by 8in. Hydraulic variable feed to table, wheel dia. 10in., mot. 400/3/50 A.C.
 K.S. Internal Grinder, ½in. to 1½in. dia., int. cap. Power feed to table, auto. sizing device, mot. 415/3/50. Late type machine, ex. con.
 OLIVETTI Automatic Hydraulic Cylindrical Grinder. Type R4/1200, 14in. swing by 48in. between centres. Plunge cut. Mot. 415/3/50.

SHAPING MACHINES

BERRY 14in. Shaper, gearbox drive, mot.
 PRATT & WHITNEY Slotter, 5½in. stroke, tilting ram.

PRESSES AND SHEET METAL, ETC.

RHODES Pluffed Hydraulic Guillotine, 6ft. by 14ft. Gauge, Micro stops.
 FROST Universal Bender, Swing Beam, 6ft. by 14 gauge, motorised.
 THERMIC Muffle Furnace, 15in. by 24in. by 12in., gas heated pyrometer 1,000 deg. C.
 T. & C. B11 and B2, motorised.
 RHODES 40 ton inc., motorised.
 BLISS No. 8, late type, motorised. £100.
 BESCO 60N Double Action, 18 ton, motorised.
 BESCO Nibbler, ½in. cap. throat 45in., mot. 415/3/50.

WILLIAM URQUHART

Head Office:—
 1023, Garratt Lane, London, S.W.17
 Showrooms:—
 Ace Works, Plough Lane, Tooting, S.W.17
 Phone: WIMbledon 6341

Two No. 6SP Potter & Johnston

Chucking Automates, with self-contained motor drive. 15 h.p., 400/3/50, 30in. dia. air-operated chuck, 14in. dia. hole and single cross slide—LEE & HUNT, LTD., Crocus Street, Nottingham.

Safag Plinion and Gear Cutting

Machine for instrument and clock wheels, etc. In unused condition.—BOX V975, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert No. 7 Junior Combina-

tion Turret Lathe, 2½in. hollow spindle, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

There are
HUNDREDS
 of **MACHINES**
 to choose
 from at

THE F.J.E. MACHINE CENTRE

ISLINGTON PARK STREET, NEAR
 Highbury Corner, LONDON, N.1
 (on the main A1 Road from the North)

Norton Cylindrical Grinder. 4in.

swing, 18in. between. Motorised. Price £125.—W. H. BARKER, 14 Mill Green Camp, Hatfield. Phone: Hatfield 2764.

NEW MACHINES EX STOCK FOR IMMEDIATE DELIVERY.

PROGRESS 4E Pillar Drill, 1½in. capacity, power feeds.
 PROGRESS 5E Pillar Drill, 2in. capacity, power feeds.
 VICTORIA V8 Vertical Mill, table 60in. by 12½in., power feed, rapid traverse in all directions.
 VICTORIA U2 Universal Mill, table 46in. by 11in., power feed all directions.
 EXCEL No. 5 Tool and Cutter Grinder, 10in. by 26in. capacity.
 ALBA 68 Shaping Machine, 24in. stroke.
 VELOX Hackaws, 7½in. and 10in. capacity.
COLCHESTER LATHES.
 CHIPMASTER 5in. by 20in. Cabinet Base, MASTER 6½in. by 36in. Cabinet base.
 TRIUMPH 7½in. by 48in. Straight bed. Cabinet base.
 MARCOT 8½in. with 8ft. or 10ft. Gap Bed.

All the above machines are motorised 415/3/50.

A. LAWRENCE & CO.
 (MACHINE TOOLS) LTD.
 WELSH HARP, EDGWARE ROAD,
 LONDON, N.W.2.

Phone: GLAdstone 0033.



NEW MACHINE TOOLS FROM STOCK

GRANOR OF HALIFAX 11in. Gap Bed Lathe by 8ft. 0in. b.c. Hole in spindle 3½in. dia. 400-440/3/50.

MITCHELL OF KEIGHLEY 10½in. Gap Bed Lathe by 5ft. 6in. b.c. 400-440/3/50.

EXCEL No. 3/12 Hydraulic Horizontal Spindle Surface Grinding Machine. Capacity 24in. by 8in. Coolant equipment. Motorised 400-440/3/50.

VICTORIA V2 Vertical Milling Machine. Spindle speeds 32-1,050 r.p.m. Table 45in. by 11in. Table traverse 20in. 400-440/3/50.

NEW MACHINE TOOLS—EARLY DELIVERY

MITCHELL OF KEIGHLEY 8½in. Gap Bed Lathe by 5ft. 3in. b.c. 400-440/3/50. Delivery—April, 1958.

MITCHELL OF KEIGHLEY 12½in. Gap Bed Lathe by 6ft. 0in. b.c. 400-440/3/50. Delivery—April, 1958.

VICTORIA U2 Universal Milling Machine. Spindle speeds 30-1,010 r.p.m. Table 45in. by 11in. Longitudinal traverse 30in. 400-440/3/50. Delivery—April, 1958.

USED MACHINE TOOLS

NORTON Horizontal Spindle Hydraulic Surface Grinding Machine, with hydraulic cross feed head. Capacity 48in. by 10in. Complete with D.C. magnetic chuck and generator. Coolant pump and fittings. 400-440/3/50.

HERBERT No. 4 Capstan Lathe, with draw-back collet, and power feed to turret slide. 400-440/3/50.

NEWALL Hydraulic "XL" 6in. by 18in. Plain Grinding Machine. 400-440/3/50.

NEWALL Type L, 10in. by 24in. Plain Grinding Machine. 400-440/3/50.

LE BLOND A.G.H. S. & S. Lathe, 15in. dia. swing. 400-440/3/50.

HULLER No. 5 Vertical Tapping Machine. 400-440/3/50.

POLLARD 21A Single Spindle Vertical Production Drilling Machine.

CLIFTON & BAIRD 30in. Hydraulic Cold Sawing Machine. 400-440/3/50.

WICKSTEED Hydraulic 28in. Cold Sawing Machine. 400-440/3/50.

ARCHDALE 18in. High Speed Vertical Milling Machine. Table size 28in. by 10in. Spindle speeds 79-2,000 r.p.m. 400-440/3/50.

WE UNDERTAKE REBUILDING OF ALL TYPES OF MACHINE TOOLS.

CENTAUR TOOL WORKS,
 EYRE STREET, SPRING HILL,
 BIRMINGHAM, 18.

Tel.: EDGhaston 1118 & 1119. Grams: Capstan, Birmingham.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

Cashmores

Selection of Machine Tools from Stock

CENTRE LATHES

LANG 8 1/2 in. S.S. & S.C. Lathe to admit 4 ft. 0 in. between centres.
COLCHESTER MASCOT 8 1/2 in. S.S. & S.C. Lathe, to admit 4 ft. 6 in. between centres.
New MITCHELL OF KEIGHLEY 12 1/2 in. S.S. & S.C. Lathe, to admit 5 ft. 0 in. between centres.
VOLMAN 8 in. S.S. & S.C. Cap Bed Lathe, to admit 4 ft. 6 in. between centres.
New MITCHELL OF KEIGHLEY 10 1/2 in. S.S. & S.C. Lathe, to admit 7 ft. 5 in. between centres.
F.L.C.B. 13 in. S.S. & S.C. Heavy Duty Lathe, to admit 17 ft. between centres, 2 saddles.

CAPSTAN LATHES

WARD 3A Capstan Lathe, with collet chuck and bar feed, 1 1/2 in. capacity.
WARD No. 7 Capstan Lathe, with covered bed, arranged for chuck work, 2 1/2 in. hollow spindle.
WARD 2A Capstan Lathe, with collet chuck and bar feed, 1 1/2 in. capacity.

BORING MACHINE

TULLIS Horizontal Boring Machine, Floor Type with 3 1/2 in. traversing spindle, 9 ft. 0 in. by 2 1/2 in. tee-slotted baseplate.

UNIVERSAL GRINDING MACHINE

LANDIS 16 in. by 36 in. Universal Grinding Machine, with hydraulic feed.

DRILLING MACHINE

GIRARD 5 ft. 0 in. Radial Drilling Machine, Elevating Arm, with Loose Box Bed, two motor type.

PLAIN GRINDING MACHINE

CHURCHILL 10 in. by 36 in. Hydraulic Plain Cylindrical Grinding Machine.

MILLING MACHINES

HERBERT 23V Vertical Milling Machine, 68 in. by 17 in. table.
CINCINNATI No. 3 Dial Type Vertical Milling Machine, 82 1/2 in. by 15 in. table, motorised.
ARCHDALE 18 in. Vertical Milling Machine, 38 in. by 10 in. table.
CRAVEN "Klidsmil" Production Milling Machines, working surface of table 39 in. by 13 in., spindle speeds 25-400 r.p.m. Two machines available.
EDGWICK 18 in. Production Milling Machine, working surface of table 26 in. by 12 in.
New VICTORIA U1, U2 and U3 Universal Milling Machines.
ARCHDALE 20 in. Horizontal Plain Milling Machine, 40 in. by 10 in. table.
CUTTAT HYPERMIL Production Milling Machine, 43 in. by 10 in. working surface of table, with 4 automatic cycles to table.

SAWING MACHINES

RUSSELL 20/24 in. Cold Circular Sawing Machine, with hydraulic clamping to vice.
NOBLE & LUND 11/16 in. Cold Circular Sawing Machine.

SHEARING MACHINE

RUSHWORTH 10 ft. 0 in. by 1/2 in. Overcrank Guillotine Shearing Machine.

SURFACE GRINDING MACHINES

EXCEL No. 3A Hydraulic Horizontal Spindle Surface Grinder, 24 in. by 8 in. capacity.
LUMSDEN 92LE Vertical Spindle Rotary Table Surface Grinder, 48 in. diameter table.

All the above machines are motorised 400-440/3/50 cycles.

JOHN CASHMORE LTD.

NEWPORT 1, MON.

Tel.: Newport 66941 (5 lines).
(Also at Great Bridge, Staffs.)



New & Used Machine Tools.

HARRISON A.G.H. Centre Lathe, 11 in. swing, 24 in. between gap bed, with taper turning and collet equipment.
12 KVA Spot Welder with timer.
ELECTRISIA 1 1/2 in. cap. Geared 27 in. Column Drilling Machine. (New.)
HERBERT 4 spindle Drill, No. 2 M.T. One geared spindle. Mot.
EDWARDS 4 ft. by 14 g. Universal Swing beam Folder.
HENRY & WRIGHT 100-ton Dieing Press, modern machine with full equipment.
BLISS No. 20 Power Press, 1 1/2 in. stroke.
NORTON Horiz. Spindle Surface Grinder, 36 in. table with 24 in. by 8 in. mag. chuck.
PALLAS Vertical Mill, sliding/swiv. head, table 44 in. by 12 in., old machine, good condition.
WARD 2A Capstan Lathe, bar feed, ball chuck, taper turn.
HERBERT No. 1 Capstan, dead length.
SHAPE-RITE 8 in. Bench Shaper.

STRAIGHT & VINES LTD.

MINT STREET, BOROUGH,
LONDON, S.E.1.

Telephone: HOP 4364.

Taylor & Challen B3 Geared

Press, 40 tons, 6 in. stroke, Fitted dial feed. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. NORTHERN 1234/5.

Perrin Jig Borer (Swiss), £550.

B. & S. No. 13 Universal Grinder, £400. Taylor Band Saw, £75. Colchester 7 in. Lathe, £100. Halifax 5 in. Lathe, £30. Frickler Surface Grinder 14 in. by 6 in., £200. Gap Gauge Grinder, £40. Various small tools and equipment to clear.—Phone: LIVINGSTONE 1651.

Centec 2B Universal Miller,

complete on pedestal with vertical attachment, etc. Motorised 400/3/50. IN STOCK for your inspection.—JAMES W. CARR & CO., LTD., 7-15, Rosebery Avenue, E.C.1. 'Phone: TERminus 8866 (P.B.E.).

Wanderer Universal Milling

Machine. Table 30 in. by 10 in. Speed 98-1,000 r.p.m., complete with dividing head, toolholders, etc. As new.—BOX T105. MACHINERY, Clifton House, Euston Road, N.W.1.

No. 3 Kendall & Gent Motorised

Horizontal Broaching Machine, 50 in. stroke. Broaches up to 3 in. squares from round, four cutting speeds. Constant quick-return.—LEE & HUNT, Crocus Street, Nottingham.

EDGWICK No. 2 Univ. Miller.
SWIFT 9 x 72 in. Gap Bed Lathe.
LA POINTE 31 1/2 Horiz. Broach, 64 in. stroke.
BARNES No. 2 Horiz. Hones.
WARD No. 7 Comb. Turret Lathe, 1940.
NILES 27 in. x 27 1/2 in. Twin Saddle Lathe.
ACME GRIDLEY HACH Chuck Auto.
CHURCHILL No. 1 Planetary Grinder.
ORCUTT HM24 Gear Grinder, 1944.
CINCINNATI 1/18, 2/24 Prod. Mills.
RIDER WELLMAN Horiz. Borer, 3 insp.
B. & S. OOG S.S. Autos, 1942.
LA POINTE 28L Horiz. Broach.
VICTORIA U2 Mill, with dividing hds., 1955.
ACME GRIDLEY 24 in. S.S. Auto, 1942.
MODERN 6 in. x 15 in. Surface Grdr., 1953.
CHURCHILL OSV 40 in. x 10 in. Vertical Spindle Surface Grinder, 1942.
ARCHDALE 30 in. H.D. Pillar Drill, 1942.
GISHOLT 4, 5 and 11 Turret Lathes, 1941-43.
WARNER & SWASEY 3, 5 and 3A Turrets.
HERBERT 21, 4, 4 Senior Turret Lathes.
B. & S. No. 3 Vert. Mill, 1942.
WARD 2A and 3A Capstans, 1942.
ARCHDALE 18 in. and 30 in. Vert. Mills, 1942.
CINCINNATI 2MH & No. 2 Plain Mills, 1942.
HEALD 48A S. End Borematics, 1941-44.
DEFIANCE No. 5 Hor. Borer, 3 in. sp., 1941.
B.S.A. 1 in. S.S. Automatics, 1941.
CINCINNATI 1L and No. 2 Vert. Mills, 1942.
B. & S. No. 2 Universal Grinders, 1941.
NEWALL 10 by 24 1/2 in. Grinders, 1942.
MONARCH Magnamatic Prod. Lathe, 1946.
ORCUTT 5 in. by 36 in. Spine Grinder, 1944.
V.D.F. 10 in. by 72 in. Centre Lathe, 1941.
CINCINNATI 3/24, 3/36 Hydromatics, 1945.
HERBERT 0, 1 and 53 Plain Mills, 1940.
P. & W. 12B 2-spindle Profiler, 1941.
KITCHEN & WADE No. 2 Cyl. Hone, 1940.
CHURCHILL NB 6 in. x 18 in. S. Gr., 1942.
CHURCHILL Centreless Gr., Model EC, 1940.
COCHRANE BLY No. 35 Cold Saw, 1940.
INDEX OR12 S.S. Auto, 4 in. cap., 1940.
FOOTBURN 1 in. cap. S.S. Automatic, 1943.
All modern fully motorised machines.

J. B. MACHINE TOOL CO., LTD.

312/4, BRADFORD STREET,
BIRMINGHAM, 5.

TEL.: MIDLAND 4375.

AND AT WOLVERHAMPTON.

Acme Gridley 1 in. R.A. 4-spindle

Auto, motorised 440/3/50. Very good condition. Three available.—BOX V876. MACHINERY, Clifton House, Euston Road, N.W.1.

TAYLOR & CHALLEN Model B3 40-ton

Geared Power Press, 5 in. stroke, motor driven 400/3/50. Price £475 0s. 0d.

PARKES (MACHINE TOOLS) LTD.

WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

NEW POWER OPERATED GUILLOTINES MOTORISED 400/3/50

1—48 in. by 4 g. MORGAN.
1—48 in. by 1 in. MORGAN.
1—72 in. by 14 g. MORGAN.
1—72 in. by 1 in. MORGAN.
1—72 in. by 1 in. KEETONA.

NEW PEDESTAL TYPE CRAMP FOLDING MACHINES.

1—48 in. by 16 g. MORGAN.
2—48 in. by 1 in. KEETONA.

STOCK DELIVERY.

JOHN CASHMORE LTD.

GREAT BRIDGE,
TIPTON,
STAFFS.

'Phone: Tipton 2181/7.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

C.E.M.

PEARSON Electro-Hydraulic Guillotine
8ft. by 1in. new, for early delivery.

BENTLEY Plate Bending Rolls, 6ft. by
1in., 8ft. by 1in. and 8ft. by 1in. New.

BERRY 12in. by 7ft. 3in. S.S. & S.C.
Lathe. New.

SEDGWICK Universal Plate Bending
and Folding Machine, 6ft. by 1in.
capacity.

BENTLEY 200-ton Power Press, 8in.
stroke. New.

BENTLEY 80-ton Power Press, adj.
stroke. New.

BENTLEY 50-ton Power Press, adj.
stroke. New.

CINCINNATI No. 2 Dial Type Horiz.
Mill.

WICKMAN 5in. five-spindle Auto-
matic.

PROGRESS 4E Drilling Machine, sufs.
New.

All machines motorised 400/3/50.
Fully detailed stock lists available.

**CHARLES E. MATTHEWS
(MACHINE TOOLS) LTD.**

34, Gladstone Road,
Croydon, Surrey

Tel. No.: THOrnton Heath 1783
Telegrams: "Matolco" Croydon

Scriven 3-Roll Plate Bending

Machine, rollers 14ft. wide, 1in. capacity.
Archdale 4ft. Radial Drilling Machine, tapping
reverse speeds, motorised.

Herbert Filing and Sawing Machine, 15in.
square adjustable table.

Alexander 16in. Cutting-off Machine, 12½ h.p.
400/3/50.

Herbert Hack-saw, 13in. blade, belt driven.

Wicksteed Hydrofeed Hack-saw, 16in. blade,
6in. by 6in.

Rex Hydraulic Hack-saw, 18in. blade, 8in.
by 8in.

Colchester 7in. Centre Lathe, 7ft. gap bed,
A.G.H.

Herbert Horizontal Milling Machine, 3ND,
table 61in. by 15in., 4 spindle speeds.

3,000 K.G. Capacity Avery Hardness Testing
Machines, 10in. dia. table (2).

V. & O. 50-ton Inclinable Geared Open
Fronted Press; 20-ton Bliss.

Crow Harvey Punch, Shears and Angle
Cropper, 18in. blade, 27in. throat, heavy duty.

Pels Punch, Shears and Cropper, 12in. blade,
shear 1in., takes 6in. by 6in. by 1in. angles.

Craig & Donald Billet Shears, 8in. blade,
6in. by 1in. capacity.

Robertson Shears, 1in. capacity, 10 h.p.
28in. blade, 9in. maximum opening. (2)

Robertson 7-roller Plate Flatteners, 8ft. 6in.
wide, approximately 1in. capacity.

Berry 3-roller Plate Bender, 7ft. wide,
approximately 1in. capacity.

Sweeney Fly Presses, all sizes, 20 available.

Masey 3-cwt. Bottle Forging Hammer.

New 1-cwt. and 2-cwt. Hammers by Masey
and Aildays & Onions.

Oliver Planishing Hammer, 29in. gap.

FRED WATKINS (BOILERS), Ltd.,
Coleford, Glos. 'Phone: Coleford 2271 (3 lines)

K.E.N.T

Monarch 14AA 8in. S.S. & S.C. Lathe.
£625.

Herbert No. 1 1in. Capstan. £150.

Herbert O Capstan, £110.

Butterworth 1½in. Automatic. £475.

Haskins ½in. Capacity Tapping Machine.
£60.

Corona 2AX No. 2 M.T. Drilling Machine.
£67 10s. 0d.

Zimmerman Hori. Boring Machine, 2in.
travelling spindle. £325.

Parkson Horizontal Milling Machine.
Table 51in. by 11in. overall. £195.

Speedax No. 2 Riveter. £35.

Jos. Heap 1in. Tangential Screwing
Machine. £165.

Ward OE Capstan. Bar feed. £165.

Hardinge Precision Lathe, Sin. £37 10s.

Peterman P10 S.S. Auto. Extensive
collets and equipment. £395.

Willson 7½in. S.S. & S.C. Lathe. £235.

Lang 8½in. S.S. & S.C. Lathe. T.T. A.G.H.
£695.

Van-Norman 22L. Hori-Vert. Milling
Machine. £895.

Archdale 18in. Vert. Milling Machine.
Fixed head. £250.

All machines mot. 400-440/3/50.

**K.E.N.T MACHINERY &
ENGINEERING CO.**

Datchelor Place, London, S.E.5.
Telephone ROD. 4149.

ARE YOU LOOKING?

FOR A MODERN MACHINE
FROM STOCK

A selection from our 1,500 available tools

LANDIS 10in. by 72in. Type 'C' motor
driven Hydraulic Plain Cylindrical Grinder.
Serial No. 21699, complete with seven
steadies.

SCHNEIDER 24in. by 8in. Horizontal
Spindle Surface Grinder, hydraulic feeds,
grinding wheelhead swivels through 90
degrees enabling sideway and cup wheel
grinding to be done. NEW.

KITCHEN & WADE V.15 Vertical Hy-
draulic Honing Machines, capacity 2in. to
9in. dia. and up to 25in. length of bore,
speeds and strokes hydraulically variable,
speeds 0 to 250 r.p.m., strokes 0 to 80ft.
per minute.

ARCHDALE 30in. Vertical Miller, table
44in. by 14½in., auto. longtl. feed 30in.,
auto cross feed 12in., hand vertical adjust-
ment 18in., 12 spindle speeds 29 to 520
r.p.m.

**FAIRBAIRN, LAWSON, COMBE &
BARBOUR** S. and S. Lathe, swing 36in.,
takes 23ft. between centres, two saddles
both with taper turning and electric
control. 4½in. hollow mandrel, 24 spindle
speeds 1.08 to 152 r.p.m.

SENTINEL 6in. by 30in. Hydraulic Copying
Lathe, operated on electrical system,
five slides (2 back, 3 overhead).

HULLER No. 5 Tapping Machine, capacity
1½in. in steel, 1½in. in brass.

LIBBY 2H8 Universal Combination Turret
Lathe, height of centres 13½in., swings over
cut-off slide 25in., hole through spindle
8½in., 8 spindle speeds 8 to 128 r.p.m.,
chases 4 to 64 t.p.i. Quick return to cut-
off slide, saddle and turret.

VOLMAN 8in. by 24in. capacity High
Speed Sliding and Surfacing Diamond
Turning Lathe, 12 spindle speeds 95 to
1,180 r.p.m.

MAAG SS.30 Automatic Gear Grinding
Machines for spur gears. Max. dia. for
up to 2½in., face 1½in., from 2½in. to 5½in.,
8½in., min. pitch circle diameter 1½in.,
max./min. cutting pitch 2½ to 12½ d.p.,
max./min. number of teeth 120/10.

PITTLER RE.11.60 Turret Lathes, 8½in.
centres, spindle flange to turret 31½in.
spindle hole 2½in., swing 21½in., fitted,
chasing attachment.

HERBERT 23V Vertical Miller, table 68in.
by 12in., auto longtl. feed 48in., auto cross
feed 18in., vertical travel 25in., vertical
adjustment of head 10in., spindle speeds
16.5 to 427 r.p.m.

LEES-BRADNER Type HT Thread Milling
Machines, capacity 12in. dia. by 102in.
long.

ROWLAND Model ADD Motor driven
Hydraulic Duplex Surface Grinding
Machine, disc opening 13½in.

RYDERMATIC No. 12 single spindle Vertical
Multi-tool Chucking Auto max. swing
20in., length between centres 16in.,
turning slide vertical stroke 8in., facing
slide stroke 5½in., auxiliary stroke 4in.,
speed range 31½in. to 309.

BERTRAM (NILES TYPE) S.S. & S.C. Lathe
17½in. centre on 39ft. bed, 30ft. between
centres, 3in. hollow mandrel, two saddles
both with independent electric control
and taper turning.

PEARNS RICHARDS No. 1 Hori. Boring
and Facing Machine with facing head,
quartering table, Vernier scales, table
20½in. by 32in., facing head 18in. dia.

CHURCHILL P8H Universal Grinder, 16in.
by 50in. capacity, work speeds 46 to 181
r.p.m., table traverse (hydraulic) up to
180in. per minute.

VAN NORMAN IV Vertical Miller, table
32½in. by 9in., auto longtl. feed 24in.,
hand cross feed 6½in., hand vertical 16½in.,
eight speeds from 100 to 2,500 r.p.m.

CONOMATIC 4-spindle, 4½in. capacity
Bar Automatics, two drilling spindles,
master collets, quantity of pads.

ALL MOTORS 400-440 volts, 3-phase, 50-cycle SUPPLY

LITTON'S MACHINE TOOL CO., LTD.

Telephone: SH0reditch 4814/5.

372-378, OLD STREET, LONDON, E.C.1

Telegrams: "Galloon, Avenue, London".

When answering advertisements kindly mention MACHINERY.

SELECTIONS FROM OUR LARGE STOCK OF MODERN MACHINE TOOLS

(All machines motorised 400-440/3/50 and overhauled unless otherwise stated)

LATHES, CAPSTANS AND AUTOS.
WILLSON 6 1/2 in. x 36 in. S.S. & S.C. Lathe.
WARD 1A Capstan, B.C. and B.F.
HERBERT 2D Capstan, B.C. and B.F.
WARD 10 Combination Turret Lathe.
HERBERT No. 8 Combination Turret Lathe, covered bed.
SMALLFEE No. 6 M.S.I. Multi-Production Lathe.
HERBERT 5A Capstan chucking m/c.
HERBERT No. 4 Capstans, 4 chucking machines.
ACME 5W Turret Lathe, chuck machine.
HERBERT Model O Capstan, pneumatic bar chuck and bar feed.
WARD 3A Capstans, B.C. and B.F. 2 M/cs.
WARD 2A Capstans, B.C. and B.F.
D.S.G. 13Z MINOR 6 1/2 in. by 31 in. S.S. & S.C. Lathe.

DRILLS.

KITCHEN & WADE 32 in. Radial 3 M.T. Sens.
ARCHDALE Mod. 2220 Pillar, 1 1/2 in. cap., p/feeds.
HERBERT Type "C" Pillar, 1 1/2 in. cap., p/feeds.
JONES & SHIPMAN Fig. 921, 30 in. Pillar, 2 in. cap., p/feeds.

GRINDERS.

CINCINNATI No. 2 Tool and Cutter.
CHURCHILL Mod. H.A.Y. Internal Hyd.
NEWALL 10 in. by 36 in. Plain Hyd.
ABRASIVE Mod. 3B Surface, cap. 8 in. by 24 in.
CHURCHILL Mod. N.B. Horizontal Surface, cap. 6 in. by 18 in.



M. WARD (MACHINE TOOLS) LTD.
PHONE: MAIDA VALE 1195-1196
GRAMS: EMWARNEERS KILB-LONDON
**I, KILBURN HIGH ROAD
KILBURN-LONDON-N.W.6**

Robertson 7-stage Section Forming Machine for Sale with additional curving unit. Specially suitable for profiling and bending stainless steel sections. Drive is by 20 h.p. motor through 3-speed gearbox. Diameter of roller shafts, 2 in. Length of shafts available for forming rollers 8 1/2 in. Rolling speeds with 6 in. diameter rollers, 40, 80 and 120 ft. per minute. Weight about 1 1/2 tons. Full details and illustrations from F. J. EDWARDS, LIMITED, 359/361, Euston Road, London, N.W.1, or 41, Water Street, Birmingham, 3.

Drummond K. Capstan. Equivalent to No. 4. Good condition. With equipment. 400/3/50 electric. £200 for quick sale.—BOX V994, MACHINERY, Clifton House, Euston Road, N.W.1.

MARTIN BROS. (Machinery) Ltd.

Telephone: TRAFFORD Park 1091-2

**REBUILDERS OF ALL
TYPES OF TOOLS FOR
OVER 40 YEARS
PRECISION REBUILDERS TO
THE TRADE & GOVT DEPTS**
Guaranteed 6 months, Crane Capacity 15 tons

EMPRESS WORKS, EMPRESS STREET, CORNBROOK, MANCHESTER 16



NEW, USED and REBUILT

**MACHINE TOOLS
400 ALWAYS IN STOCK**

U.K. AGENTS FOR: H.M.V. (Swedish)
Universal Boring, SCOTT SUNDER-
LAND SHEET METAL TOOLS,
BULLOWS COMPRESSORS, C.V.A.
CHUCKS, GRANOR CENTRE
LATHES.

MILLERS.

MILWAUKEE Mod. 2HL. Plain.
KENT-OWEN No. 1/14 Hyd. Plain. 2 m/cs.
VAN NORMAN No. 2L. Plain, table 45 in. by 10 in.
CINCINNATI Mod. 08 Vert., table 24 in. by 6 in.
HERBERT No. 1 Plain, with auto. feed.
ARCHDALE 20 in. Plain, with rapid traverse.
CINCINNATI 18 in. Manfig. Model O.K., table 34 in. by 12 in.
ARCHDALE 14 in. Plain, table 27 in. by 8 in., long travel 14 in.
ASQUITH Type V Vert., table 50 in. by 14 in., long travel 28 in.

MISCELLANEOUS.

NOBLE & LUND 11 in.-16 in. Cold Saw.
T.M.A. Mod. G2 Pantograph Engraving Machine.
CLEVELAND Rigidhobbers, 2 machines, mod. 120, 1 machine mod. 130.

CINCINNATI No. 3 Dial Type Vertical Milling Machine. Speed range 18-450 r.p.m.
HERBERT 47V Vertical Milling Machine. Speed range 21-750 r.p.m.
ARCHDALE 30 in. Vertical Milling Machine. Speed range 29-525 r.p.m.
PARKSON INA Universal Milling Machine. Speed range 17-450 r.p.m. Comprehensive equipment.
PARKSON 2T Universal Milling Machine. Speed range 15-300 r.p.m. Comprehensive equipment.
BROWN & SHARPE No. 10 Production Milling Machine. Speed range 55-1,800 r.p.m.
HERBERT 98 Combination Turret Lathe. Speed range 14-400 r.p.m.
WARD 7 Combination Turret Lathe. Taper turning. Bar feed and chucking. Speed range 37-750 r.p.m. Comprehensive equipment.
WARD 7, 3A, 2A, 1A, 0E Capstan Lathes Bar feed.
CHURCHILL 16 in. by 50 in. Universal Grinding Machine. Comprehensive equipment. Unused.
NEWALL Type L 10 in. by 36 in. Plain Grinding Machine.
JONES & SHIPMAN 10 in. by 27 in. Plain Grinding Machine.
B.S.A.-LANDIS Type C 6 in. by 18 in. Plain Grinding Machine.
NORTON 6 in. by 18 in. Surface Grinder.
CHURCHILL 16 in. Ring Grinder.
CHURCHILL 24 in. Ring Grinder.
CHURCHILL 42 in. Ring Grinder.
SCRIVENER 2C Centreless Grinder.
HENDEY 24 in. by 168 in. S.S. & S.C. Lathe. Speed range 14-560 r.p.m.
F.L.C.B. 17 in. by 10 ft. S.S. & S.C. Lathe. Speed range 1.08-152 r.p.m.
OLDFIELD & SCHOFIELD 15 in. by 8 ft. S.S. & S.C. Gap Bed Lathe. Speed range 6.5-332 r.p.m.
OLDFIELD & SCHOFIELD 12 1/2 in. by 7 ft. S.S. & S.C. Gap Bed Lathe. Speed range 12-400 r.p.m.
CINCINNATI Type LT 8 in. by 4 ft. 6 in. S.S. & S.C. Lathe. Speed range 16-392 r.p.m.
LANG 9 in. by 5 ft. 6 in. S.S. & S.C. Lathe. Speed range 8.75-240 r.p.m.
DEAN SMITH & GRACE 7 in. by 3 ft. 6 in. S.S. & S.C. Gap Bed Lathe. Speed range 11-490 r.p.m.
DEAN SMITH & GRACE 7 in. by 2 ft. 6 in. S.S. & S.C. Gap Bed Lathe. Speed range 11-490 r.p.m.
DENHAM 6 in. by 3 ft. 0 in. S.S. & S.C. Gap Bed Lathe. Speed range 10-400 r.p.m.
KITCHEN & WADE 4 ft. No. 5 M.T. Radial Drill. Speed range 20-1,000 r.p.m.
TOWN 4 ft. No. 3 M.T. Radial Drill. Speed range 20-1,000 r.p.m.
TOWN 3 ft. No. 2 M.T. Radial Drill. Speed range 126-1,450 r.p.m.
ASQUITH Type E.G.C. 6 ft. Girder Type Radial Drill. Speed range 183-580 r.p.m.
ASQUITH Type E.G.C. 8 ft. Girder Type Radial Drill. Speed range 31-830 r.p.m.
HEALD 47B Borematic.
KEARNS Type OA Horizontal Boring Machine.
B.S.I.V. 1 in. Automatic Screwing Machine.
KENC0 6-3 Screwing Machine. Comprehensive equipment.
CLIFTON & BAIRD Punching and Cropping Machine. Capacity 4 1/2 in. by 4 1/2 in. by 1 in. angle.
BIGWOOD 4-Roll Bending and Straightening Machine. Capacity 4 ft. by 1 in.
Modern Machines—Motorised 400-440/3/50. Fully Overhauled—Six Months Guarantee.
**WESTERN MACHINE TOOLS
(SWANSEA) LTD.**
72, MANSEL STREET, SWANSEA.
Tel.: 50061/2.

Churchill No. 2 Centreless
grinder. Unused. Fitted hydraulic feed, concentric grinding attachment, truing diamonds etc. Inspection London.—BOX 991, c/o WALTER JUDD, LTD., 47, Gresham Street, London, E.C.2.

When answering advertisements kindly mention MACHINERY.

Newman

FOR MACHINE TOOLS

Below are selected offers from our extensive and varied stock

SLOTING MACHINES

MUIR 17in. Stroke Vertical Slotting Machine.

GRINDING MACHINES

SCRIVENER No. 2 Centreless Grinding Machine.

LANDIS Plain Hydraulic Cylindrical Grinding Machine, capacity 10in. by 96in.

LANDIS Hydraulic Universal Grinding Machine, 14in. by 36in. between centres.

LANDIS Type D Hydraulic Crank Pin Grinding Machine, capacity 21in. by 72in.

NEW EXCEL No. 3 Hydraulic Surface Grinding Machine.

NEW EXCEL No. 5 Tool and Cutter Grinder.

BROWN & SHARPE No. 2 Surface Grinding Machine, capacity 6in. by 18in.

NORTON Universal Grinding Machine, type "C", capacity 12in. by 36in.

LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machine, capacity 10in. by 36in.

CHURCHILL Universal Grinding Machine, 10in. by 24in. between centres.

NORTON 6in. by 18in. Plain Cylindrical Grinding Machine.

B.S.A.-LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machines, 6in. by 30in. (Two available.)

CHURCHILL Model HBY Internal Grinding Machine.

BORING MACHINES

UNION Horizontal Boring Machine, Model BFT, 100 3/8in. dia. travelling spindle, 24in. dia. facing head (1957).

RICHARDS Type PRT Horizontal Type Floor Boring Machine, 34in. dia. travelling spindle and 28in. dia. facing head.

ASQUITH 7in. Horizontal Floor Boring Machine.

BERTHIEZ Model 9340 Vertical Boring Mill table diameter 7ft. 10in., maximum turning capacity 9ft. 6in. (1953.)

JUNGENTHAL Model KE 1200 Vertical Boring Mill, table diameter 39in., maximum turning capacity 50in. (1954.)

FRORIEP Vertical Boring Mill, table diameter 39in., maximum turning capacity 52in. (1955.)

KEARNS No. 3 Horizontal Boring Machine, 34in. diameter travelling spindle, maximum facing diameter 24in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

RICHARDS Double Column 6ft. Vertical Boring Mill, maximum turning capacity 72in.

CINCINNATI 2M Universal Milling Machine.

MILWAUKEE No. 4H Plain Horizontal Milling Machine, table 74in. by 154in.

CINCINNATI No. 3 Dial Type Plain Horizontal Milling Machine, table 624in. by 15in.

VICTOMATIC Automatic Cycle Production Milling Machine, capacity 50in. by 10in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

REED-PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.

CAPSTAN & CENTRE LATHES

WARD 78 Hexagon Turret Lathes with bar feed. (Two available.)

OLDFIELD & SCHOFIELD Boring and Surfacing Lathe, cross-traversing Turret type.

LE BLOND Regal Centre Lathe, 94in. by 42in. between centres.

BRADFORD 84in. centre height by 30in. between centres Centre Lathe.

HERBERT No. 8 Combination Turret Lathe.

URQUHART LINDSAY & ROBERTSON ORCHAR Centre Lathe, 16in. by 30ft. 6in. between centres.

LIBBY Model 2H-8 Combination Turret Lathe, 84in. hollow spindle.

HERBERT No. 12 Combination Turret Lathe with comprehensive tooling.

NILES Centre Lathes 134in. centre height by 27ft. between centres. (Two available.)

NILES Centre Lathes, 15in. centre height by 28ft. between centres. (Two available.)

BETTS-BRIDGEFORD Centre Lathe, 15in. centre height by 16ft. between centres. (Two available.)

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

WARD No. 7 Combination Turret Lathe.

DRILLING MACHINES

KITCHEN & WADE 28V10 Single Spindle Vertical Drilling Machine, No. 4 M.T.

ARCHDALE Multi-spindle Drill Machine, 36 spindles.

HETTNER Radial Drilling Machine, having 10ft. Radial Arm elevating column type.

TOWN 30in. Vertical Spindle Boring, Drilling and Tapping Machine, No. 5 M.T.

KITCHEN & WADE 4ft. 6in. Radial Drilling Machine.

KITCHEN & WADE 4ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

ASQUITH ODI 6ft. Radial Drilling Machine.

AS

Classified Advertisements (PLANT FOR SALE, contd.)

**UNREPEATABLE BARGAIN for GOOD CLASS USED MACHINE TOOLS**

9in. **LANG** Toolroom S.S. & S.C. Lathe, 4ft. 0in. bet. centres, speeds 12-600 r.p.m. Serial No. 27649/1587. Full equipment £375

6in. x 30in. **PRATT & WHITNEY** Toolroom Lathe, full equipment including T.T. att. £225

CINCINNATI 1/18 Automatic Cycle Milling Machine. Table 41in. x 10in. Speeds 50-1,500 r.p.m. £325

CINCINNATI 1/12 Automatic Cycle Milling Machine, speeds 50-1,500 r.p.m. £300

BLANCHARD No. 10 Vertical Rotary Surface Grinder. 16in. dia. Table. 10in. Wheel. £250

2-Off **GISHOLT** No. 4 Universal Turret Lathes. Speeds variable to 730 r.p.m. Hardened Bedways. Power feeds to cross slide and turret, complete with full equipment. War time machines. Each £200

2-Off **LIBBY** 4R Universal Turret Lathes. Swing over Bed 20in. Power feeds to cross slide and turret. Speeds to 725 r.p.m. Chucking machines with full equipment. Each £185

1-Off **LIBBY** 4R Turret Lathe, as above, but Ball Chuck Bar Feed. £225

WICKMAN Profile Grinder, 50-1 Pantograph, 50-1 Microscope. £650

LANDIS 6in. x 18in. Hydraulic Plain Cyl. Grinder (American built) in perfect condition. £450

MANY OTHER MACHINE TOOLS AT VERY COMPETITIVE PRICES.

Write for Stock List.

THE CAUSEWAY, EGHAM, SURREY.

Tel.: Egham 3155/6.



**LATE TYPE
HIGH CLASS
SLOTING MACHINES
IN STOCK**

BUTLER 20in. High Production, table dia. 45in., admits in dia. 70in., h.p. motor 15.

ORMEROD 21in. table dia. 41in., admits in dia. 72in., h.p. motor 15.

BUTLER 12in. High Production, table dia. 30in., admits in dia. 44in., h.p. motor 7½.

ORMEROD 12in., unused; table dia. 30in., admits in dia. 50in., h.p. motor 8.

MUIR 12in., table dia. 32in., admits in dia. 44in., h.p. motor 7½.

BUTLER 8in. High Production, table dia. 20in., admits in dia. 24in., h.p. motor 5.

ORMEROD 8in., table dia. 18in., admits in dia. 30in., h.p. motor 4.

All with automatic and hand, long/cross and rotary table movements.

Offered as purchased or fully rebuilt.
Inspection invited.

It's Cheaper to Buy Now

**SOAG MACHINE TOOLS LTD.,
JUXON STREET, LAMBETH, LONDON, S.E.11.**

'Phone: REliance 7201.

'Grams: Sotoolag, London, S.E.11.

AT LAST!

A PRECISION
SURFACING
AND BORING
ATTACHMENT
ADJUSTABLE
WHILST IN
MOTION
IN 3 SIZES



Capacities : 6in., 10in. and 14in. diameter facing

D'ANDREA

PATENT

UNIVERSAL BORING FACING & TURNING ATTACHMENT

Direct reading to 0.0005in., hand and two rates auto feed, automatic stop, all for operation whilst rotating.

Fits any Jig Borer, Horizontal or Vertical Miller, Horizontal Borer, Drilling Machine, etc.

SOLE AGENTS:

HERBERT WIDDOWSON & SONS LTD
CANAL STREET WORKS · NOTTINGHAM

PHONE: NOTTINGHAM 42061 (3 LINES)

Kent-Owen Production Miller.

Auto. cycle. Table 32in. x 9in. o/a. Kneeless type. Motorised.—WILCOX & CO., Barr Street, Birmingham 19. Northern 1234/5.

R. E. Ormerod Ltd., Bromsgrove

2411—offer one Archdale 18in. Vertical Milling Machine, 2,000 r.p.m., at £825, or will go to the best offer made within the next three weeks. Seen working, any trial.

One Motorised Single Spindle

Herbert Drilling Machine.
One High Speed Deep Throated Drilling Machine for sheet metal work.

One 6in. Denham Centre Lathe.

All nearly new, with double spindle hand grinder and two new 4in. vices.
Bargain, £275 or near offer.—BOX Z14, MACHINERY, Clifton House, Euston Road, N.W.1.

Norton Surface Grinder, 6in. by

18in. Hydraulic feed to table. Machine as new.—BOX Z27, MACHINERY, Clifton House, Euston Road, N.W.1.

Nearly New, 1,000 Ton Eumuco

Coining and Sizing Press, 2in. stroke, 31in. between sides. Air operated clutch and brake, with 40 h.p. motor drive. Heavy Steel Plate construction.

160 ton Hordern, Mason & Edwards high speed Friction Screw Press, type 4 SP, 18in. effective stroke, 21in. tool space, 6in. dia. screw. 10 h.p. motor drive.

REED BROTHERS (ENGINEERING), Ltd.,

Replant Works,
Woolwich Industrial Estate,
London, S.E.18

Telephone: Woolwich 7611/6.

When answering advertisements kindly mention **MACHINERY**.

NORTON

FOR "NEARLY NEW"

OFFER FROM STOCK— AUTOMATICS

WICKMAN 5-spindle Bar Automatics 1½in. capacity. Serial Nos. 42346/5.
BROWN & SHARPE OOG Bar Automatic, Vertical Slide, Bar Strand, turret, tools, collets. Serial No. 12715.

BORER

RICHARDS 48in. Double Upright Vertical Boring and Turning Mill, two swivelling toolboxes on cross slide.

CAPSTAN & TURRET LATHES

WARD 2A Bar Capstan Lathe, fitted collet chuck, speeds 71 to 1,541 r.p.m. War-time manufacture.
HERBERT 4BS Bar Capstan Lathe, fitted turret toolholders, pump, bar feed, speeds 30 to 511 r.p.m.
WARD No 7 Bar Capstan Lathe, bar feed, speeds 20 to 416 r.p.m.
HERBERT No. 20 Combination Turret Lathe, 7½in. diameter spindle, 28in. swing over bed, 97in. distance spindle to turret. Speeds 5 to 201 r.p.m.

CENTRE LATHES

LE BLOND Heavy Duty 33in. swing by 28ft. between centres, S.S. & S.C. Lathe, late type, all geared headstock, twin saddles, taper turning, 32in. diameter, four-jaw chuck, 25 h.p. A.C., 3-phase electric, speeds 4 to 255 r.p.m.
BROADBENT 14in. S.S. & S.C. Gap Bed Lathe, admits 90in. swings in gap 50in., speeds 5.5 to 204 r.p.m. Well equipped Nearly New.
BINNS & BERRY 12½in. S.S. & S.C. Gap Bed Lathe, admits 7ft. 6in. between centres, speeds 12 to 600 r.p.m. NEW.
COLCHESTER MASCOT 8½in. by 54in. All-gear Head Centre Lathe, speeds 37 to 600 r.p.m. NEW.
COLCHESTER TRIUMPH 7½in. by 48in. All-gear Head Gap Bed Lathe, speeds 40 to 800 r.p.m. NEW.
DEAN SMITH & GRACE Model "AN" 7½in. by 48in. S.S. & S.C. Straight Bed Lathe, speeds 11 to 490 r.p.m. Serial No. 20300.
WILLSON Mark V 7½in. by 48in., S.S. & S.C. Gap Bed Lathe, admits 48in., speeds 54 to 954 r.p.m. and 37 to 739 r.p.m. NEW.
DEAN SMITH & GRACE Type "A" 7in. by 31in. S.S. & S.C. Gap Bed Centre Lathe, speeds 11 to 490 r.p.m. Serial No. 21303.

REIDEN 7½in. by 40in. S.S. & S.C. Gap Bed Toolroom Lathe, fitted taper turning attachment, pump, 3-jaw chuck, speeds 25 to 1,350 r.p.m. NEW.

MITCHELL 6½in. by 64in. S.S. & S.C. Gap Bed Centre Lathe, taper turning attachment, speeds 27 to 400 r.p.m. Nearly New.
MYFORD Super Seven Lathe, 3½in. by 19in., speeds 25 to 2,150 r.p.m. NEW.

DRILLING MACHINES

RICHMOND S.R.2 36in. Radial Drill, elevating table, suds pump. NEW.
JONES & SHIPMAN 30in. Model 921, 2-spindle Manufacturing Drilling Machine. 1½in. capacity, speeds 39 to 825 r.p.m. Table 42in. by 24in.
PROGRESS 3A Pillar Drilling Machine, Circular table. NEW.

THIS WEEK'S SPECIAL

Machine Tool
Values
Competition;
apply for
Illustrated Stock
List
giving particulars

GRINDERS

JONES & SHIPMAN 18in. by 6in. capacity Hydraulic Horizontal Spindle Surface Grinder, Model 540. Nearly New.

All machines motorised 400-440 volts, 3 phase, 50 cycles, A.C. supply.
Sole London and South of England agents for BRONX Press brakes.

BURDETT Hydraulic Horizontal Spindle Surface Grinder, capacity 18in. by 6in. by 10in. NEW.

LANDIS Hydraulic Universal Grinder, type "C", capacity 10in. by 24in. Serial No. 27916.

MYFORD M.G.12 Plain Cylindrical Grinder, capacity 5in. by 12in. NEW.

MILLING MACHINES Vertical

CINCINNATI No. 4 Dial Type Vertical Milling Machine, table 78½in. by 16½in. rapid and power traverses 42in. by 16in. by 16in. Speeds 18 to 1,300 r.p.m. British built 1941.
BIERNATSKI No. 5 Swivel Head Vertical Milling Machine, table 78in. by 19in., traverses 49in. by 15in. by 35in.
CRAVEN Swivel Head Vertical Milling Machine, table 47in. by 13in., traverses 42in. by 7in. by 12in., speeds 41 to 1,188 r.p.m.

Universal

CINCINNATI No. 4 Dial type Universal Milling Machine, table 78½in. by 16½in., rapid and power traverses, 42in. by 14in. by 19in. Speeds 18 to 1,300 r.p.m. With Universal Vertical Attachment. British built 1947.
REIDEN H.F.30 Universal Milling Machine table 59in. by 14½in., rapid and power traverses 39in. by 11½in. by 15½in., speeds 44 to 1,457 r.p.m. NEW.
VICTORIA U.2 Universal Milling Machine, table 45in. by 11in., power feeds 29in. by 65in. by 16in., speeds 30 to 1,010 r.p.m. NEW.
RICHMOND No. 3 Universal Milling Machine, table 48in. by 11in., rapid and power traverses 30in. by 8in. by 16in., speeds 20 to 1,000 r.p.m. NEW.
DENBIGH C.4 Universal Milling Machine, table 46in. by 10in., automatic longitudinal feed 36½in., speeds 13 to 400 r.p.m. NEW.

Horizontal

ARCHDALE 20in. Plain Horizontal Milling Machines, table 40in. by 10in., traverses 20in. by 5½in. by 12in., speeds 30 to 615 r.p.m.
CINCINNATI 1/12 Automatic Milling Machine, table 35in. by 10in., speeds 50 to 1,500 r.p.m. British built.

W. E. NORTON (MACHINE TOOLS) LTD
GROSVENOR GARDENS HOUSE, GROSVENOR GARDENS, LONDON, S.W.1
Telephone: TATE Gallery 0633-45
Showroom & Stores: Bridge Works, 342 Queenstown Road (Close Chelsea Bridge) Battersea, S.W.11
Cables: Norbros, London

When answering advertisements kindly mention MACHINERY.

NEW MACHINES

MITCHELL 12 $\frac{1}{2}$ in. Lathe, 10ft. 9in. between centres, 4 $\frac{1}{2}$ in. hollow spindle. Equipment. **MYFORD** MG12 Cylindrical Grinder, 3 x 12 $\frac{1}{2}$ capacity. Full equipment. **MIDGLEY & SUTCLIFFE** O3SD Universal Miller. Universal Dividing Heads. **COLCHESTER** 'Mascot' 8 $\frac{1}{2}$ in. x 54in. Lathe. With equipment. **GRANOR** Type HL 11in. Gap Bed Lathe. 5ft. between centres. Full equipment. **COLCHESTER** 'Triumph' 7 $\frac{1}{2}$ in. x 40in. Lathe. Coolant, fourway toolpost, etc. **MITCHELL** 8 $\frac{1}{2}$ in. Gap Bed Lathe, 4ft. 3in. between centres, fourway toolpost, chucks, etc. **VICTORIA** U3 Universal Miller, 60in. x 12 $\frac{1}{2}$ in. table, rapid traverse. **MODERN** 2C 1 $\frac{1}{2}$ in. capacity Capstan. Complete with bar feed. **SMART AND BROWN** Model 'A' 4 $\frac{1}{2}$ in. S.S. & S.C. Precision Toolroom Lathe. **HARRISON** 8in. x 40in. Lathe. Fourway toolpost, chucks, steadies, etc. **MODERN** 18in. x 6in. Fully Automatic surface Grinder, 12in. wheel to table.

**USED MACHINES**

VAN NORMAN Vertical Miller, 56 x 10 $\frac{1}{2}$ in. table, Power and rapid traverse all directions. Very good condition. Price £1,150. **WILSON** Nawel 7 $\frac{1}{2}$ in. Lathe. Fourway Toolpost chuck, etc. Late machine, excellent condition. Price £345. **WARD** No. 7 Capstan. Fully equipped. Levers and nuts Arranged as chucking machine. Good order. Price £550. **REINECKER** FV1 Vertical Miller, 43in. x 10in. table. 20in. between spindle and table, dial change, as new condition. Price £1,050. **LUND** Precimax MPL 6 x 36 Grinder, 20 x 4 wheel. Coolant equipment, etc. Price £525. **HERBERT** Small piece Lathe. Type 6WSL 12in. swing two tailstocks. Price £110. **ADCOCK & SHIPLEY** 3 $\frac{1}{2}$ in. Radial Drill. Power feed to spindle. Coolant equipment. Good condition. Price £335. **HERBERT** 2B Capstan. Collet attachment, chuck bar feed, tooling, etc. Price £300. **DELAPENA** Model MA Bench Honer, 0-185 to 2-625 capacity. Price £50. **MITCHELL** 14 $\frac{1}{2}$ in. Lathe. 7ft. 9in. between centres. 4 $\frac{1}{2}$ in. hollow spindle. Equipment. Overhauled. Price £1,950.

MODERN

**GOSFORD
STREET
COVENTRY
TEL. COVENTRY 2138**

MACHINE**TOOLS LTD**

**GOSFORD
STREET
COVENTRY
TEL. COVENTRY 2138**



STIRK "PIONEER," 8ft. x 3ft. 6in. x 3ft. double column Planing Machine. All electric split-field drive with two tool heads on cross rail; tool lifts; cutting speeds up to 240 r.p.m. Modern machine, unused.

CHURCHILL-REDMAN 14ft. x 3ft. 6in. x 3ft. 6in. double column, Lancashire Dynamo drive, two tool heads on cross rail and two side heads, push button and control panel. In sound working order and condition.

Full particulars from:—

**SOAG MACHINE TOOLS LTD.,
JUXON STREET, LAMBETH, LONDON, S.E.11.**

'Phone: RELiance 7201.

'Grams: Sotoolsag, London, S.E.11.

Centreless Grinding Machine,
B.S.A. Max. capacity 3in. dia. Electrics 400/3/50. Excellent condition.—BOX V985, MACHINERY, Clifton House, Euston Road, N.W.1.

New Abene Combined Horizontal and Vertical Milling Machine for stock delivery, table 40in. x 10in. Widely used for diesinking. £1,525.—MORTIMER ENGINEERING COMPANY, 202-206, Acton Lane, London, N.W.10.

Hasse & Wrede Heavy Duty carbide tool comb, turret lathe, 1952 manufacture. 18 $\frac{1}{2}$ in. swing. 59in. between spindle and turret face. 18 speeds preselected 18/900 r.p.m. 9 feeds. 3 $\frac{1}{2}$ in. dia. through spindle or 2 $\frac{1}{2}$ in. dia. with hydraulic chucking. Turret accepts Herbert tooling 400-440 electrics. Can be seen working, £1,200 or near.—ROBERTSONS (ENGINEERS), LTD., New Street, Horsforth, Leeds.

Radyne 6-kW Induction Heater with pump and accessories, £850.—HARDEN PRECISION ENGINEERING CO., LTD., Manor Estate, Church Road, Thundersley, Essex.

Blanchard No. 10 Rotary Table Surface Grinder. 16in. dia. mag. table. 10in. dia. cup wheel. Motorised.—WILCOX & CO., Barr Street, Birmingham 19. Northern 1234/5.

Facing Lathe "VDF" Face Plate, diam. 5ft., swing 6ft. diam. over bed, admit 20ft. between centres. Motorised. (1942) good condition.—Further details from DR.-ING. EMIL LINGEMANN, Rather Str. 49, Dusseldorf, Germany.

Brown & Sharpe 00 and 0 H.S. Automatics, ex. cond., also No. 0 and 2 Reg. B.S.A. 1 $\frac{1}{2}$ in. long stroke, third slide, Brown and Ward 1 $\frac{1}{2}$ in. 4-Op. Threader, Mot.—C. L. THOMAS, LTD., 18 Park Avenue, Solihull 1281.

Sweeney & Blocksidge 25-ton column press, adj. stroke. Mot. current model in first class condition. Half list price, also Bliss inclinable 15 ton. Mot. £95.—C. L. THOMAS, LTD., 18 Park Avenue, Solihull 1281.

Victoria U2 Miller, Scarcely used, 40in. x 11in. Univ. dividing head, change wheels, vert. att., Slitting att., rotary table, swivel vice.—Offers: C. L. THOMAS, LTD., 18, Park Avenue, Solihull 1281.

1 Die Casting Machine EMB. No. 9, cold chamber, in excellent condition.—Inspection invited.—Offers: BOX Z3, MACHINERY, Clifton House, Euston Road, N.W.1.

Ward 3A Capstan Lathe, Serial 86100, fitted with 7 $\frac{1}{2}$ in. 3-jaw airchuck and control gear, power feeds to turret, speeds 59 to 1,155, electric coolant pump, self-contained machine, 400-440/3/50, very good condition. £250.—E. SMITH (MACHINE TOOLS), LTD., 76, St. Lukes Road, Birmingham, 5. Tel.: CALthorpe 3761.

4 mm. Wickman Automatic Machine Vinco A.C.W. 5 slides. Slitting, Drilling and Threading attachment. 50/3/400. Speeds 1,500-12,000. Very good condition. £245.—BOX V987, MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

-BETTER TRY 600 FIRST!

for NEW AND USED PRESSES & SHEET METAL MACHINERY

Unused RUSHWORTH 8ft. by 4in. M.S. Overcrank Double Geared Drive Guillotine Shearing Machine with cam operated plate hold down, 6in. gap in end frames.

Unused RUSHWORTH 6ft. by 4in. M.S. Overcrank Double Geared Drive Guillotine Shearing with cam operated plate hold down, 6in. gap in end frames.

New PEARSON 10ft. by 4in. Electro Hydraulic Guillotine Shearing Machine with 12in. gap in end frames.

New PEARSON 8ft. by 4in. Electro Hydraulic Guillotine Shearing Machine with 12in. gap in end frames.

Unused RUSHWORTH 150/8 All Steel Frame Press Brake, forming capacity 8ft. by 4in. M.S. Distance between columns 97in. Overall bed 114in. Die space ram down 12in. Gap in end frames 10in.

Unused RUSHWORTH 75/8 All Steel Frame Press Brake, forming capacity 8ft. by 4in. M.S. Distance between columns 97in. Overall bed 108in. Die space ram down 12in. Gap in end frames 9in.

Unused PELS MB.22 All Steel Combined Punching, Shearing and Section Cropping Machine, capacity in mild steel, shear 4in., punch 1 1/2in. through 3in. Crop 6in. by 6in. by 4in., angles at 90° or 4in. by 4in. by 4in. at 45°, 2 1/2in. rounds, 2in. squares.

New WEYBRIDGE MS.48 Medium Type Rotary Gang Slitting Shear. Max. capacity 6-cuts in 48in. by 4in. mild steel.

New STECO 6ft. by 4in. Pyramid Type Plate Bending Rolls, 7 1/2in. dia. Top Roll, 6 1/2in. dia. Bottom Rolls.

New STECO 8ft. by 4in. Pyramid Type Plate Bending Rolls, 8 1/2in. dia. Top Roll, 7 1/2in. dia. Bottom Rolls.

Three-Used RHODES 7 1/2/72 Straight Side Double Crank Geared Power Presses, capacity 200-tons. Bed area 72in. by 50in. Stroke 12in. Complete with 'Worson' Air Cushion equipment.

Used TAYLOR & CHALLEN 7 1/2 Double Action Geared Toggle Drawing Press. Punch stroke 20in. Blankholder stroke 10in., 44in. between uprights.

All arranged for Motor Drive 400-440/3/50.

**GEORGE COHEN
SONS & COMPANY LIMITED**
Sunbeam Road, London, N.W.10
Tel: Elgar 7222/7

Classified Advertisements (PLANT FOR SALE, contd.)

Universal Grinding Machine, with Internal and External Wheel Spindle. Hydraulic feed to table. Precimax model UPH. 10in. by 24in. Electrics 400/3/50. In excellent condition.—BOX 235, MACHINERY, Clifton House, Euston Road, N.W.1.

HARRY KIRK

can recommend the following modern quality machines from STOCK:

KEARNS No. 2 HORIZONTAL BORING, MILLING, DRILLING AND FACING MACHINE. 3in. sliding spindle, 20in. dia. facing head. Size of top table 48in. by 48in.
SWIFT 4ft. RADIAL DRILLING MACHINE. Elevating arm, box table.
BROWN & SHARPE HORIZONTAL SPINDLE SURFACE GRINDING MACHINE. Capacity 18in. by 6in.
HERBERT No. 4 AUTOMATIC CHUCKING LATHE.
PARKINSON No. 3J UNIVERSAL MILLING MACHINE.
PRATT & WHITNEY 12in. STROKE SLOTTING MACHINE. Tilting ram.
MODERN OPTICAL PROFILE GRINDING MACHINE.
LANG JUNIOR CENTRE LATHE. Capacity 6 1/2in. centre height by 30in. between centres.
CHURCHILL-REDMAN HEAVY DUTY SHAPING MACHINE. 24in. stroke, swivelling vice, 10 h.p. motor.
BUTLER 8in. STROKE SLOTTING MACHINE. with tilting table.
B.S.A. 9in. SINGLE SPINDLE CHUCKING AUTOMATIC. Complete with air-operated chuck.
KITCHEN & WADE VERTICAL FINE BORING MACHINE. 14in. stroke. Compound table.
KITCHEN & WADE HEAVY DUTY PILLAR DRILL. No. 5 Morse. Speeds 22-1,000 r.p.m.
CHURCHILL 12in. by 36in. UNIVERSAL HYDRAULIC GRINDING MACHINE.

Further details from

**HARRY KIRK
ENGINEERING LTD.**
BRANDON ROAD WORKS, BRANDON ROAD, COVENTRY.
Phone: WALGRAVE-ON-SOWE 2213/4

Kendrick Press Brake, 6ft. by 18in. capacity in steel, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

**Scrivener No. 2 Centreless
Grinder Reconditioned, with
Hydraulic Wheel Trimmer.
Motorised 400/3/50.**

**THE SURPLUS MACHINERY & STORES
CLEARING HOUSE LTD.**

108 East Hill, Wandsworth,
London, S.W.18
Phone: Vandyke 3266-7-8

**E. H. Jones No. 55 (New) Vertical
Milling Machine, table 32in. by 11in.,
motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught
Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.**

EX STOCK

New MODERN 2C Capstans, 1 1/2in. bar feed.
Used WARD 1A Capstan, 1in. bar feed.
New CHIPMASTER 5 x 20 High Speed Precision Lathes.
New STUDENT 6 x 24 Lathes.
New WILLSON 7 1/2in. Mark V Lathe.
New PROGRESS 4E Pillar Drill, 1 1/2in.
New G. & S. Pillar Drill, 1 1/2in.
New G. & S. (Kerry) Radial Drill, 3ft. x 1 1/2in.
New RICHMOND Radial Drill, 4ft. x 2in.
Selection of Bench and Pillar Drills, 4in. to 1 1/2in.
New SMART & BROWN Precision Lathes, Models M.L. and SABEL.
New SENIOR Horizontal Millers, M1.
New DENBIGH Horizontal Millers, C4. Latest variable feed.
New E.H.J.55 Vertical Miller.

C. H. JOYCE LTD

32-40, Monkton St. (Kennington),
London, S.E.11.

REliance 1437-9.

Many other machines of various types available also, please ask for Stock list.

NORTON 12in. by 36in. Universal Grinder, hydraulic, motorised 415/3/50. With internal grinding attachment, and other useful equipment.
HERBERT HUNT Horizontal Surface Grinder, 6in. by 18in., with wheel truing device and dust extraction unit, 415/3/50.
LUKE & SPENCER type Double Ended Grinder, wheels 16in. dia. by 2in. wide. 415/3/50.
FIRTH-BROWN Twist Drill Grinder, capacity up to 4in., with quantity of drill bushes. 415/3/50.
KEARNS No. 0 Production type Horizontal Borer with 2in. dia. traversing spindle. Top table 30in. by 36in.
BULLARD 38in. Vertical Boring and Turning Mill. Twin columns. Pentagon turret and one plain swivel toolpost. S.P. drive.
HERBERT No. 95 Combination Turret Lathe. 415/3/50. 4 1/2in. hollow spindle. Good equipment.
WARD No. 8 Combination Turret Lathe. 415/3/50. 4 1/2in. hollow spindle, taper turning attachment.
PITTLER H.R.A. Turret Lathe, arranged for bar feed and chucking. Bar capacity 4 1/2in. 415/3/50.
WARD No. 2A and 3A Capstan Lathes with bar feed and automatic ball chucks, power feed to turret and saddle. 415/3/50.
CLIFTON & WADDELL 36in. Heavy Duty Metal Bandsawing Machine with two movable tables 21in. by 40in. 415/3/50.
RAPIDOR 20in. Power Hacksawing Machine.
RAPIDOR 10in. Power Hacksawing Machine. 415/3/50.
RAPIDOR 8in. Power Hacksawing Machine. 415/3/50.
Etc., Etc.

R. O. Gray

46, Minerva Road, Park Royal,
LONDON, N.W.10.
Telephone: ELGar 4841/2.

When answering advertisements kindly mention MACHINERY.

MIDLAND

ACME GRIDLEY 1in. cap. six spindle bar auto. Bar feed, collets, tooling and live spindle.

BROWN & SHARPE 2G Auto. 1in. cap. Bar feed and tooling.

HERBERT Junior Chucking Auto. 6in. swing. Very well equipped.

FISCHER K.D.M. 11/70 Copying Lathe. Automatic. 1954 machine.

LANG 15in. by 15ft. S.S. & S.C. Lathe.

BROWN & SHARPE No. 2 Universal Grinder. 14in. swing by 28in. b.c. Well equipped. First class condition.

PILKINGTON 5-cwt. Air-operated Power Hammer. Almost new.

HARRISON 7in. by 4ft. S.S. & S.C. Gap Bed Lathe. Full equipt. and taper turning. As new. 1956 machine.

MILWAUKEE 2 C.E. Horizontal Miller. Vertical and slotting heads. Speeds to 2,000 r.p.m. As new. 1954 machine.

1952 BIERNATZKI Heavy Duty Horizontal Miller. Speeds 29 to 1,500 r.p.m. Quick Power all ways. As new condition.

HERBERT No. 7 Combination Turret Lathe. Screwcutting. 2½in. hollow spindle.

HERBERT 21 Combination Turret Lathe. 34in. swing. 7½in. hollow spindle. Screwcutting and taperturning.

HILLE Leadscrew Type Thread Miller. Six cutter spindle speeds. 64 to 177 r.p.m. Well equipped. First-class condition.

CHURCHILL-REDMAN 15in. C.H. by 7ft. 6in. b.c. Heavy Duty S.S. & S.C. Gap Bed Lathe. 34in. swing in gap. 5½in. H/Spindle.

HERBERT No. 4 Capstan A.G.H. eight speeds. 30 to 750 r.p.m. Covered bed.

Unless otherwise stated all above motorised 400/3/50.

THE MIDLAND MACHINE TOOL CO.

BRADLEY, BILSTON, STAFFS. Bilston 41953.

G. M. BUCKINGHAM LTD.

New Machines for delivery ex-stock

LATHES

COLCHESTER 5in. Chipmaster, 6in. Scudent, 6½in. Master, 7½in. Triumph and 8½in. Mascot.

WILLSON 6½in. Mark I, 7½in. Newel and Mark V, and 8½in. Fidel.

CARDIFF 7½in. to 11in., various bed lengths.

MILLING MACHINES

VICTORIA Omnimis, Models O1 and O2, both with Hilger and Watts Optics.

Also all other Victoria Universal and Vertical Models.

DENBIGH Model C4 semi-Universal, 46in. x 10in.

RICHMOND H.S. Turret Mill.

SHAPING MACHINES

NEW INVICTA "Major" Shapers, 30in. and 24in., with swivel table and auto downfeed.

Also other standard INVICTA and ALBA Models, 10in. to 24in.

DRILLING MACHINES

RICHMOND 4ft. 6in. Radial Drill, Model HB3/12, 2in. cap. with coolant equipment.

RICHMOND 36in. Radial Drill, Model SR2, 1½in. cap. with power elevation and coolant equipment.

PROGRESS 5E 2in. cap. Pedestal Drill.


PROGRESS 4E 1½in. cap. Pedestal Drill.

GRINDING MACHINES

MYFORD/MG12 Cylindrical Grinder, cap. 5in. by 12in.

EXCEL Model 3/12 Hydraulic Surface Grinder, 24in. by 8in.

8, Clarendon Ave., Leamington Spa.
Telephone 1215



NEW MACHINES EX STOCK FOR IMMEDIATE DELIVERY

COLCHESTER Lathes, Mascot, 8in. by 60in.

TRIUMPH 7½in. by 48in.

STUDENT 6in. by 24in.

CHIPMASTER 5in. by 24in.

"ACE" Bench Lathe, 4½in. centres by 23in. between. Norton feed box and on cabinet stand. 415/3/50.

ROBLING Lathe, Model 600/2, 5½in. centres by 24in. between, 1,920 r.p.m., accuracy 0.0002in. 415/3/50 A.C.

PELFER Precision Toolroom Lathe, Model P.12, 9in. centres by 44in. between, 1,000 r.p.m. Norton feed box, 187 threads Whitworth, metric and module, turning accuracy 0.002mm., 415/3/50 A.C.

TROGLA Lathe, Model TPM20, 10½in. centres by 76in. between, 31in. in gap, 850 r.p.m., Norton feed box, Whitworth, metric and module. 415/3/50 A.C.

GRANVILLE SENIOR 3½in./4in. H.D. Bench Centre Lathe, 21in. b.c. Motorised.

ASTRA 6in. Stroke Slotting Machine, 4 speeds to ram, compound table. Mot. 415/3/50.

SENIOR M.1 Horizontal Milling Machines, Table 25in. by 6½in. W/S, longt. power feed, spindle speeds 12, 50/1,650 r.p.m., coolant pump. Motorised 415/3/50.

P.T.V. Universal Mill, Model 51, Table 33½in. by 8½in. power feed, 60/1,200. Dividing heads, etc. 415/3/50.

P.T.V. Vertical Mill, Model IV, Table 39in. by 8½in. power feed all directions, swivel head, rise and fall, speeds 60/1,400, dial change. 415/3/50.

ASTRA Vertical Mill, Table 23in. by 8in., hand feeds to table in all directions. No. 8 Morse spindle. Motorised 415/3/50.

FIVE STAR Tool and Cutter Grinder, capacity 5in. by 12½in., with motorised workhead for external and internal grinding. 415/3/50.

PLEASE ADDRESS YOUR ENQUIRIES TO DEPARTMENT "P."

WILLIAM URQUHART

1023-1027, Garratt Lane, London, S.W.17

'Phone: WIMbledon 6341

MACHINE TOOLS

SELECTIONS FROM LARGE STOCKS

NEW MITCHELL 16½IN. CENTRE × 24FT.

GAP BED LATHE
Admit between centres .. 17ft. 3in.
Swing over saddle .. 25in. dia.
Swing in gap .. 61in. dia. × 18½in.
Hollow spindle dia. .. 4½in.
Spindle speeds (8) .. 8 to 160

NEW MITCHELL 14½IN. CENTRE × 16FT.

GAP BED LATHE
Admit between centres .. 9ft. 9in.
Swing over saddle .. 21½in. dia.
Swing in gap .. 32in. dia. × 17in.
Hollow spindle dia. .. 4½in.
Spindle speeds (8) .. 8 to 250

FOUR CINCINNATI NO. 0-8 AUTOMATIC

HORIZONTAL MILLING MACHINES
Automatic table feed cycle and rise and fall spindle carrier.

Table working surface .. 18½in. × 6½in.
Power longitudinal traverser .. 8in.
Vertical adjustment of spindle carrier .. 4½in.
Cross adjustment of spindle quill .. 1in.
No. of spindle speeds, with full set of gears .. 10
Range .. 75-1,100 r.p.m.

NEW G.S.P. 9FT. RADIAL DRILLING, TAP-

PING AND BORING MACHINE
With pump and loose box table.

Spindle .. No. 6 Morse taper
Capacity in cast iron .. 4½in.
Capacity in steel .. 3½in.
Tapping capacity .. 3in.
Spindle feed .. 18½in.
Max. dia. spindle to baseplate .. 6ft. 3in.
Column dia. .. 23½in.
Traverse of saddle along arm .. 6ft. 8 in.
Spindle speeds .. 5-1,725 r.p.m.
Working surface of baseplate .. 9ft. 1in. × 4ft. 7in.
H.P. of main motor .. 12
Weight approx. .. 11½ tons.

BILLETER 4-MOTOR TWIN HEAD RADIAL

ARM OPEN SIDED HYDRAULIC SLIDE- WAY GRINDER

One head carries vertically mounted segmental wheel; other is lighter, with swivel adjustment; rapid power traverse for raising and lowering; push button control; infinitely variable table speeds.

Approximate dimension
Overall size of table .. 9ft. 5in. × 2ft. 3in.
Speed of table .. 6ft. 6in. to 38ft. per min.

Max. grinding length .. 6ft. 6½in.
Max. grinding width .. 2ft. 3½in.
Dia. of segment wheel .. 19in.
Weight .. 6½ tons
Humphrey magnetic chuck .. 6ft. × 1ft. 6in.

WANDERER MODEL 31L 1000 MOTORISED

UNIVERSAL LONG THREAD MILLING AND HOBBING MACHINE

For internal and external threads, helical and parallel splines, worms, etc.

Length of hob spindle travel .. 39½in.
Height of centres .. 6½in.
Maximum swing over saddle .. 8in.
Maximum work dia. over bed .. 16½in.
Dia. of hollow spindle .. 3½in.
Pitch of leadscrew .. ½in.
Number of cutter spindle revs. .. 55, 80, 118, 170, 250 r.p.m.
Range of cutter rev. .. 55, 80, 118, 170, 250 r.p.m.

No. of feeds per rev. .. 82

OMEROD 26IN. STROKE HEAVY DUTY HIGH

SPEED SLOTTING MACHINE

With power feeds and rapid traverses to table in all directions.

Max. dia. admitted .. 7ft. 2in.
Max. height admitted .. 3ft. 6in.
Working surface of table .. 50in. × 50in.
Longitudinal traverse of table .. 3ft. 9in.
Cross traverse of table .. 3ft. 4in.

F. J. EDWARDS LTD.

359-361 EUSTON ROAD, LONDON, N.W.1.
Telephone: EUston 4681-3771.

and at
41 WATER STREET, BIRMINGHAM, 3.
Telephone: Central 7606-8.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



PIDGEN BROS. LIMITED

HELMET ROW, OLD STREET, LONDON, E.C.1.

Telephone: CLerkenwell 6481



ALL MACHINES MOTORISED FOR 3 PHASE SUPPLY UNLESS OTHERWISE STATED

AUTOMATICS

CONOMATIC 4 Spindle.
INDEX OR/12 4in. capacity.
CLEVELAND 14in. by 18in. Model B.

CAPSTANS

WARD No. 8 Combination. Serial R.
TURNER 14 A.
WARD 2A, Serial WT and 3A Serial M.
GISHOLT No. 4 Simplified. 2in. cap.
GRUMMOND Model K, 14in. Bar feed.
HILLE R.M. 15in. Bar feed.
ACCURATOOL 4in. Bar feed.
WARNER & SWASEY No. 2 1in. Bar feed.
HERBERT No. 7 Combination Turret.
ACME SW Universal Turret, 2in. bar feed.
LIBBY 4A 2in. bar feed.
MURAD 4in. bar feed.
HAHN & KOLB RH25 1in. bar. Unused.
SOUTHWARK No. 2 14in. bar feed.

DRILLS

JONES & SHIPMAN 2-sp., 15in., No. 2 M.T.
HERBERT Type V 2 spindle.
GRIMSTON Electrica.
DENBIGH 21in. B.G. New.
JONES & SHIPMAN 15in. Speed Drill-Max.
HERBERT Type H Junior Pillar.
CORONA 12AX 4in. cap.
BOLEY Cluster Type.
BRIDON 4in. 2 Spindle.
ARCHDALE 20in. Mfg.
15in. HERBERT Type C, No. 3 M.T.

ENGRAYERS

T.M.A. Type G.3
LIENHARD New. All sizes.
T.T.H. Multi Etcher and 3 D.S.
FILE AND SAWING MACHINES
VELOX 10in. Hackaw.
TAYLOR Cutting Off Machine.
EDGWICK Filer.
RAPIDOR No. 1 Hackaw.
THIEL No. 17 Bandaw.
WICKSTEED Cold Saw No. 1, 6in
GEAR CUTTERS
SYKES HV 14 Hobber.
PETERMANN No. 2.
MAXICUT 7in. by 2in. by 6 D.P.
RAPIDAN No. 14, 21in. dia. gears.
FELLOWS "Hourglass."

GRINDERS (Cylindrical)

PRECIMAX MPH 10 by 48.
MYFORD MG.12. New.
PRECIMAX MPH Plain. 10 by 24.
PRECIMAX U.P.J.-Universal. 12 by 48.
NORTON 6 by 18 Hyd. Type C.
NORTON 10 by 36. Type C.
GRINDERS (Miscellaneous)
J. & S. 12in. by 24in. 305 T. & C.
EXCEL T. & C.
SCRIVENER No. 1 C.B. Centreless.
JONES & SHIPMAN Carbide.
HERBERT HUNT No. 1A, 3 & 4 Drill.

GRINDERS (Surface)

ABRASIVE No. 14 15 x 10.
WRIGHT 8in. Table.
ROBOT 18 by 6.
SNOW P24, 24in. by 8in., Hyd.
ABWOOD 18 x 6 Vertical.
P. & W. Vertical Spindle, 36 by 14.

GRINDERS (Internal)

SMART & BROWN.
SAACKE Model VII, Jig.
GUILLOTINES
RUSHWORTH 3ft. Treadle.
KEETONA 4ft. Treadle.
KEETONA 4ft. x 14G. Power

HONER

SUNNEN Type LA.

KEYSEATERS

EDGWICK No. 1.
CARTER & WRIGHT No. 2, 24in. by 14in.

LATHES

COLCHESTER MASCOT 84in. by 6ft. 6in.
COLCHESTER Triumph.
EDWARDS 12in. Spinning.
WILLSON 74in. by 3ft., S.S. & S.C.
BRADFORD 8in. S.S. & S.C.
RYDERMATIC No. 12 Multi Tool.
CARDIFF 7in. by 60in.
DENHAM 54in. S.S. & S.C.
LE BLOND 11in. by 16in. Prod.
SOAG-OXFORD 64in. by 24in. S.S. & S.C.
SOUTH BEND 9in. (Workshop), 13in. and 14in.
SMART & BROWN 4in. S.C.
10in. GLASS 7ft. 6in. b.c. S.S. & S.C.
LEBLOND Regal 10in. swing.

MILLERS (Horizontal)

BURNERS Bench. Table 14 1/2 x 4.
U.S. (Whitney Type) Production.
VICTORIA M2. Table 40 x 10.
KEMPSMITH No. 1G and 2G.
BROWN & SHARPE No. 12 and 000 Prod.
CINCINNATI 08. & 1-18 Prod.
BROWN & SHARPE No. 2 Univ. Light
CENTEC No. 2. Table 12in. by 34in.
SUNDSTRAND No. 00 Rigidmill.
BURKE. Table 16 x 34.
ARCHDALE 28in. Mfr. and G.P.
CINCINNATI 3-24 Hyd.
HERBERT IS. Table 18in. by 84in.

MILLERS (Vertical)

RICHMOND VHM. Table 26 x 8.
VICTORIA V2. Table 40 by 10.
ARCHDALE 30in. Table 48 by 124
HERBERT IS5. Table 50 by 104.

PRESSES (Power)

BLISS No. 8.
BESCO TWO Bench, 4 ton.
O. & S. 30 tons straightening.
BESCO EB4, 40 tons. New.
TAYLOR & CHALLENGE B2, 10 ton.
RHODES No. 19. 10 ton.
SCHULER VZZ 15 ton d/s gripper feed.

RIVETERS

ROTORIVET No. 5 Hammer.

TURNER RS5 and RH14/12.

SCREWING MACHINES

OSTER 1in.-6in. Pipes No. 326.
ATLAS No. 2 3in.-6in. (Unused)

SHAPERS

INVICTA 4M 18in.
AMCO 6in. Bench.

NEWHEY 14in.

TAPPERS

HULLER No. 2 4in. Cap.
SUPERIOR 3in.
JONES No. 26. 2 B.A.-4in.
THIEL Nos. 3 & 4.
J. & S. Electrotap 4in.

THREAD MILLERS

FACKS Plain, cap. 3in. by 4in.
REINECKER R. by 72in.
LEES BRADNER Mod. 40. 64in. H.M.
HANSON WHITNEY. 8in. by 40in.

Woodhouse & Mitchell 369

Turret Mill, 36in. by 9in. table, power-fed table, motorised 400/350. Two months old.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

KENDALL & GENT Plano Miller, 6ft. by 2ft. 6in. by 2ft. 6in., two horizontal heads and one vertical head, motor driven 400/350. £950 Os. Od.**PARKES (MACHINE TOOLS) LTD.**

WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

Cincinnati 3FS Semi-dial Plain

Horizontal Milling Machine, table 624in. by 154in., spindle speeds to 450 r.p.m., motorised 400/350.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

5D Potter & Johnson Semi-

Automatic Turret Lathe.—BOX 22, MACHINERY, Clifton House, Euston Road, N.W.1.

61in. Chucking 6-spindle Auto-

matic by Acme Gridley (U.S.A.), in excellent condition, £1,500 as lying London area, any inspection.—BOX 2938, MACHINERY, Clifton House, Euston Road, N.W.1.

16in. Diameter Rotary Surface

Grinder. Heald model 22. Horizontal wheel spindle. Fully motorised 400/350.—BOX 251, MACHINERY, Clifton House, Euston Road, N.W.1

Herbert 2D Capstan Lathe. Just

reconditioned, 14in. dia. capacity.—BOX V988, MACHINERY, Clifton House, Euston Road, N.W.1.

New Almhuft Gear Hobber for

stock delivery, 234in. gear diameter, complete with all accessories. Will cut a 66-tooth helical gear, 5 D.P. 10 deg. helix angle, 2in. face in nickel chrome steel 371 EL in 37 minutes floor to floor, four gears cut per setting and only one cut required. Very competitive price.—MORTIMER ENGINEERING COMPANY, 202-206, Acton Lane London, N.W.10.

Lumsden Vertical Spindle

Hydraulic Surface Grinder. Table 20in. x 64in. 7in. dia. cup wheel. Motorised.—WILCOX & CO., Barr Street, Birmingham 19, Northern 1234/5

Herbert No. 4 14in. Capacity,

Ward 2A, 14in. capacity, and Atlas 1in. capacity Bar Capstan Lathes. Herbert 24in. capacity Bar Turret Lathe. Gisholt No. 4 Simplified Chucking Capstan Lathe. All 400/350.—HICKS MACHINERY, LTD., 26, Addison Place, London, W.11. Tel.: PARK 2938.

A.1 Type AF3 Automatic Flash

Butt Welder for sale. With pneumatic clamping and upsetting motions. Automatic control. Capacity 1 1/2in. square. K.V.A. 100. Upsetting pressure 3 tons. Clamping pressure 5 tons. Electric supply 212 volts, 50 cycles.—Photo and full details, etc., from P. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1. EUSTON 4681.

Bryant No. 16A Hole and Face

Grinder. Max. swing 16in. Max. grinding travel 13in. Workhead speeds 4. Range 150-450 r.p.m. Fully hydraulic traverse and spindle lifter. Motorised 400-440 v., 3 ph. In good condition.—BOX V984, MACHINERY, Clifton House, Euston Road, N.W.1.

Six New 1 Ton
Holt "Pneumatic Bench Presses
For Sale.

Complete with Foot Valves
and 4in. Feed.
Price £80 each.

BOX V981, MACHINERY,
Clifton House,
Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

C.V.A. No. 8 Automatic.
B.S.A. 4in. capacity Automatic.
B.S.A. 1in. capacity Automatic.
WARD 1A and 2A Capstans.
HERBERT 2B, 4BS and No. 4 Pre-optive Capstans.
WARNER & SWASEY No. 2 and No. 3 Capstans.
E.H.J. No. 13 Filing and Sawing Machine.
PALLAS No. 2 Surface Grinder.
SNOW T.14 and 20in. Table Surface Grinder.
CHURCHILL HBY 10in. x 24in. Plain Grinder.
CHURCHILL HDY Internal Grinder.
PRECIMAX 10in. x 48in. Plain Grinder.
NORTON 18in. x 6in. Surface Grinder.
CAPCO Surface Grinder.
ABWOOD Surface Grinder.
WOTAN Internal Grinder.
MAXNOVA Profilomatic Type B Copying Lathe.
HOLBROOK S.S. & S.C. 4in. x 24in. Lathe.
HOLBROOK S.S. & S.C. 7in. x 30in. Lathe.
HOLBROOK S.S. & S.C. 8in. x 36in. Lathe.
CHURCHILL-REDMAN 8in. x 30in. A.G.H. Gap Bed Lathe.
SOUTHBEND 6in. Centre Lathe.
LEBLOND 8in. Centre Lathe.
LODGE & SHIPLEY 12in. S.S. & S.C. Lathe.
PROGRESSIVE 8in. S.S. & S.C. Gap Bed Centre Lathe.
D.S. & G. 7in. A.G.H. Straight Bed S.S. & S.C. Lathes.
CINCINNATI 3/36 Hydromatic Duplex Mill.
CINCINNATI 2M Vertical Mill.
MILWAUKEE 2K Vertical Mill.
C.V.A. No. 79 Vertical Mill.
CINCINNATI 1/18 Production Mill.
EDGWICK No. 1 Speedmill.
MANN 4102 Production Mills.
FRITZ WERNER Production Mills.
HILLE Thread Mill.
HOLROYD Thread Mill.
VICTORIA 2M Horizontal Mill.

All Machines motorised 400-440/3/50 unless otherwise stated.

E.H. JONES
(MACHINE TOOLS) LTD
48, HIGH ST. EDGWARE, MDDX
Telephone: EDGware 4488/7
BIRMINGHAM: MIDLAND 5593

Richmond HB3/12 (New) 4ft. 6in.
Radial Drilling Machine. 2in. capacity, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

LUCAS No. 32 Precision Horizontal Borer, table 56in by 36in., max. from spindle to outer support 7ft., motor driven 400/3/50. £250 Os. 0d.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

Thread Grinder by Newall.
Cap. 3in. dia. by 10in. and equipment. Condition as new. Suitable for tap manufacture.—Apply BOX 223, MACHINERY, Clifton House, Euston Road, N.W.1.

Edwards

MASSEY 5 cwt. size Pneumatic Power Hammer. Overhanging type with slides. Arranged for direct geared motor drive. Size of hammer 5 cwt. Longest stroke 21in. Weight approximately 6½ tons.
BESCO High Speed Open End Guillotine Shearing Machine. Overcrank type. Arranged with automatic sheet hold-down and complete with front, back and side gauges. Capacity in mild steel 48½ in. x 14 S.W.G.
BESCO High Duty Geared Guillotine Shearing Machine. Overcrank type. Model "R." Capable of cutting mild steel plates 72in. wide x ½ in. thick. Arranged motor drive 400-440/3/50. Length 72in. Depth of gap 3½ in. Weight approximately 69 cwt.
NEW BRUECK Type 20/1600 All Steel Motorised Press Brake. Geared Steel plate construction. Arranged for motor drive 400-440/3/50. Maximum pressure 20 tons. Maximum working length 63½ in. Forming capacity 63in. x ¼ in. Weight approximately 36 cwt.
MADISON-KIPP Model S.315. Size 6in. x 6in. Pneumatic Die Casting Machine, for zinc, lead and tin alloys. Die size 6in. x 6in. x ¼ in. thickness. Capacity per shot, zinc 1½ lbs.
NEW CHICAGO No. 314 All Steel Folding Machine. Capacity 36½ in. x 14 S.W.G. For floor mounting. With auxiliary blade in position the capacity given is for a 1½ in. wide flange in mild steel.

Photographs of the above are available.

MACHINE TOOLS, NEW AND USED,
Of Every Description. Attractive Prices.

F. J. EDWARDS LTD.

359-361, EUSTON RD., LONDON, N.W.1
Telephone: EUSTON 4681-3771.

And at Lansdowne House, 41, Water St
Birmingham, 3. Telephone: Central 7606-8

Colchester Student S.S. & S.C.

Centre Lathe, 6in. height by 24in. between centres, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Herbert 2S Capstan, 1½ in. Cap.
Modern machine. Motor and electric 400/3/50.—BOX 25, MACHINERY, Clifton House, Euston Road, N.W.1.

Lamination High Speed Wien-
garten Press, 70 tons capacity with shaft-driven gripper feed mechanism. Variable stroke and 8 variable speeds. In excellent condition.—BOX 244, MACHINERY, Clifton House, Euston Road, N.W.1.

No. 4 Cincinnati Plain Milling
Machine. Dial type. High speed. S.C. motor drive 400/3/50. Table 74in. by 16in. Speeds 18-1,300 r.p.m. Auto. feeds all ways.—LEE & HUNT, LTD., Crocus Street, Nottingham.

Ward No. 7 A.G.H. Combination
Turret Lathe. Speeds to 750 r.p.m. M.D. 400/3/50.—ALBERT EDWARDS (MACHINERY), LTD., 79/89, Pentonville Road, London, N.1. Phone: TERMINUS 0167/8/9

H. BELL (MACHINE TOOLS) LTD

Offer from stock:

MONARCH 10in. Centre Lathe. Admits 10ft. between centres. Taper Turning.
SWIFT 8½ in. Gap Bed S.S. & S.C. Lathe. Admits 6ft. 6in. between centres. Taper Turning.
SEDGWICK 10ft. by 4in. Plate Bending Machine. Motor Driven. D.C. electric.
KEARNS Model OA Horizontal Borer. Vernier scales for rise and fall of head and cross traverse of table.
CHURCHILL 1½ in. 4-spindle Cono-
matic Bar Auto. With bar feed, tubes and stands.
CHURCHILL No. 1 Planetary Type
Internal Grinder. Reconditioned.
With dust extraction unit and equipment.
BERRY 8½ in. S.S. & S.C. Lathe. Takes 4ft. 6in. between centres.
C.V.A. 4in. Capstan Model C.A.9. Speeds to 2,000 r.p.m. With bar feed etc.
WARD 2A Capstan. Reconditioned. Speeds to 1,531 r.p.m. With ball chuck and bar feed, etc.
HERBERT No. 1 Horizontal Miller. Table 16 by 5. Hand lever feeds.
WILLSON 7½ in. S.S. & S.C. Gap Bed
Lathe. Takes 4ft. between centres.
ARCHDALE 30in. Vertical Millers. Speeds to 522 r.p.m. With 15in. circular table.
CINCINNATI No. 3 Dial Type Vertical
Miller. Reconditioned.
VAN NORMAN Plain Miller. Table 45½ in. by 10in. 18 speeds 30 to 1,450 r.p.m. Quick power traverse.

For full list of modern motorised machine tools write or phone:—

H. BELL (MACHINE TOOLS) LTD

WALTER STREET, LEEDS, 4
Tel. 637398-9.

Norton 10in. by 18in. Cylindrical
Grinder. Electric 400/3/50. Inspection London area.—BOX 230, MACHINERY, Clifton House, Euston Road, N.W.1.

400 Ton Hydraulic Drawing
Press. Hydraulic cushion, 6ft. by 6ft., with self-contained Pump Unit.

REED BROTHERS (ENGINEERING) LTD.,
Replant Works,
Woolwich Industrial Estate,
London, S.E.18.
Telephone: Woolwich 7611/6.

Lang Lathe, S.S. & S.C., 7in. by
30in. centres. Speeds 37-908. In good condition.—BOX V978, MACHINERY, Clifton House, Euston Road, N.W.1

Milnes (New) Vertical Milling
and Boring Machine, table 30in. by 8½ in., with measuring equipment. Motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

**"ALPHA" GLASSCUTTING AND WORKING MACHINES, ETC.**

New Machines for cutting out irregular shapes in Sheet and Plate Glass. Motorised or for Hand operation.

New Machines for cutting off Glass Rods and Tubes. Motorised.

New Glassworkers' Lathes with Precision 3-Jaw Chuck, Motorised.

New (Positive Control) Mixture Control Valves for Oxy./Gas and Gas/Air.

LATHES

New **COLCHESTER TRIUMPH** 7 $\frac{1}{2}$ in. \times 48in. Gap Bed Lathe. Motorised.

New **COLCHESTER STUDENT** 6in. \times 24in. Gap Bed Lathe. Motorised.

BOXFORD 4 $\frac{1}{2}$ in. S.S. & S.C. Lathe, Motorised.

CRAFTSMAN 6in. \times 18in. S.S. & S.C. Lathe, Less Motor.

BRADFORD 8in. \times 72in. S.S. & S.C. Lathe, Motorised.

LODGE & SHIPLEY 9in. \times 56in. S.S. & S.C. Lathe, Single Pulley Drive.

DARLING & SELLARS 9in. \times 56in. S.S. & S.C. Lathe, Cone Drive.

DARLING & SELLARS 7 $\frac{1}{2}$ in. \times 36in. Sliding and Surfacing Lathe, Cone Drive.

VARIOUS.

DENBIGH Swivel Table Miller, 34in. \times 10in. Motorised.

HERBERT 2D Capstan, Flanard Bed, B.C. and B.F., Motorised.

NORTON No. 4 D.B. Fly Press, 10in. throat, Motorised.

C.V.A. No. 79 Vertical Miller, 19in. \times 7in. Table, Motorised.

STAFFA 10in. \times 1in. Double End Grinder, Steel Stand as new, Motorised.

We have capacity to Rebuild Machine Tools to Markers' Specifications and Capacity for Planing or Grinding Lathe Beds, etc.

All Motorised Machines are for 400/3/50 unless otherwise stated.

Machines can be inspected under Power at short notice.

THE SURPLUS MACHINERY & STORES CLEARING HOUSE LTD

Empire Works, 108, East Hill, Wandsworth, London, S.W.18.

'Phone: Vandyke 3266/7/8.

'Gram: "Wandspur, Put, London."

Universal Thread Grinder,

No 10 Matrix. Internal and External threads 4-40 T.P.I. 7-6mm., 2-12 B.A. Flute grinding 2-12. With equipment. Modern machine with full electrics 400/3/50. Situated London.—BOX Z16, MACHINERY, Clifton House, Euston Road, N.W.1.

Rotary Surface Grinder. Mag-

netic chuck, 36in. dia. Blanchard Model 16 Electrics 400/3/50.—Viewed London area.—BOX Z11, MACHINERY, Clifton House, Euston Road, N.W.1.

Harrison (New) 11in. Swing

S.S. & S.C. Gap Bed Centre Lathe, 24in. between centres, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Hole and Face Grinder, Bryant

16A. Capacity 16in. dia. by 13in. stroke. Fully motorised. In good working order.—BOX Z47, MACHINERY, Clifton House, Euston Road, N.W.1.

Besco 6ft. \times 14G. Guillotine.

400/3/50.—HICKS MACHINERY, LTD., 28, Addison Place, London, W.11. Tel.: Park 2933.

TATE**MILLING**

VICTORIA V.1 40in. by 11in. Vertical (nearly new).

Two **CINCINNATI** 4-48 Simplex Hydromatic Millers.

Two **EDGWICK** Plain (Dial) 40in. by 10in.

ARCHDALE 24in. Production Auto-cycle (1946).

RICHMOND 01 Plain 30in. by 8in. with Vertical Head.

PALLAS HO Plain 30in. by 8in., with Vertical Head.

PALLAS HOO Plain, 22in. by 7 $\frac{1}{2}$ in.

CINCINNATI Plain, 30in. by 8in.

WADKIN LXA 36in. by 12in., Vertical for alloy, etc.

GRINDING

JONES SHIPMAN Fig. 1204 EIUR, 8in. by 22in. Universal (nearly new).

MYFORD MG9 5in. by 9in. Int. and External (three years old).

MYFORD MG12 5in. by 12in. Int. and External (one year old).

EXCEL 3A 24in. by 8in. Horizontal Surface (nearly new).

JONES SHIPMAN Fig. 138 Universal 10in. by 27in.

SEASTRAND 10in. by 5in. Vertical Surface (similar Excel No. 1).

JONES SHIPMAN Fig. 540 18in. by 6in. Surface, Chuck and Coolant (1954).

SHAPING AND PLANING

ALBA 45 18in. £95

NEWLEY 14in.

LATHES

COLCHESTER 6in. "Student" (two years old).

MITCHELL OF KEIGHLEY 8 $\frac{1}{2}$ in. by 4ft. 6in., 32in. by 9in. gap, 3 $\frac{1}{2}$ in. sp. hole.

LANG 10in. by 3ft. 6in. Heavy Duty Centre Lathe.

SMALLPEICE 6WSL Multi-cut Lathe, 5 h.p.

CARDIFF 7in. Lathe (1952).

WILLSON 7 $\frac{1}{2}$ in. "Newel".

MITCHELL 6 $\frac{1}{2}$ in. by 60in. Gap Bed Lathe (1952).

PRATT & WHITNEY 7in. Lathe with Sadi Drive and Motor.

CAPSTAN LATHES

SIMMONS 1 $\frac{1}{2}$ in. Bar. £125

MURAD 1A Bar (Unused).

SHEET METAL

BESCO 4ft. by 16 s.w.g. Guillotine £85

SAWS

GROB Type 614 Bandsaw on stand. £70

BORING

DICKINSON Horizontal Borer, 2 $\frac{1}{2}$ in.

Trav. sp. No. 5 M.T., 45in. by 28in.

main table, 10 h.p. motor (will take facing head). This machine is in good condition and ready to be put to immediate use. Weight 9,000 lbs. Low price.

Illustrations of each of above freely available

Secondhand machines offered on 7 days

approval by arrangement.

Open Saturday Morning.

TATE MACHINE TOOL**CO. LTD.,**

4, NORTH END PARADE,
OPPOSITE OLYMPIA,
LONDON, W.14.

Fulham 6563/4/5.

Mitchell 8 $\frac{1}{2}$ in. by 4ft. 3in. b.c

A.G.H. Gap Bed Centre Lathe, 32in. in

gap, 3 $\frac{1}{2}$ in. hollow spindle. M/D 400/3/50.—

ALBERT EDWARDS (MACHINERY), LTD.,

79/89, Pentonville Road, London, N.1. 'Phone:

TERminus 0167/8/9.

ACBARS LIMITED

57a, HOLBORN VIADUCT,
LONDON, E.C.1.

Telephone: Central 2287. Telegrams: Acfrib. Cent. London

AVAILABLE FROM STOCK

All machines listed below are at our Works in Sutherland Walk, Walworth Road, S.E.17.

AUTOMATICS.

HERBERT Auto. Junior.

HERBERT 3A Chucking Auto.

INDEX OR12 Auto.

ACME-GRIDLEY, Type R, 4-spindle, $\frac{1}{2}$ in. capacity.

ACME-GRIDLEY, Type R, 4-spindle, 1 $\frac{1}{2}$ in. capacity, (2 machines).

WICKMAN 4mm. Swiss Type.

RYDERMATIC No. 12 Multi Tool Lathes.

BORERS.

New **GRAFFENSTADEN** AF.075 Horizontal

Borer, 3in. dia. travelling spindle,

17 $\frac{1}{2}$ in. dia. faceplate.

GRINDERS.

ABWOOD Vertical Spindle Surface.

BROWN & SHARPE No. 2 Surface Grinder.

NORTON Surface Grinder, hydraulic,

18in. by 6in.

JONES & SHIPMAN Fig. 62M Plain Cyl.

8in. dia. by 10in.

LANDIS 10in. by 18in. Plain Grinder.

JONES & SHIPMAN 10in. by 27in. Semi-

Universal.

CHURCHILL 24in. by 10in. Universal.

PRECIMAX Type UPJ 12in. by 36in.

Universal.

BRYANT 16C 16in. Internal Grinder.

CAPSTAN LATHES.

HERBERT No.0 $\frac{1}{2}$ in. collet cap. (2).

MURAD $\frac{1}{2}$ in. Capstan Lathes (2).

SOUTHWARK No. 2 1 $\frac{1}{2}$ in. Capstan Lathe.

WARD 2A Capstan Lathes (6), with 1 $\frac{1}{2}$ in.

collet chucks and bar feed. Machines

have 2 speed motors and power feeds to

both saddle and turret.

New **MODERN** 2C 1 $\frac{1}{2}$ in. bar feed capacity.

HERBERT No. 3 High Speed Capstan, Air

Chuck. Spindle speeds 60-1,500 r.p.m.

DRUMMOND Type K Capstan Lathes (2).

GISHOLT No. 4 Friction Head Capstan.

LIBBY 4R 2in. Capstan Lathe. Bar feed.

BARDONS & OLIVER No. 5 Capstan Lathe.

HERBERT No. 7 Turret Lathe.

FOSTER No. 28 Turret Lathe.

CENTRE LATHES.

New **BOXFORD** 4 $\frac{1}{2}$ in. Type A.

New **COLCHESTER** CHIFMASTER, 5in. by

20in.

SOAG OXFORD 6 $\frac{1}{2}$ in. Centre Lathe.

SOUTHBEND 13in. swing taper turning.

WILLSON 8 $\frac{1}{2}$ in. A.G.H. Lathe.

CARDIFF 8 $\frac{1}{2}$ in. by 48in. Lathe.

New **COLCHESTER** ASCOT 8 $\frac{1}{2}$ in.

MILLERS.

New **CHRISTEN** Swiss Universal Tool and

Die Mill.

HERBERT No. 1 Horizontal.

New **VICTORIA** U1 and U2 Universal.

ARCHDALE 20in. Horizontal Mills (3).

ARCHDALE 28in. Horizontal Mill.

OLIVETTI FP2 Manufacturing Miller. Table

52 $\frac{1}{2}$ in. by 14 $\frac{1}{2}$ in. Longitudinal traverse

39in.

New **GRAFFENSTADEN** Model GH3 Plain

Horizontal, table size 67 $\frac{1}{2}$ in. by 16 $\frac{1}{2}$ in.

New **TAYLOR** Vertical, table 17 $\frac{1}{2}$ in. by 5 $\frac{1}{2}$ in.

RICHMOND VHM Vertical Mill

New **VICTORIA** V2 Vertical.

New **GRAFFENSTADEN** FV.102 Vertical

Mill. Table 51in. by 11 $\frac{1}{2}$ in.; 39 $\frac{1}{2}$ in.

longitudinal traverse.

HOLROYD T117 Thread Miller.

HELLER Automatic Thread Millers (4).

MISCELLANEOUS.

JONES & SHIPMAN 2-spindle Pillar Drill,

with No. 3 M.T. spindle, power feed.

New **VELOX** 7 $\frac{1}{2}$ in. and 10in. Hacksaws.

New **ESSEX** 18 Bandsaw.

New **RICHMOND** SR2 3ft. Radial Drill.

New **ALBA** 18in. Shaper.

MAIDEN Bar Chamferer, $\frac{1}{2}$ in.

New Fly Presses up to No. 6.


All Machines motorised 400/3/50 unless

otherwise stated.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

All Steel Record Filing Desks



WITH

horizontal Roller Shutters. Top portion 6ft. 6in. by 2ft. 4in. by 9in. deep, three sections with Roller Shutters, fitted locks, each section two divisions, 12in. wide by 7in. deep, mounted on two pedestals 2ft. 0in. by

1ft. 4in. by 2ft. 0in. high, with two drawers 12in. wide by 7in. deep, one drawer 12in. wide by 4in. deep, fitted locks. Price £15 each.

Also two section types, size 4ft. 4in. by 2ft. 4in., all other dimensions as above, £10 each.

Useful for many purposes, marvellous value.

W. URQUHART, 1023 Garratt Lane, S.W.17 BALham 8551



IN STOCK

KNEELESS TABLE TYPE VERTICAL MILLERS

CVM25 KENDALL & GENT, separate motor drive for spindle, table and rise and fall of spindle head, with circular table, table dia. 30in., capacity 30in. by 36in. by 32in., 15 spindle speeds from 15-320 r.p.m.

47V HERBERT, multi-motor drive, table 72in. by 17in., capacity 48in. by 16in., max. distance table top to spindle nose 23in., 16 spindle speeds from 21-750 r.p.m.

28in. CINCINNATI Hydrotel fixed height bed, single power control lever, stepless feed regulation, rapid power traverse multi-motor drive, table working surface 28in. by 83in., capacity 60in. by 30in. by 14in., vertical travel of spindle head gap 38in., 16 spindle speeds from 52-300 r.p.m.

We also have a good stock of Table Type Milling Machines, Plain Horizontal, Universal and Vertical, by Cincinnati, Archdale, Brown & Sharpe, Parkson, etc., available.

Inspection invited.

It's Cheaper to Buy Now

Full details on request to:

SOAG MACHINE TOOLS LTD.,
JUXON STREET, LAMBETH, LONDON, S.E.11.

'Phone: REliance 7201.

'Grams: Sotoolsag, London, S.E.11.

No. 2 Dial Cincinnati Universal
Horizontal Mill, 1,500 r.p.m. Seen
London.—BOX V992, MACHINERY, Clifton
House, Euston Road, N.W.1.

ARCHDALE 3ft. 6in. - 4ft. Radial Drilling
Machines, rising and falling arm, No. 4
Morse taper, box table. £250 0s. 0d. each.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

Archdale 20in. Plain Horizontal
Milling Machine. Table size 40in. by 10in.
Speeds to 615 r.p.m. M/D 400/3/50.—ALBERT
EDWARDS (MACHINERY), LTD., 79/80,
Pentonville Road, London, N.1. 'Phone:
TERminus 0167/8/9.

LEONARD ROTH

ABBOT STREET,
KINGSLAND HIGH STREET,
DALSTON JUNCTION,
LONDON, E.8.

TERMS ARRANGED

Tel.: Clissold 0513/4

BROWN & SHARPE Type No 2 Surface
Grinder, 18in. by 6in. table, automatic
feeds, 14in. by 6in. magnetic chuck.
£125.

CAPCO Surface Grinder, 18in. by 6in.
table, 14in. by 6in. magnetic chuck,
motorised 400/3/50. £108.

ATKINS 9in. Ring Surface Grinder, 9in.
magnetic chuck, motorised 400/3/50.
£75.

GUEST 18in. by 7in. Plain Cylindrical
Grinder, motorised 400/3/50. £45.

WE HOLD BIG STOCKS OF LATHES,
SHAPERS, MILLS, DRILLS AND
PRESSES.

PLEASE WRITE FOR LISTS.

NORMAN E. POTTS (B'HAM) LTD.
offer:—

HERBERT type "V" Junior 2-spindle
Pedestal Drilling Machine.

BAKEWELL (U.S.A.) No. 2 Vert. Hyd.
Precision Tapping Machine. Table 36in.
by 18in.

WEATHERLEY Oilgear Cyclematic Broach
Model XM 80. 30in. stroke. As New.

130, MOSELEY ROAD, BIRMINGHAM 12.
VIC. 1278.

NEW MACHINES IN STOCK.

MITCHELL OF KEIGHLEY 10 1/2in. x
7 1/2in. B.C. S.S. & S.C. Gap Bed Centre
Lathe.

MITCHELL OF KEIGHLEY 8 1/2in. x 4 1/2in.
B.C. S.S. & S.C. Gap Bed Centre Lathe.

STANLEY 8 1/2in. x 6ft. 0in. B.C. S.S. &
S.C. Gap Bed Centre Lathe. 2-speed
motor.

STANLEY 7in. x 2ft. 10in. B.C. S.S. & S.C.
Gap Bed Centre Lathe. 2-speed motor.

COLCHESTER "Mascot" 8 1/2in. x 4ft. 6in.
B.C. Gap Bed Centre Lathe.

COLCHESTER "Student" 6in. x 24in. B.C.
Gap Bed Centre Lathe.

COLCHESTER "Chipmaster" 5in. x 20in.
Centre Lathe.

CARDIFF "Major" 7 1/2in. x 40in. B.C.
S.S. & S.C. Gap Bed Centre Lathe.

WILLSON Mk. 1 6 1/2in. x 24in. Inclined
Bed Centre Lathe.

VICTORIA V.2 Vertical Milling Machine.
Table 45in. x 11in.

RICHMOND SR.2 48in. Radial Arm Drilling
Machine.

KERRY 150 1 1/2in. cap. All Geared Drilling
Machine.

KERRY 100 1in. cap. Pillar Drilling
Machine.

PROGRESS 3A 1 1/2in. cap. Pillar Drilling
Machine.

PROGRESS 2GS 1 1/2in. cap. Pillar Drilling
Machine.

EXCEL 3/12 Hydraulic Surface Grinder.

EXCEL No. 1 Pedestal Surface Grinder,
cap. 10in. x 5in.

EXCEL No. 5 Tool and Cutter Grinder.

MYFORD MC.12 Cylindrical Grinder.

ABWOOD Mod. CGL Carbide Tool Grinder.

ALBA 2S 14in. Shaper.

P. SIMPSON & CO., LTD.

177, RAIKES LANE, BIRSTALL, Nr. LEEDS
Tel.: Batley 1235.



No. 4 CINCINNATI Dial Type Plain Miller.
16 spindle speeds 18-450 r.p.m. Dual con-
trol. Longitudinal feed 42in. Power feeds
and rapids. 3 arbors. Overhauled. £1,650

No. 2M CINCINNATI Vertical Miller. Table
49in. by 10 1/2in. 12 spindle speeds 31-660
r.p.m. Longitudinal feed 28in. Power feeds
and rapids. £725

No. 2 CINCINNATI Dial Type Plain Miller.
Table 52in. by 12in. 16 speeds 20-500 r.p.m.
Longitudinal feed 28in. Power feeds and
rapids. £675

25 R.V.M. KENDALL & GENT Vertical
Miller. Kneeless type. Combined circular
and rectangular table 48in. by 20in. Circular
table 22in. Speeds 25-375 r.p.m. Power
feeds and rapids. Swivelling head. £750

50in. by 12in. VARNAMO Universal Miller.
Speeds 30-1,400 r.p.m. Power feeds and
rapids. Longitudinal feed 31in. New. £1,350

No. 1 KEARNS Horizontal Boring and Facing
Machine. Patent. Spindle 2 1/2in. diameter.
Facing maximum 24in. Traverse of spindle
36in. Speeds 10-600 r.p.m. With equip-
ment. Overhauled. Modern machine. £1,600

DIMCO (Gt. Britain) LTD.,
415-417, OXFORD STREET,
LONDON, W.1.

Tel: Mayfair 1585.

When answering advertisements kindly mention MACHINERY.

June 13, 1958

MACHINERY

(Suppt.) 183

Classified Advertisements (PLANT FOR SALE, contd.)

Tangye 3ft. 6in. Radial Drilling Machine, No. 4 M.T. Low base. Elevating arm. M/D 400/3/50.—ALBERT EDWARDS (MACHINERY), LTD., 79/81, Pentonville Road, London, N.1. Phone: TERminus 0167/8/9.

STEDALL SPOT
Machine Tool
NEW LATHES
MITCHELL

8½ in. centre	£934
10½ in. centre	£1,499
12½ in. centre	£1,855

Immediate delivery. — Prices include 3-phase electrical equipment.

Stedall Machine Tool Co.
145-157 ST. JOHN ST. CLERKENWELL E.C.1
Phone: CLERKENWELL 1010

Precimax Universal Grinding machine, 10 x 24. First-class condition. Dickinson Horizontal Boring, Facing, Milling, Tapping Machine. Good condition. Wild Barfield Electric Carbursing and Hardening Furnace. As new. Herbert No. 3 Combination Turret Lathe, motorised.—BROOK ENGINEERING COMPANY, Hermitage Road, Coalville, Leicestershire. Phone: Coalville 748.

For Sale, All Motorised 400/3/50. 2-Ward 1A 1in. cap. Capstans. Woodhouse & Mitchell Spinning Lathe. Archdale S.S. Var. Speed Drill. Herbert S.S. Var. Speed Drill. No. 4 Herbert Lathe. Kendall & Gent Vert. Miller, 30in. cir. table. Pacera Bench Drills. Ward 20 Capstans and equipment, as new. All in excellent condition.—WOODMET LIMITED, Globe Lane, Dukinfield, Cheshire.

AUCTIONS

STEWART ENGINEERING CO., LTD., 25a HANWORTH ROAD, SUNBURY-ON-THAMES, MIDD.

Situate on A.305, at rear of "Sundeala" and "C. & C." Soft Drinks Premises.

Messrs.

WELLER & CO.

are instructed by the above Company to sell by auction on the premises on **WEDNESDAY, JUNE 18th, 1958,** the whole of the valuable

LIGHT ENGINEERING PLANT AND MACHINERY

including
10 ton and 5 ton Power Presses. Holbrooks 5ft. 8½ in. Lathe. Colchester. Capstan and C.V.A. Lathes. Denbigh Milling Machine. Maier 12 KVA Spot Welder. 4 Compressors (400 lb., 200 lb. and 125 lb. pressure). "Besco" Benders and Guillotine—Bench Folders—2 Plating Generators. Electric Motors and Equipment—4-Spindle Multi Drill. Springfield 12in. Shaper. Siemens Schuckert Converter. B.E.N. High Pressure Washer. Welding Equipment. Black & Decker 7in. Rip Snorter Saw. Two Large Stove Enamelling Ovens. I.C.I. Degreasing Plant. Spraying Booth. Metal Cabinets and Office Equipment.

6 Tons Nuts and Bolts, etc. Large quantity surplus stock. 10 cwt. Beeswax, etc., etc. **SALE TO COMMENCE 11.30 A.M.** (Viewing Tuesday, June 17th, 10 to 4, or by appointment. Tel.: Hounslow 7070.) Catalogues from Auctioneers, opposite Cattle Market, Woodbridge Road. Guildford 3386

By Order of the **LONGFORD MACHINE TOOL CO., LTD.,**

75a, LONGFORD ROAD, (REAR OF CENTRAL GARAGE), COVENTRY.

HENRY BUTCHER & CO.

are instructed to offer for SALE at the WORKS,

on **WEDNESDAY, 18th JULY 1958,** at 11.15 a.m.

AS A FIRST LOT:

THE FREEHOLD LAND

having a

SITE AREA OF ABOUT 1½ ACRES

developed with **SINGLE-STORY BUILDINGS** providing a

FLOOR SPACE OF 5,750 SQUARE FEET with

VACANT POSSESSION

TO BE FOLLOWED BY THE SALE IN LOTS IN DETAIL OF THE:

MACHINE TOOLS STORES & EQUIPMENT

including

S.S. & S.C. CAPSTAN and TURRET LATHES. AUTOMATICS. BORING MACHINES.

UNIVERSAL, CYLINDRICAL and INTERNAL GRINDERS. HORIZONTAL and VERTICAL MILLING MACHINES.

POWER PRESSES UP TO 75 TONS. DRILLING, HONING and GEAR CUTTING MACHINES.

ENGINEERS' SMALL TOOLS and STORES. WROUGHT IRON and STEEL SCRAP. ELECTRIC MOTORS;

"RAPIER" 2-TON CRANE.

LORRIES, VANS and MOTOR CARS.

Combined Particulars and Conditions of Sale of the property, with a catalogue of the Plant and Machinery and Equipment, price 6d. each (when ready) may be obtained of: Messrs. Varley Hibbs & Co., 9, Eaton Road, Coventry; and of Messrs. Henry Butcher & Co., Auctioneers, Valuers and Surveyors of Factories, Plant and Equipment, 73, Chancery Lane, London, W.C.2. Telephone: HOLborn 8411 (8 lines).

By Order
of
the



Minister
of
Supply.

SALE BY AUCTION AT MELTON MOWBRAY
(15 miles from Leicester, 18 miles from Nottingham; 16 miles from Grantham; 20 miles from Stamford).

MACHINE TOOLS; LATHE SPARES; SURPLUS STORES; LIFTING EQUIPMENT

now lying at **TECHNICAL STORES DEPOT, OLD DALBY** (6 miles from Melton; 12 from Nottingham; 15 from Leicester; and near Old Dalby L.M.S. Railway Station).

GENERAL STORES SUB-DEPOT, BOUGHTON, NR. NEW OLLERTON, NOTTS. (8 miles from Mansfield; 16 miles Nottingham; 12 miles Newark).

TECHNICAL STORES SUB-DEPOT, QUENIBOROUGH (midway Melton and Leicester).

THE GUN RANGE, ASFORDBY VALLEY, (2 miles from Melton).

50 Centre and Capstan Lathes, 5in. to 8in.; Miller, Pillar and Bench Drills; Arc Welders; Tool and Cutter Grinders; Metal-spraying Compressors; Caterpillar Track Presses; Hyd. Straightening Presses; Hack Saws; Electric and L.O. Warehouse Stacks and Elevated Platform Trucks; Valve Refacers; Engine Belting; Bench, Ped. and Flex Shaft Grinders; Hearths and Furnaces; Matrix Metal; 1,200 Gravity Conveyor Rollers; Steel Wire Rope; Wheeled Fire Extinguishers; Stencil Cutters; Scales and Weighing Machines; Scratch Brushes; Sack Barrows; Painters' Masks; 1,100 tons Strapping Steel and Wire; Lathe Chucks and Spares; Test Instruments; Circuit Analyzers; Ross & Clark Fork-Lift Stackers; Steel Pallets; Calico sheeting; Camouflage Netting; Face Veils; Wax; Paint; Linseed Oil.

WHICH WILL BE SOLD BY AUCTION BY

SHOULDER & SON

on **WEDNESDAY and THURSDAY,**

JULY 2nd and 3rd, 1958.

At 10.30 a.m. prompt each day.

AT THEIR AUCTION ASSEMBLY ROOMS,

1 NORMAN STREET, MELTON MOWBRAY.

ON VIEW: 26th and 30th June and 1st July, 1958, and on mornings of sale.

CATALOGUES 1s. each (P.O. only, no stamps) obtainable from the Auctioneers, Dept. 12, 1 and 3 Norman Street, Melton Mowbray. Tel.: 81 and 669.

BY AUCTION—WITHOUT RESERVE

THE IMPORTANT CONTENTS OF THE WORKS ON THE PREMISES AT

70b STAFFORD ROAD, CROYDON, SURREY

(Opposite the "Propeller" Public House)

COMPRISING

E.M.B. Hot and Cold Chamber Die Casting machines, also EDGWICK, HARPER & A.D.C. Machines. HOLMAN and LACEY-HULBERT Compressors, Polishing and Rumbling Machines, Linishers. Extraction Plant, DENBIGH, NORTON and other Fly Presses, A.G.M. and NU-WAY oil Fired Furnaces. PACERA and other Drilling Machines, CINCINNATI, SMART & BROWN and other Horizontal and Vertical MILLERS, ALBA SHAPER, DELAPENA Honing Machines, LITTLE JOHN, ROSENFORS, PRATT & WHITNEY, Lathes, B. & S. Surface Grinder, ASHWORTH & AVERY Weighing Machines, MANCHESTER Hackaws, MAVITTA Drawing Machine, NITRALLOY and other Toolroom Steel, Drills, Angle and Face Plates, Cutters, Chucks, Shafting, Benches, Reamers and Honing Tools, also Canteen and Office Furniture, including Desks, Typewriters, Convertors and many other important lots.

10.30 a.m. WEDNESDAY, 25th JUNE, 1958

On View Monday and Tuesday prior to Sale, 10 a.m. to 4 p.m. Catalogues Price 6d. from the Auctioneers.

HENRY LEWIS & CO.

Specialist Incorporated Auctioneers and Valuers,

3-5, GODING STREET, VAUXHALL, LONDON, S.E.11. RELIANCE 5252

When answering advertisements kindly mention MACHINERY.

SITUATIONS VACANT

If you do not wish your reply to any Box No. advertisement in this section to be forwarded to certain firms, please advise us. Your reply will then be destroyed, but you will not be notified as this would disclose the identity of the advertiser.

Designer Draughtsman or Senior

draughtsman required immediately to take charge of Drawing Office engaged on design and production drawings for specialised mechanical handling fixtures for induction heating equipment. Machine tool design experience an advantage. Permanent position with pension scheme. Commencing salary in the range £900-£1,100 per annum, depending on experience and ability.—Write or telephone the SECRETARY, WILD-BARFIELD ELECTRIC FURNACES, LIMITED, Otterspool Way, Watford By-pass, Watford, Herts. Telephone: Watford 6091.

Loader / Chaser Required by


North London Repetition Part Manufacturer. Must be fully conversant with automatic, capstan and 2nd operation work.—Please state experience and age to BOX V989, MACHINERY, Clifton House, Euston Road, N.W.1.

Dynamic Sales Manager Re-

quired for old-established used Machine Tool Merchants able to act on own initiative and promote home and export sales. Good connections in the trade essential. Only men who are prepared to offer services above and beyond the call of normal duty need apply. Salary equivalent to that of a Junior Cabinet Minister eventually available to the right personality.—BOX Z9, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanted—Senior Jig and Tool

Draughtsman and Machine Tool Draughtsman by Company in the South Coast area. Experience in machining light alloys and knowledge of hydraulics and pneumatics an advantage.—Write stating age, details of experience, qualifications and salary required, to BOX V934, MACHINERY, Clifton House, Euston Road, N.W.1.



BALDING ENGINEERING LTD

Have vacancies for first class Millers & Machine Tool Fitters. Good rates, plenty overtime, bonus, sick pay, etc.

SANDY LANE, NORWICH.

This Company has expanded threefold in three years and offers excellent scope to men of undoubted ability and integrity. Attractive conditions of employment in new factory

Medium-sized Light Engineer-

ing Company producing large volume lines wish to appoint an Engineering Assistant to the Works Manager: his responsibilities will include (1) the programming and production of all equipment including plastic moulding tools, press tools, jigs and fixtures, etc., and (2) control of all plant maintenance.—Please submit applications containing fairly full details to WORKS MANAGER, ASHLEY ACCESSORIES, LTD., Ulverston, North Lancs.

Fully Experienced Draughtsmen

with Machine Tool and/or Jig and Tool design qualifications, can make highly remunerative progressive position with a leading engineering concern in Worcestershire.—Full details to BOX V951, MACHINERY, Clifton House, Euston Road, N.W.1.

Machine Tool Salesman, Capable

of organising outside sales drive of approved Transfer Press and other specialised machines required. Good position and salary for right man. Connections in industries utilising light pressings an advantage.—Apply PLATARG, Shortlands, London, W.6. Phone: RIVerside 6632.

Highly Paid Secure and Interest-

ing posts are always available for technically trained men. Find out how you can put some letters after your name by preparing at home in "No Pass—No Fee" terms for A.M.I.Mech.E., A.M.I.Prod.E., A.M.S.E., City and Guilds, etc., etc. Full details of exams and hundreds of courses in all branches of Engineering, Draughtsmanship and Management, the Benefits of our Employment Dept., and unique record of 95 per cent. successes, are given in "Engineering Opportunities"—valuable 144-page Guide which will reveal many chances you are now missing. Write for your copy today (stating subject of interest).—FREE and without obligation.—B.I.E.T., Dept. 34a, Wright's Lane, London, W.8.

APPRENTICE INSTRUCTOR

Qualified to give theoretical training to the O.N.C. standard and instruct in the use of general machine tools and hand tools. Good salary with staff conditions offered a suitable applicant having qualities of leadership and ability to maintain fifteen apprentices in the Company's training school and supervise the progress of other apprentices, revolving between the training school and the works as progress demands. Apply in strict confidence with full details of age, education and experience to

**Personnel Manager
W. E. SYKES LIMITED,
Staines, Middlesex.**

WHEN YOU WANT . . .

- TO BUY OR SELL PLANT OR MATERIAL
- WORK FOR A SLACK DEPARTMENT
- AGENCIES OR PARTNERSHIPS
- MEN FOR EXECUTIVE POSITIONS

A SMALL ADVERTISEMENT IN "MACHINERY"
BRINGS RESULTS

When answering advertisements kindly mention **MACHINERY**.

SITUATIONS WANTED

Engineer, Past Nine Years Sales, toolroom and D.O. experience. Resident Essex. Seeks change.—BOX V947, MACHINERY, Clifton House, Euston Road, N.W.1.

Practical Engineer (46), With thirty years experience light/medium mechanical production, including twelve years executive posts with smaller firms, seeks progressive situation. Fully conversant with modern techniques in batch or prototype production. Sound knowledge of planning estimating, jig and tool design, production control, automatic production, etc. Would consider suitable offer in technical sales or similar. Available at short notice. London or South Essex preferred.—BOX V948, MACHINERY, Clifton House, Euston Road, N.W.1.

Senior Planning Engineer, 38, A.M.Inst.B.E., with wide experience of production techniques, designing experience of tooling and special-purpose machinery, estimating and work contract placing. Versatile, seeks position as Technical Sales Representative, Manager or similar responsible position. Willing to reside convenient to position, available immediately. All replies acknowledged.—BOX V971, MACHINERY, Clifton House, Euston Road, N.W.1.

Senior Executive, Fully Experi-enced general administration, buying, commercial and works procedure, etc. Desires responsible post small or medium sized firm. London or Home Counties. Age 43 years.—BOX V980, MACHINERY, Clifton House, Euston Road, N.W.1.

Executive Engineer (British), M.I.Mech.E., A.M.B.I.M., now in India, seeks change. Age 44. Wide experience in Works Management, Development, Overall Works Administration. Well versed on commercial side, estimating, costing, quoting, etc. Early training in machine tools, later experience in medium/heavy engineering industry, especially steel foundries. Would act in representative capacity in India or elsewhere. Available for interview in India now, and later in U.K.—Reply BOX V991, MACHINERY, Clifton House Euston Road, N.W.1.

Mechanical Designer, Experi-enced in design and production of wide variety of machinery, industrial gas turbines, aero engines, precision machinery, etc. Desires change.—BOX V961, MACHINERY, Clifton House, Euston Road, N.W.1.

Auto Planning Engineer and Cam designer, requires position with progressive company. Age 40.—BOX Z12, MACHINERY, Clifton House, Euston Road, N.W.1.

Senior Designer Wishes to obtain position chief or assistant of D.O. Supervisory posts D.O., Toolroom held. Wide experience on special-purpose machines, press work, jigs, fixtures, moulds.—BOX V987, MACHINERY, Clifton House, Euston Road, N.W.1.

Production Engineer. Wide Ex-perience process planning, estimating, etc. Fine limit work for machine shop and press shop. Med./light engineering.—BOX V990, MACHINERY, Clifton House, Euston Road, N.W.1.

REPRESENTATIVES

Technical Sales Representative requires change. Resident North London, experienced Plastic Moulds, Die Casting, Machine Tools. Salary £1,000 per annum.—BOX V960, MACHINERY, Clifton House, Euston Road, N.W.1.

A Technical Representative—mechanical engineer, 37, seeks position Supervisory experience in D.O., Toolroom, Production departments on special-purpose machines, jigs, fixtures, press tools and plastic moulding.—BOX V996, MACHINERY, Clifton House, Euston Road, N.W.1.

RECEIVED TOO LATE FOR CLASSIFICATION

CONTRACT WORK

DAVIES-CHARLTON (U.K.) LTD.
STATION SAWMILLS, BARNOLDSWICK, VIA
COLNE, LANCs. TEL. BARNOLDSWICK 3310
A.I.D. APPROVED

Are specialists in component
production for the Aero-Jet
engine industry, and can offer
capacity on

**THREAD GRINDING
THREAD ROLLING**

Capstan, Auto and Centre Lathe
turning. External, internal
Centreless and surface grinding.
Horizontal, vertical and profile
milling. Drilling, Tapping and
Honing.

**QUOTATIONS FOR LARGE OR SMALL
QUANTITIES**

PLANT WANTED

1 S/H Horizontal Spindle Grind-ing machine or tool grinder with compound slide. Maximum price £100 depending on type and condition.—BOX Z4, MACHINERY, Clifton House, Euston Road, N.W.1.

Cold Chamber Die Casting Ma-chine required, 9 lbs. Aluminium capacity or over.—BOX Z7, MACHINERY, Clifton House, Euston Road, N.W.1.

GLEASON 12in. and 6in. Straight Bevel Gear Cutters, with equipment.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

MISCELLANEOUS FOR SALE

Mavitta Draughting Machine, stand and Anglepoise lamp, £35. "Ever-taut" Draughtsman's chair, £5. All in good condition.—BOX Z8, MACHINERY, Clifton House, Euston Road, N.W.1.

FACTORY FOR SALE

Factory For Sale. 21 Years' lease. Approx. 2,600 sq. ft. With 4 new milling machines (2 vertical and 2 horizontal). 1 No. 11 Herbert. Rent £950 p.a. Ashford, Middlesex. Price: List price for machines. No premium for lease.—Telephone: Exmoor 4861.

BUSINESS FOR SALE

Precision Engineering Business for sale, Director retiring. North Midlands area. Ample premises for expansion. Freehold Factory, substantial private mortgage available.—BOX Z13, MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

If you require a perfectly accurate and sensitive SMALL BORE GAUGE


— we recommend

'COMPAC'

IAOO for bores 0.149 - 0.272in.

IAO „ „ 0.268 - 0.492in.

All gauges operate on rack and pinion movements, and may be supplied with tungsten carbide contact points.



Both Gauges are available with dials giving readings of 0.001in., 0.0002in., 0.0001in. or alternatively, their metric equivalents. Write for leaflet 'COMPAC' A for full details of these gauges.

We are exhibiting at the Chemical and Petroleum Engineering Exhibition, Stand 28, Outer Row, Gallery, Grand Hall, Olympia, June 18-28

H. WILLIAMS & SON LTD. TOOL MANUFACTURERS

LARK WORKS, ST. ALBANS

• SOLE DISTRIBUTORS FOR THE UNITED KINGDOM

PHONE: ST. ALBANS 52264/5/6

INDEX TO ADVERTISERS

	PAGE
Abbey Heat Treatments Ltd.	156
A.B.M.T.M. Ltd.	Front Cover, 9 & 10
Abwood Machine Tools Ltd.	19
Acabars Ltd.	181
Adam Machine Equipment Ltd.	145
Ajax Machine Tool Co. Ltd.	139
Alexander, Geo. H. Machinery Ltd.	2, 164 & 165
Alfa-Laval Co. Ltd.	80
Alka Co., The	158
Alleyn Foster Engineering Co. Ltd.	157
Almco Superseeh Division of G.B. Ltd.	4
A.M.D. Engineering Co. Ltd.	155
A.M.T. (Birmingham) Ltd.	40
Archdale, James & Co. Ltd.	67
Ashtead Engineering Co. Ltd.	160
Atkins, W. T. (Tottenham) Ltd.	163
Aurora Gearing Co. (Willmot North) Ltd.	151
Autoproductions Ltd.	158
Avenue Engineering Co., The	159
Aylesbury Turned Parts (True Screws) Ltd.	158

Ballinger, L. J. H. Ltd.	118
Barber & Colman Ltd.	Inside Back Cover
Baynes, Charles Ltd.	136
Bell, H. (Machine Tools) Ltd.	180
Benson Bond	144
Benton Engineering Co. Ltd.	156
Birfield Tools & Design Ltd.	138
Blaker Motor & Welding Co. Ltd., The	156
Bliss, E. W. (England) Ltd.	89
Bliss, G. H. Ltd.	124
Boneham & Turner Ltd.	124
Bowen Road Eng'g. Co. Ltd.	158
Braby, Fredk. & Co. Ltd.	158
Bristol Repetition Ltd.	160
British Ernato Corporation Ltd.	118
British Rawhide Belting Co. Ltd.	140
Brock, L. & T. I. & Co. Ltd.	157
Brockhouse, J. & Co. Ltd.	110
Broom & Wade Ltd.	42

Brown, David Corporation (Sales) Ltd., The	137
Brown's Engineering Works	157
Brown, F.	153
B.S.A. Tools Ltd.	93
B.T.R. Industries Ltd.	5
Buck & Hickman Ltd.	58
Buck & Ryan Ltd.	146
Buckingham, G. M. Ltd.	178
Burdett, G. W. S. & Co. Ltd.	123
Burton Griffiths & Co. Ltd.	93
Butcher, Henry & Co.	167 & 183
Butler Machine Tool Co. Ltd., The	Front Cover
Butterworth, A. & Co.	168
Butterworth British Automatic Machine Tool Co. Ltd.	125
Camdentools	162
Carder, R. E. Ltd.	153
Carne, Rudolph & Co. Ltd.	79
Cashmore, John Ltd.	170
Castle Engineering Co. (Nottingham) Ltd.	148
Catmur Machine Tool Corporation Ltd.	127
Centaur Tool Works Ltd.	169
Centec Machine Tools Ltd.	134
Central Engineers (Herne Hill) Ltd.	161
Chalwin, Thomas & Co.	132
Chetna Manufacturing Co. Ltd.	154
Clarkson (Engineers) Ltd.	81
Cohen, Geo. Sons & Co. Ltd.	177
Coventry Gauge & Tool Co. Ltd.	25
Coventry Grinders Ltd.	162
Croze Manufacturing Co. (1938) Ltd.	144
Croydon Tool & Case Hardening Specialists	156
Cuxson, Gerrard & Co. Ltd.	150
Davall Gear Co. Ltd., The	154
Davies-Charlton (U.K.) Ltd.	186
Davis, Stuart Ltd.	83
Dawson, Edward (Pumps) Ltd.	134
Dean, Smith & Grace Ltd.	23

Denfords Engineering Co. Ltd.	56
Desinex (Coventry) Ltd.	153
Diamond H Switches Ltd.	107
Dimco (Gt. Britain) Ltd.	168 & 182
Donovan Electrical Co. Ltd., The	164
Dorner & Wadsworth Ltd.	163
Dowling & Doll Ltd.	6, 7 & 136
Dowling, David Ltd.	148
Drayton Regulator & Instrument Co. Ltd.	138
Drew, L. A. & Co. Ltd.	141
Drummond-Asquith (Sales) Ltd.	102, 103 & 104
Dukes & Briggs Eng'g. Co. Ltd.	140
Eagle Milling Machine Co. Ltd.	155
Eclipse Foundry & Engineering Co. (Dudley) Ltd.	155
Economic Stampings Ltd.	161
Edmonton Tool & Eng'g. Co. Ltd.	161
Edwards, F. J. Ltd.	41, 132, 166, 168, 169, 178 & 180
Elgar Machine Tool Co. Ltd.	39
Elliott, B. (Machinery) Ltd.	33
Engineering Products Ltd.	151
Eng'g. & Scientific Equip., Ltd.	146
English Electric Co. Ltd., The	49
English Steel Tool Corp. Ltd.	59
Erma Ltd.	100
Evans, Fredk. W. Ltd.	159
Fawcett-Preston & Co.	94
Ferd, W. Klingelberg Sohne	45
Finucane, Wm. (Springs & Pressings) Ltd.	164
Firth, Thomas & John Brown Ltd.	29
Fischer Bearings Co. Ltd.	17
Flame Hardeners Ltd.	120
Fletcher, Miller Ltd.	76
Flexello Castors & Wheels Ltd.	130
Forrest, W. & Co. Ltd.	168
Fuller, Horsey, Sons & Cassell	143

(Continued on page 188)

When answering advertisements kindly mention MACHINERY.

INDEX TO ADVERTISERS—(continued from page 187)

	PAGE		PAGE		PAGE
G.A. Precision Products Ltd.	161	Martin Bros. (Machinery) Ltd.	172	Selson Machine Tool Co. Ltd., The	87
Gib Precision Ltd.	106	Martonair Ltd.	70	Seton Creaghe Engineering Ltd.	153, 165 & 158
Glacier Metal Co. Ltd., The	114	Mathews, Chas. E. (Machine Tools) Ltd.	171	Shardlow Micrometers Ltd.	38
Gouldier, J. & Sons Ltd.	105	Maun Industries Ltd.	152	Shaw, A. & Son (Diamonds) Ltd.	128
Gray, R. O.	177	Maurall Engineering Co.	154	Sheepbridge Alloy Castings Ltd.	108
G.R.M. Services Ltd.	155	Mek-Elek Engineering Ltd.	146	Sheffield Twist Drill & Steel Co. Ltd., The	92
Grosvenor Works (Holloway) Ltd.	163	Mercer, Thomas Ltd.	57	Shelmerdine & Mulley Ltd.	153
Gunn, D. A. (Eng'g.) Ltd.	160	Midland Machine Tool Co., The	166 & 178	Shouler & Son	57
		Millen, Edwin	165	Siemens-Schuckert (G.B.) Ltd.	188
Halifax Rack & Screw Cutting Co. Ltd.	130	Mills, George (Engineers) Ltd.	156	Silvafume Co. Ltd., The	86
Hallamshire Steel & File Co. Ltd., The	141	Milnes, Henry Ltd.	31	Simmonds Aeroaccessories Ltd.	115
Hallmac Tools Ltd.	135	Mitcham Jig & Press Tool Co. Ltd.	162	Simpson, P. & Co. Ltd.	182
Hammond Eng'g. Co. Ltd., The	164	Modern Machine Tools Ltd.	176	Slater (Tangents) Ltd.	26
Hardinge Machine Tools Ltd.	61	Moore Manufacturing Co. Ltd., The	101	Slingsby, Walter & Co. Ltd.	164
Hargreave, J. M. & Co. Ltd.	159	Moore & Wright (Sheffield) Ltd.	75	Smart & Brown (Machine Tools) Ltd.	43
Harper, John & Co. Ltd.	146	Morgan Crucible Co. Ltd., The	95	Smith, C. & B. Ltd.	112
Harrington, T. J. & Son Ltd.	157	Mortimer Engineering Co.	69, 139 & 150	Smith & Crabb	163
Harris, John (Tools) Ltd.	52	Moser Cams & Tools Ltd.	146	Smith & Netherwood Ltd.	154
Harrison, R. C. & Sons (Brassfounders) Ltd.	142	Munro, R. W. Ltd.	154	Smith Bros. & Webb Ltd.	12
Harrison, T. S. & Sons Ltd.	62			Soug Machine Tools Ltd.	44, 166, 174, 176 & 182
Harvey, G. A. & Co. (London) Ltd.	47			Southern Engineering & Machinery Co.	167
Heap, Joshua & Co. Ltd.	105	Nalish Bros. & Co. Ltd.	154	Southern Forge Ltd.	34
Heath, W. G. & Co. Ltd.	160	Nell, James & Co. (Sheffield) Ltd.	111	Spectra Chemicals Ltd.	96
Heliot Machine Tool Co.	168	Newall, Alexander S. Machine Tool Co. Ltd.	188	Speed Tools Ltd.	Inside Front Cover
Herbert, Alfred Ltd.	11 & 35	Newall Group Sales Ltd.	128	Stalker Drill Works Ltd., The	65
High Speed Service Tool Co. Ltd.	160 & 162	Newall Used Machine Division	168	Standwell Equipment Co. Ltd.	150
Hilnor Ltd.	128	Newman Industries Ltd.	167 & 173	Stedal Machine Tool Co.	55 & 183
Hobeco Tool Co.	145	Norman Eng'g. Co. Ltd.	157	Steelcraft Jig & Tool Co.	161
Hoffmann Manufacturing Co. Ltd., The	60	Norton, W. E. (Machine Tools) Ltd.	175	Stein Atkinson Vickers Hydraulics Ltd.	84
Holbrook Machine Tool Co. Ltd.	37	Novogage Ltd.	156	Stephens, R. & Son Ltd.	161
Holly Engineering (Drayton) Ltd.	161			Stevens & Bullivant Ltd.	119
Hopkinsons Ltd.	112	Osmond Eng'g. Co. Ltd., The	113	Straight & Vines Ltd.	170
Humphreys, J. H. & Sons Ltd.	142	Osborne, Samuel & Co. Ltd.	14 & 15	Stuart Heywood Eng'g.	160
Hunt, Herbert & Sons Ltd.	147	Otterway & Try Ltd. (Machinery)	174	Surplice & Tozer Engineering Co. Ltd.	158
Ideal Hardening Co. Ltd.	156			Surplus Machinery & Stores Clearing House Ltd.	177 & 181
Industrial Electric Co. Ltd.	117	Park Gate Iron & Steel Co. Ltd., The	129	Swissomatic Ltd.	160
		Parkes (Machine Tools) Ltd.	170, 179, 180, 182 & 186	Sykes Machine Tool Co. Ltd.	88
Jackman, Geo. Machine Tool Co. Ltd.	148				
Jacobs Manufacturing Co. Ltd.	24	Parkin, F. M. (Sheffield) Ltd.	32	Toolmakers of Andover (1932) Ltd.	159
Jay-Eff Flame Hardening Co., The	152	Pearson Panke Ltd.	181	Tool Machine Tool Co. Ltd.	181
J.B. Machine Tool Co. Ltd.	166 & 170	Pidgen Bros. Ltd.	179	Taylor, Charles (Birmingham) Ltd.	82
Jessop, William & Sons Ltd.	68	Pilot Plug Gauge Co. Ltd., The	51	Taylor, Geo. & Son (Engineers) Ltd.	110
Johansson, C. E. Ltd.	90	Polaroid Ltd.	161	Taylor Industrial Clutches	110
Jones, A. A. & Shipman Ltd.	110	Pollard, Fredk. & Co. Ltd.	48	Taylor Rustless Fittings Co. Ltd.	156
Jones, E. H. (Machine Tools) Ltd.	13, 166 & 180	Polts, N. E. (Birmingham) Ltd.	182	Tecalemit Ltd.	131
Joyce, C. H. Ltd.	122 & 177	P.R. Motors Ltd.	147	Teroy Ltd.	78
Kayser Ellison & Co. Ltd.	99	Pratt, Levick & Co. Ltd.	21	Toone, B. (Nottingham) Ltd.	156
Kelaville Rotary Pumps & Motors Ltd.	20	Pratt Precision Hydraulics Ltd.	Back Cover	Trevena & Glover Ltd.	161
Kemp Precision Tooling Ltd.	163	Precision Heating Ltd.	156		
Kemworthy Jig & Press Tool Co., The	163	Precision Products (Romford) Ltd.	153	Universal Ball Bearing Co.	164
K.E.N.T. Machinery & Engineering Co.	171	Precision Rubbers Ltd.	126	Urquhart, Wm.	3, 166, 169, 178 & 182
Kirk, Harry Eng'g. Ltd.	177	Preconomy Co. Ltd.	163		
		Pringle, Robert & Sons	153	Vaughan Associates Ltd.	16
Landen (Engineers) Ltd.	153	Radek Eng'g.	150	Vaughan Crane Co. Ltd., The	122
Lang, John & Sons Ltd.	10	Raistrick, J. E. Ltd.	166	Verrolec Ltd.	114
Lapointe Machine Tool Co. Ltd., The	133	Rawlplug Co. Ltd., The	Inside Back Cover	Victa Engineering Co.	120 & 142
Lattimer, E. R. Ltd.	158	Raybrook Precision Honing Co. Ltd.	30	Vulcan Mfg. (Wolverhampton) Ltd.	161
Lawrence, A. & Co. (Machine Tools) Ltd.	166 & 169	Redcar Engineering Co. Ltd.	159		
Layton, M. C. Ltd.	167	Reid Gear Co. Ltd., The	119	Wakelin, S. E. & Co. Ltd.	162
Lench, Thos. Wm. Ltd.	116	Renold Chains Ltd.	71	Ward, H. W. & Co. Ltd.	9
Leithaby, Wm. & Co. Ltd.	116	Revolving Centres Ltd.	118	Ward, Thos. W. Ltd.	166 & 172
Levy, B. & Co. (Patterns) Ltd.	156	Riley, Robert Ltd.	143	Wheley & Scott Ltd.	168
Lewis Henry, & Co.	183	Rockwell Machine Tool Co. Ltd.	64, 67 & 152	Weller & Co.	183
Leyton Engineering Co. Ltd.	160	Rocol Ltd.	66	Western Machine Tools (Swansea) Ltd.	172
Leytonstone Jig & Tool Co. Ltd.	Inside Front Cover	Rodgers Bros. Ltd.	150	Wharton & Wilcocks Ltd.	109
Lindley, C. & Co. Ltd.	120	Rosser & Russell Ltd.	158	Whiteley, Wm. & Sons Ltd.	28
Litton's Machine Tool Co. Ltd.	171	Roth, L.	182	Whitlam & Co.	164
Lloyd, Richard Ltd.	8	Rubert & Co. Ltd.	139	Wickman Ltd.	16 & 77
Lumsden Machine Co. Ltd.	36	Ryder, Thomas & Son Ltd.	27	Widdowson, Herbert & Sons Ltd.	167 & 174
		Rye, Claude Bearings	164 & 165	Wigsworth, Frank & Co. Ltd.	142
MacDowall Equipment Co. Ltd.	162			Wild-Bartfield Electric Furnaces Ltd.	1
MacEchern & Co. Ltd.	165	Sanders, H. G. & Son Ltd.	161	Williams & Hiffe Ltd.	153
Machine Shop Equipment Ltd.	97 & 152	Sanderson Instruments (Huddersfield) Ltd.	91	Williams, H. & Son Ltd.	187
Machinery Publishing Co. Ltd., The	149	Sandiacre Screw Co. Ltd., The	106	Windle Bros. Ltd.	50
Macready's Metal Co. Ltd.	54	Scaife, Robert (Coine) Ltd.	108	Worcester Royal Porcelain Co. Ltd., The	121
Manifold Machinery Co. Ltd.	159	Schrader's Son, A.	98	Worsen Die Cushions Ltd.	144
Marbair, Gaston E. Ltd.	72 & 74	Scialky Electric Welding Machines Ltd.	22		
Marbair Industries Ltd.	73			Zephyr Engineers Ltd.	157
Marsden & Shiers Ltd.	160				
Martin, Arthur (Milling Cutters) Ltd.	137				

ROCH-ETALON STAINLESS STEEL PRECISION MEASURING INSTRUMENTS

ARE THE BEST—STAY THE BEST

SOLE IMPORTERS ALEXANDER S. NEWALL MACHINE TOOL CO. LTD.

Telegrams
ETALON LONDON N.W.3.

287 FINCHLEY ROAD, LONDON, N.W.3.

Telephone
HAMPSTEAD 3855/9949

When answering advertisements kindly mention MACHINERY.

BARBER-COLMAN

HOBBIING MACHINES

Hob sharpening machines
and Hobs

★ A Hobbing service with over
40 years' experience behind it

We illustrate the Barber-Colman Combination
Sharpening Machine for sharpening reamers, hobs
and milling cutters.

The machine shaves irregularly spaced flutes,
grinds and sets dry. Controls flute spacing and
lead of hobs.

Handles short leads and small diameters. Con-
trols diameter size and profile. Reproduces
desired cutting and relief clearance.


Ask for full particulars



BARBER & COLMAN LTD.
BROOKLANDS SALE CHESHIRE
Phone: SALE 2277 (PBX) Grams & Cables BARCOL, SALE

RAWLBOLTS LIFT 5-TON BOULDERS

We are indebted to
Messrs. George
Wimpey & Co.
Ltd., the Building
and Civil
Engineering
Contractors, for
the information.
The photograph
was kindly provided
by Mr. Howarth
from the North
Point Generating
Station, Hong Kong.



When wire slinging fails, how do
you excavate round granite
boulders, weighing five tons or
more each, from a pit 12ft. square
and 20ft. deep?

That was the problem in Hong
Kong. It was solved by drilling
the granite to take a "K" size
Rawlbolt fitted with a 1in. diameter
eyebolt. Says Mr. A. C. Howarth,
M.I.C. Project Manager—"This
device proved invaluable and
lifted boulders up to five tons in
weight, even though there was
considerable extra load due to
suction when we were getting
down to the sandbed."

It is this tremendous grip of
Rawlbolts that ensures safety in
any bolt-fixing job, large or small.

RAWLBOLTS

For Speed and Strength!



THE RAWLPLUG CO. LTD.


CROMWELL RD., LONDON, S.W.7

581

Published by THE MACHINERY PUBLISHING CO., LTD., at their Office, Clifton House, 83-117, Euston Rd., London, N.W.1. Telephone Euston 8441.
LONDON: HARRISON & SONS, LTD., by Appointment to Her Majesty The Queen, Printers, London, Hayes (Middx.) and High Wycombe.

MACHINERY, JUNE 13, 1958

PRATT CHUCKS



hydraulic cylinders

Rotary Hydraulic Cylinders in a range of sizes for operation up to the highest speeds, suitable for equipping all classes of Automatic and Turret Lathes.

A complete range of Hydraulic Control Gear is available.

PRATT PRECISION HYDRAULICS LTD.,
CRAVEN EDGE WORKS · HALIFAX · ENGLAND

